



DRILL STEM TEST REPORT

**BJ SERVICE DIVISION
BORG-WARNER (CANADA) LIMITED**

CANDEL MOBIL ET AL IROQUOIS

I-11

TEST NO. 3



DRILL-STEM TEST DATA

Well Name **CANDEL ET AL IROQUOIS I-11**Test No. **3**Well Number **I-11**Zone Tested **RONNING**Company **CANDEL OIL LTD.**Interval **3200.0 TO 3614.0**Comp. Rep. **DOUG HADDOW**Tester **LEO PENNER**Date **MAY 31, 1972**Type of Test **DUAL BOTTOM HOLE**RFS Tool No. **105**Preflow **5.0** mins. ISI **27.0** mins. Flow **114.0** mins. FSI **230.0** mins.

	OUT REC. No. 3852		OUT REC. No. 3689		REC. No.	
	5800	RANGE 12 HR. CLOCK	5700	RANGE 12 HR. CLOCK	RANGE	HR. CLOCK
DEPTH		3219.0		3225.0		
Initial Hydro Mud Press		1704.0		1707.0		
Initial Shut In Press		1359.0		1361.9		
Initial Flow Press		622.0		625.5		
Final Flow Press		1364.0		1367.6		
Final Shut-In Press		1368.0		1371.8		
Final Hydro Mud Press		1704.0		1707.0		

Mud Drop **YES**Viscosity **29.0**

Fluid Loss

Temperature °F **68.0**Mud Weight **10.3**Net Pay Tested **130.0**Top Packer Depth **3200.0**

Bottom Packer Depth

Total Depth **3614.0**Drill Pipe Size **3.5 IF**Wt. **13.5**Drill Collar I.D. **2.375**Ft. Run **450.00**Surface Choke Size **CLOSED**Bottom Choke Size **0.5**Main Hole Size **8.750**Anchor Size **4.75**

Rat Hole Size

Feet of Rat Hole

Cushion Amount

Type

Rubber Size **7.5**Fluid Recovery Total Feet **2820.0**Recovered Feet of **RFS CONT. 2700 CC'S OF CLEAN SALT WATER**

Recovered Feet of

Recovered Feet of

Recovered Feet of

Recovered Feet of

Gas Recovery How Measured

Riser size:

mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day

Bleed Off Time for Drill Pipe

REMARKS: **PULL TEST UNTIL REACHED TOP OF FLUID RECOVERY. CAUGHT SAMPLE OF MUD THEN WHEN WE CONTINUED PULLING OUT OF THE HOLE THE PIPE WAS EMPTY. OUR TOOL HAS A PUMP-OFF FEATURE IN CASE IT IS NEEDED FOR FREEING THE PIPE WHEN STUCK THAT IS ACTIVATED BY APPLYING 500 PSI DIFFERENTIAL TO THE DRILL PIPE**



DRILL-STEM TEST DATA

Well Name **CANDEL ET AL IROQUOIS I-11**Test No. **3**Well Number **I-11**Zone Tested **RONNING**Company **CANDEL OIL LTD**Interval **3200.0 TO 3614.0**Comp. Rep. **DOUG HADDOW**Tester **LEO PENNER**Date **MAY 31, 1972**

Type of Test

RFS Tool No.

Preflow	mins.	ISI	mins.	Flow	mins.	FSI	mins.		
DEPTH	REC. No.	RANGE	HR. CLOCK	REC. No.	RANGE	HR. CLOCK	REC. No.	RANGE	HR. CLOCK
Initial Hydro Mud Press									
Initial Shut In Press									
Initial Flow Press									
Final Flow Press									
Final Shut-In Press									
Final Hydro Mud Press									

Mud Drop

Fluid Loss

Mud Weight

Viscosity

Temperature °F

Net Pay Tested

Top Packer Depth

Bottom Packer Depth

Total Depth

Drill Pipe Size

Wt.

Drill Collar I.D.

Ft. Run

Surface Choke Size

Bottom Choke Size

Main Hole Size

Anchor Size

Rat Hole Size

Feet of Rat Hole

Cushion Amount

Type

Rubber Size

Fluid Recovery Total Feet

Recovered Feet of

Recovered Feet of

Recovered Feet of

Recovered Feet of

Recovered Feet of

Gas Recovery How Measured

Riser size:

mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day

Bleed Off Time for Drill Pipe

REMARKS: **ALLOWING YOU TO CIRCULATE OR PRESSURE UP UNDER THE PACKERS.
THE SAME RESULTS OCCUR IF THE HOLE IS NOT KEPT FULL WHILE
PULLING TEST - THE RECOVERY OVERBALANCES THE ANNULUS
PRESSURE BY 500 PSI.**




TESTING REPORT

WEIGHT INDICATOR READING
PRIOR TO SETTING PACKERS
AFTER PULL PACKERS LOOSE



	ID	OD	LENGTH	
4S LANDING SUB				
4S CHAMBER				
4S TOOL OR P.O. SUB			1.00	
CO SUB			1.00	
SHUT IN TOOL		4%	5.00	
R.F.S. No. 105	2 1/4	4%	3.25	
R.F.S. No.	2 1/4	4%		
HYDRAULIC TOOL		4%	7.00	
JARS	1	4%	5.30	
RECORDER No.	2 1/4	4%		DEPTH
RECORDER No.	2 1/4	4%		DEPTH
SAFETY JOINT	2 11/16	4%	1.75	
BY PASS SUB	1 5/32	4%		
1. PACKER DEPTH 3194	PACKER	1 OR 3/4	7 1/2	6.00
2. PACKER DEPTH 3200	PACKER	1 OR 3/4	7 1/2	5.00
	ANCHOR—SPECIFY	2 1/2	1.00	TOOL ABOVE INTERVAL 35.30
	PERFS		17.00	
	BLANK OFF OR BY PASS SUB	1 5/32	4%	
	RECORDER No. 3852	2 1/4	4%	6.00 DEPTH 3219
3. PACKER DEPTH	PACKER	1 OR 3/4		TOTAL INTERVAL 413.50
4. PACKER DEPTH	PACKER	1 OR 3/4		
	ANCHOR—SPECIFY	2 1/2		
	DRILL PIPE	3 1/2 IF	377.00	
	RECORDER No. 3689	2 1/4	4%	5.00 DEPTH 3225
	PERFS		5.00	
TOTAL DEPTH 3614	BULLNOSE	2 1/4	4%	2.50
				TOTAL TAIL PIPE
				TOTAL TEST TOOL 71.80

DST CHARTS FOR COMPARATIVE VISUAL ANALYSIS





WELL NAME CANDEL ET AL IROQUOIS I-11

DST. NO. 3

LOCATION I-11

REC. NO. 3689

DEPTH 3225.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
RUN IN HOLE	1	0.0	0.0
	2	81.0	1707.0
INITIAL HYDRO PRESSURE	3	107.0	1707.0
INITIAL PREFLOW PRESSURE	4	107.0	525.7
FINAL PREFLOW PRESSURE	5	112.0	575.7
START INITIAL SHUT-IN	6	112.0	575.7
	7	113.0	1332.4
	8	117.0	1357.7
	9	122.0	1359.1
	10	127.0	1360.5
	11	132.0	1360.5
	12	137.0	1361.9
INITIAL SHUT-IN PRESSURE	13	139.0	1361.9
START FLOW PERIOD	14	139.0	1361.9
INITIAL FLOW PRESSURE	15	140.0	625.5
	16	144.0	729.4
	17	149.0	846.1
	18	154.0	941.5
	19	159.0	1025.5
	20	164.0	1096.7
	21	169.0	1160.5
	22	174.0	1204.2
	23	179.0	1239.4
	24	184.0	1269.0
	25	189.0	1294.3
	26	194.0	1314.0
	27	199.0	1329.5
	28	204.0	1340.8
	29	209.0	1350.7
	30	214.0	1356.3
	31	219.0	1360.5
	32	224.0	1361.9
	33	229.0	1363.3
	34	234.0	1364.8
	35	239.0	1366.2



WELL NAME CANDEL ET AL IROQUOIS I-11

DST. NO. 3

LOCATION I-11


REC. NO. 3689

DEPTH 3225.


MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
	36	244.0	1366.2
	37	249.0	1366.2
FINAL FLOW PRESSURE	38	253.0	1367.6
START FINAL SHUT-IN	39	253.0	1367.6
	40	258.0	1367.6
	41	263.0	1367.6
	42	273.0	1367.6
	43	283.0	1367.6
	44	293.0	1367.6
	45	303.0	1367.6
	46	313.0	1369.0
	47	323.0	1369.0
	48	333.0	1369.0
	49	343.0	1369.0
	50	353.0	1369.0
	51	363.0	1369.0
	52	373.0	1369.0
	53	383.0	1370.4
	54	393.0	1370.4
	55	403.0	1370.4
	56	413.0	1370.4
	57	423.0	1370.4
	58	433.0	1370.4
	59	443.0	1371.8
	60	453.0	1371.8
	61	463.0	1371.8
	62	473.0	1371.8
FINAL SHUT IN PRESSURE	63	483.0	1371.8
RUN OUT OF HOLE	64	483.0	1371.8
FINAL HYDRO PRESSURE	65	484.0	1707.0
	66	497.0	1707.0
OUT OF HOLE	67	572.0	0.0

PRESSURE VS. TIME
 CANDEL ET AL IR000015 I-11
 I-11
 DST NO. 3 REC. NO.3689




CANDEL MOBIL ET AL IROQUOIS I-11
INTERVAL 3200 - 3614
DST NO. 3 REC. NO. 3852



DST RECORDER CHARTS

CANDEL MOBIL ET AL IROQUOIS I-11
INTERVAL 3200 - 3614
DST NO. 3 REC. NO. 3689





DRILL STEM TEST REPORT

**BJ SERVICE DIVISION
BORG-WARNER (CANADA) LIMITED**

CANDEL MOBIL ET AL

IROQUOIS I-11

TEST NO. 2



DRILL-STEM TEST DATA

Well Name	CANDEL MOBIL ET AL INDIAN 1-11	Test No.	2
Well Number	1-11	Zone Tested	RONNING
Company	CANDEL OIL LTD.	Interval	2121.0 TO 2261.0
Comp. Rep.	M. MILLER	Tester	MEL MOSCRIPT
		Date	MAY 5, 1972

Type of Test **DUAL BOTTOM HOLE**RFS Tool No. **124**Prelow **5.0** mins. ISI **27.0** mins. Flow **60.0** mins. FSI **60.0** mins.

	IN REC. No. 5773		OUT REC. No. 5979		REC. No.					
	1150	RANGE	12	HR. CLOCK	1200	RANGE	12	HR. CLOCK	RANGE	HR. CLOCK
DEPTH										
Initial Hydro Mud Press			2104.0				2138.0			
Initial Shut-In Press			904.5				924.3			
Initial Flow Press			874.7				891.7			
Final Flow Press			162.0				181.7			
Final Shut-In Press			594.2				614.1			
Final Hydro Mud Press			875.5				892.3			
			904.5				924.3			

Mud Drop **10**
Viscosity **28.0**
Top Packer Depth **2115.0**
Drill Pipe Size **3.5 IF**
Surface Choke Size **CLOSED**
Anchor Size
Cushion Amount
Fluid Recovery Total Feet **1300.0**
Recovered **90** Feet of **FRESH WATER**
Recovered **1210** Feet of **SULPHUROUS FRESH WATER**
Recovered
Recovered
Recovered
Recovered

Fluid Loss
Temperature °F **84.0**
Bottom Packer Depth
Wt. **13.0**
Bottom Choke Size
Rat Hole Size
Type

Mud Weight **8.4**
Net Pay Tested **90.0**
Total Depth **2261.0**
Ft. Run **447.00**
Main Hole Size **8.750**
Feet of Rat Hole
Rubber Size **8.0**

Drill Collar I.D. **2.875**
Bottom Choke Size **0.5**

Gas Recovery	How Measured	Riser size:
mins.	Temp. °F Press Rdg. psi Orifice Size	= MCF/Day
mins.	Temp. °F Press Rdg. psi Orifice Size	= MCF/Day
mins.	Temp. °F Press Rdg. psi Orifice Size	= MCF/Day
mins.	Temp. °F Press Rdg. psi Orifice Size	= MCF/Day
mins.	Temp. °F Press Rdg. psi Orifice Size	= MCF/Day
mins.	Temp. °F Press Rdg. psi Orifice Size	= MCF/Day

Bleed Off Time for Drill Pipe

REMARKS: **WEAK INITIAL PUFF. WEAK AIR BLOW DECREASING THROUGHOUT TEST.**









TESTING REPORT

WEIGHT INDICATOR READING
PRIOR TO SETTING PACKERS
AFTER PULL PACKERS LOOSE

	ID	OD	LENGTH	
45 LANDING SUB				
45 CHAMBER COS			1.00	
45 TOOL OR P.O. SUB			5.00	
CO SUB				
SHUT IN TOOL		4 3/4	5.20	
R.F.S. No. 134	2 1/4	4 3/4	3.30	
R.F.S. No.	2 1/4	4 3/4		
HYDRAULIC TOOL		4 3/4	7.20	
JARS	1	4 3/4	6.00	
RECORDER No. 5773	2 1/4	4 3/4	5.00	DEPTH 2104
RECORDER No.	2 1/4	4 3/4		DEPTH
SAFETY JOINT	2 11/16	4 3/4	1.75	
BY PASS SUB	1 5/32	4 3/4		
1. PACKER DEPTH 2115	PACKER	1 OR 3/4	6.00	
2. PACKER DEPTH 2121	PACKER	1 OR 3/4	5.00	TOOL ABOVE INTERVAL 45.45
	ANCHOR—SPECIFY	2 1/2	1.00	
	PERF		15.00	
	BLANK OFF OR BY PASS SUB	1 5/32	4 3/4	
	RECORDER No. 5979	2 1/4	5.00	DEPTH 2138
3. PACKER DEPTH	PACKER	1 OR 3/4		TOTAL INTERVAL
4. PACKER DEPTH	PACKER	1 OR 3/4		
	ANCHOR—SPECIFY	2 1/2		
	RECORDER No.	2 1/4	4 3/4	DEPTH
	DRILL COLLARS		116.50	
TOTAL DEPTH 22.61	BULLNOSE	2 3/4	4 3/4	2.50
				TOTAL TAIL PIPE 140.00
				TOTAL TEST TOOL 68.95

DST CHARTS FOR COMPARATIVE VISUAL ANALYSIS

HIGH PERMEABILITY
STRONG DAMAGE EFFECTHIGH PERMEABILITY
NO DAMAGE EFFECTMEDIUM PERMEABILITY
STRONG DAMAGE EFFECTMEDIUM PERMEABILITY
NO DAMAGE EFFECTLOW PERMEABILITY
STRONG DAMAGE EFFECTLOW PERMEABILITY
NO DAMAGE EFFECT



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 5979

DEPTH 2138.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
RUN IN HQLE	1	0.0	0.0
	2	93.0	924.3
INITIAL HYDRO PRESSURE	3	124.0	924.3
INITIAL PREFLOW PRESSURE	4	124.0	94.6
FINAL PREFLOW PRESSURE	5	129.0	126.8
START INITIAL SHUT-IN	6	129.0	126.8
	7	134.0	822.5
	8	139.0	873.5
	9	144.0	886.5
	10	149.0	889.8
	11	154.0	891.4
INITIAL SHUT-IN PRESSURE	12	156.0	891.7
START FLOW PERIOD	13	156.0	891.7
INITIAL FLOW PRESSURE	14	157.0	181.7
	15	161.0	214.0
	16	166.0	265.2
	17	171.0	312.5
	18	176.0	355.2
	19	181.0	395.7
	20	186.0	433.6
	21	191.0	467.9
	22	196.0	501.2
	23	201.0	533.3
	24	206.0	563.0
	25	211.0	592.0
FINAL FLOW PRESSURE	26	216.0	614.1
START FINAL SHUT-IN	27	216.0	614.1
	28	221.0	837.5
	29	226.0	871.4
	30	231.0	882.8
	31	236.0	887.4
	32	241.0	889.5
	33	246.0	890.8



WELL NAME CANDEL MOBIL ET AL IROQUOIS 1-11

DST. NO. 2

LOCATION 1-11

REC. NO. 5979

DEPTH 2138.

MEASURED PRESSURES

	POINT NUMBER -----	TIME MIN -----	PRESSURE PSIG -----
	34	251.0	891.4
	35	256.0	891.7
	36	261.0	892.0
	37	266.0	892.3
	38	271.0	892.3
FINAL SHUT-IN PRESSURE	39	276.0	892.3
RUN OUT OF HOLE	40	276.0	892.3
FINAL HYDRO PRESSURE	41	277.0	924.3
	42	289.0	924.3
OUT OF HOLE	43	366.0	0.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11 DST. NO. 2
LOCATION I-11 REC. NO. 5979 DEPTH 2138.

CALCULATIONS FOR LIQUID RECOVERY (FIRST SHUT-IN)
=====

(A) EXTRAPOLATED RESERVOIR PRESSURE	899.5
NO. OF POINTS CONSIDERED IN BUILD-UP	6
NO. OF POINTS USED IN EXTRAPOLATION	4
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI).....	0.21
EFFECTIVE PRODUCING TIME (MIN)	5.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS 1-11

DST. NO. 2

LOCATION 1-11

REC. NO. 5979

DEPTH 2138.

DATA FOR BUILD-UP PLOT (FIRST SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------

PORTION OF BUILD-UP CURVE NOT USED IN EXTRAPOLATION

7	5.0	822.5			2.00
8	10.0	873.5			1.50

POINTS USED IN EXTRAPOLATION

9	15.0	886.5	886.6	0.2	1.33
10	20.0	889.8	889.5	-0.3	1.25
11	25.0	891.4	891.3	-0.0	1.20
12	27.0	891.7	891.9	0.2	1.19



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11 DST. NO. 2
LOCATION I-11 REC. NO. 5979 DEPTH 2138.

CALCULATIONS FOR LIQUID RECOVERY (SECOND SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE 895.3
NO. OF POINTS CONSIDERED IN BUILD-UP 12
NO. OF POINTS USED IN EXTRAPOLATION 7
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI) 0.13
EFFECTIVE PRODUCING TIME (MIN) 65.0

(B) IN SITU CAPACITY (KH - MD FT) 3341.91
SLOPE OF BUILD-UP CURVE (PSI/CYCLE) 8.76
PRODUCING RATE (BBL/DAY) 219.78
FLUID VISCOSITY (CP) 0.820
FORMATION VOLUME FACTOR (RES BBL/ST BBL) 1.000

(C) EFFECTIVE PERMEABILITY (MD) 37.13
FORMATION THICKNESS 90.00

(D) PRODUCTIVITY INDEX (BBL/DAY/PSI) 0.78
FLOWING PRESSURE (PSIG) 614.1

(E) APPROXIMATE DRAINAGE RADIUS (FT) 267.3
TOTAL FLOWING TIME (MIN) 65.0

(F) ESTIMATED DAMAGE RATIO 5.86
RESERVOIR POROSITY (PERCENT) 9.00
TOTAL COMPRESSIBILITY (VOL/VOL/PSI X 10⁻⁶) 8.00
WELL-BORE RADIUS (IN) 4.375
CALCULATED SKIN FACTOR 30.63

(G) PRODUCTION WITH DAMAGE REMOVED (BBL/DAY) 1287.2



WELL NAME CANDEL MOBIL ET AL IROQUOIS 1-11

DST. NO. 2

LOCATION 1-11

REC. NO. 5979

DEPTH 2138.

DATA FOR BUILD-UP PLOT (SECOND SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------

PORTION OF BUILD-UP CURVE NOT USED IN EXTRAPOLATION

28	5.0	837.5			14.00
29	10.0	871.4			7.50
30	15.0	882.8			5.33
31	20.0	887.4			4.29
32	25.0	889.5			3.60


POINTS USED IN EXTRAPOLATION

33	30.0	890.8	890.9	0.2	3.17
34	35.0	891.4	891.3	-0.1	2.86
35	40.0	891.7	891.6	-0.1	2.62
36	45.0	892.0	891.9	-0.1	2.44
37	50.0	892.3	892.1	-0.2	2.30
38	55.0	892.3	892.3	0.0	2.18
39	60.0	892.3	892.5	0.2	2.08

ASSUMPTIONS AND LIMITATIONS

THE ENCLOSED DST INTERPRETATION CALCULATIONS REQUIRE SEVERAL NECESSARY ASSUMPTIONS TO PROVIDE A QUICK ESTIMATE OF MANY OF THE FACTORS INVOLVED. AS A RESULT THE INFORMATION GAINED SHOULD BE USED TO FORM AN OPINION OR ESTIMATE ONLY, UNTIL THE ASSUMPTIONS OF RESERVOIR AND FLUID PROPERTIES CAN BE WHOLLY OR PARTIALLY CLARIFIED BY MORE COMPLETE ANALYSIS AND TESTING.

PRESSURE VS. TIME
 CANDEL MOBIL ET AL IROQUOIS I-11
 I-11
 DST NO. 2 REC. NO. 5979



915.0

900.0

885.0

870.0

855.0


840.0

825.0

810.0

BOTTOM - HOLE PRESSURE (psig)


HORNER PRES. EXTRAPOLATION
CANDEL MOBIL ET AL IRROQUOIS I-11
I-11
DST NO. 2 P_w = 895.3



$(T + \Delta t) / \Delta t$


100

CANDEL MOBIL ET AL IROQUOIS I-11
 INTERVAL 2121 - 2261
 DST NO. 2 REC. NO. 5773



DST RECORDER CHARTS

CANDEL MOBIL ET AL IROQUOIS I-11
 INTERVAL 2121 - 2261
 DST NO. 2 REC. NO. 5979





DRILL STEM TEST REPORT

**BJ SERVICE DIVISION
BORG-WARNER (CANADA) LIMITED**

CANDEL MOBIL ET AL

IROQUOIS I-11

TEST NO. 1



DRILL-STEM TEST DATA

Well Name CANDEL MOBIL ET AL IROQUOIS I-11 Test No. 1
Well Number I-11 Zone Tested BEAR ROCK
Company CANDEL OIL CO. Interval 900.0 TO 1010.0
Comp. Rep. H. MARTINOFF Tester MEL MOSCRIP Date MAY 2, 1972

Type of Test DUAL BOTTOM HOLE

RFS Tool No. 29

Prewlow 5.0 mins. ISI 57.0 mins. Flow 84.0 mins. FSI 85.0 mins.

	IN REC. No. 5773	OUT REC. No. 5979	REC. No.	
	1150 RANGE 12 HR. CLOCK	1200 RANGE 24 HR. CLOCK	RANGE	HR. CLOCK
DEPTH				
Initial Hydro Mud Press	883.0	917.0		
Initial Shut-In Press	377.3	396.0		
Initial Flow Press	346.8	363.7		
Final Flow Press	51.5	69.1		
Final Shut-In Press	311.2	329.6		
Final Hydro Mud Press	346.0	363.1		
	377.3	396.0		

Mud Drop NIL

Fluid Loss

Mud Weight 8.4

Viscosity 27.0

Temperature °F 80.0

Net Pay Tested 30.0

Top Packer Depth 894.0

Bottom Packer Depth 900.0

Total Depth 1010.0

Drill Pipe Size 3.5 IF

Wt 13.0 Drill Collar I.D. 2.750

Ft. Run 443.61

Surface Choke Size

Bottom Choke Size 0.5

Main Hole Size 8.750

Anchor Size 4.75

Rat Hole Size

Feet of Rat Hole

Cushion Amount

Type

Rubber Size 7.5 X 2

Fluid Recovery Total Feet 890.0

Recovered 90 Feet of FRESH WATER

Recovered 800 Feet of SULPHURIC FRESH WATER

Recovered Feet of

Recovered Feet of

Recovered Feet of

Gas Recovery How Measured

Riser size:

mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day

Bleed Off Time for Drill Pipe







REMARKS: VERY WEAK INITIAL PUFF. WEAK AIR BLOW DYING IN 15 MIN.



TESTING REPORT

	ID	OD	LENGTH
45 LANDING SUB			
45 CHAMBER COS			1.00
45 TOOL OR P.O. SUB			6.00
CO SUB			
SHUT IN TOOL		4%	5.20
R.F.S. No.	2 1/4	4%	3.30
R.F.S. No.	2 1/4	4%	
HYDRAULIC TOOL		4%	7.20
JARS	1	4%	6.00
RECORDER No. 5773	2 1/4	4%	5.00 DEPTH 883
RECORDER No.	2 1/4	4%	DEPTH
SAFETY JOINT	2 11/16	4%	1.75
BY PASS SUB	1 5/32	4%	
1. PACKER DEPTH 894	1 OR 3/4		6.00
2. PACKER DEPTH 900	1 OR 3/4		5.00 TOOL ABOVE INTERVAL 46.45
	2 1/4		1.00
			15.00
	1 5/32	4%	
BLANK OFF OR BY PASS SUB	2 1/4	4%	5.00 DEPTH 917
RECORDER No. 5979			
3. PACKER DEPTH	1 OR 3/4		TOTAL INTERVAL
4. PACKER DEPTH	1 OR 3/4		
	2 1/4		
ANCHOR—SPECIFY			
DR. COLLARS			86.72
RECORDER No.	2 1/4	4%	DEPTH
TOTAL DEPTH 1010	2 1/4	4%	2.50 TOTAL TAIL PIPE 110.22
			TOTAL TEST TOOL 69.95

DST CHARTS FOR COMPARATIVE VISUAL ANALYSIS

HIGH PERMEABILITY
STRONG DAMAGE EFFECTHIGH PERMEABILITY
NO DAMAGE EFFECTMEDIUM PERMEABILITY
STRONG DAMAGE EFFECTMEDIUM PERMEABILITY
NO DAMAGE EFFECTLOW PERMEABILITY
STRONG DAMAGE EFFECTLOW PERMEABILITY
NO DAMAGE EFFECT



WELL NAME CANDEL MOBIL ET AL IRCQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
RUN IN HOLE	1	0.0	0.0
	2	34.0	377.3
INITIAL HYDRO PRESSURE	3	84.0	377.3
INITIAL PREFLOW PRESSURE	4	84.0	16.4
FINAL PREFLOW PRESSURE	5	89.0	36.8
START INITIAL SHUT-IN	6	89.0	36.8
	7	90.0	341.4
	8	94.0	343.7
	9	99.0	345.1
	10	104.0	346.0
	11	109.0	346.3
	12	114.0	346.6
	13	119.0	346.6
	14	124.0	346.6
	15	129.0	346.6
	16	134.0	346.6
	17	139.0	346.8
	18	144.0	346.8
INITIAL SHUT-IN PRESSURE	19	146.0	346.8
START FLOW PERIOD	20	146.0	346.8
INITIAL FLOW PRESSURE	21	147.0	51.5
	22	151.0	66.4
	23	156.0	90.1
	24	161.0	111.7
	25	164.0	119.9
	26	165.0	379.3
	27	166.0	379.3
	28	167.0	228.2
	29	171.0	239.7
	30	176.0	249.1
	31	181.0	257.8
	32	186.0	265.8
	33	191.0	272.7
	34	196.0	279.3
	35	201.0	285.1



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
	36	206.0	290.5
	37	211.0	295.7
	38	216.0	300.3
	39	221.0	304.6
	40	226.0	308.3
FINAL FLOW PRESSURE	41	230.0	311.2
START FINAL SHUT-IN	42	230.0	311.2
	43	231.0	342.0
	44	235.0	343.4
	45	240.0	344.5
	46	245.0	344.8
	47	250.0	344.8
	48	255.0	345.1
	49	260.0	345.1
	50	265.0	345.1
	51	270.0	345.4
	52	275.0	345.4
	53	280.0	345.4
	54	285.0	345.4
	55	290.0	345.4
	56	295.0	345.4
	57	300.0	345.7
	58	305.0	345.7
	59	310.0	345.7
FINAL SHUT-IN PRESSURE	60	315.0	346.0
RUN OUT OF HOLE	61	315.0	346.0
FINAL HYDRO PRESSURE	62	316.0	377.3
	63	320.0	377.3
OUT OF HOLE	64	365.0	0.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

CALCULATIONS FOR LIQUID RECOVERY (FIRST SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE	347.3
NO. OF POINTS CONSIDERED IN BUILD-UP	13
NO. OF POINTS USED IN EXTRAPOLATION	12
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI).....	0.11
EFFECTIVE PRODUCING TIME (MIN)	5.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

DATA FOR BUILD-UP PLOT (FIRST SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------

PORTION OF BUILD-UP CURVE NOT USED IN EXTRAPOLATION

7	1.0	341.4			6.00
---	-----	-------	--	--	------

POINTS USED IN EXTRAPOLATION

8	5.0	343.7	343.7	0.1	2.00
9	10.0	345.1	345.2	0.1	1.50
10	15.0	346.0	345.8	-0.2	1.33
11	20.0	346.3	346.1	-0.1	1.25
12	25.0	346.6	346.4	-0.2	1.20
13	30.0	346.6	346.5	-0.1	1.17
14	35.0	346.6	346.6	0.1	1.14
15	40.0	346.6	346.7	0.1	1.12
16	45.0	346.6	346.8	0.2	1.11
17	50.0	346.8	346.8	-0.0	1.10
18	55.0	346.8	346.8	0.0	1.09
19	57.0	346.8	346.9	0.0	1.09



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11 DST. NO. 1
LOCATION I-11 REC. NO. 5773 DEPTH 883.

CALCULATIONS FOR LIQUID RECOVERY (SECOND SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE 346.5
NO. OF POINTS CONSIDERED IN BUILD-UP 18
NO. OF POINTS USED IN EXTRAPOLATION 18
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI)..... 0.15
EFFECTIVE PRODUCING TIME (MIN) 89.0

(B) IN SITU CAPACITY (KH - MD FT) 6570.75
SLOPE OF BUILD-UP CURVE (PSI/CYCLE) 2.26
PRODUCING RATE (BBL/DAY) 106.34
FLUID VISCOSITY (CP) 0.860
FORMATION VOLUME FACTOR (RES BBL/ST BBL)..... 1.000

(C) EFFECTIVE PERMEABILITY (MD) 219.02
FORMATION THICKNESS 30.00

(D) PRODUCTIVITY INDEX (BBL/DAY/PSI) 3.02
FLOWING PRESSURE (PSIG) 311.2

(E) APPROXIMATE DRAINAGE RADIUS (FT) 856.4
TOTAL FLOWING TIME (MIN) 89.0

(F) ESTIMATED DAMAGE RATIO 2.40
RESERVOIR POROSITY (PERCENT) 6.00
TOTAL COMPRESSIBILITY (VOL/VOL/PSI X 10-6) 9.00
WELL-BORE RADIUS (IN) 4.375
CALCULATED SKIN FACTOR 10.47

(G) PRODUCTION WITH DAMAGE REMOVED (BBL/DAY) 255.4



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

DATA FOR BUILD-UP PLOT (SECOND SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------


POINTS USED IN EXTRAPOLATION

43	1.0	342.0	342.1	0.1	90.00
44	5.0	343.4	343.6	0.2	18.80
45	10.0	344.5	344.2	-0.3	9.90
46	15.0	344.8	344.6	-0.3	6.93
47	20.0	344.8	344.8	-0.0	5.45
48	25.0	345.1	345.0	-0.1	4.56
49	30.0	345.1	345.1	0.0	3.97
50	35.0	345.1	345.2	0.1	3.54
51	40.0	345.4	345.3	-0.1	3.22
52	45.0	345.4	345.4	-0.0	2.98
53	50.0	345.4	345.5	0.1	2.78
54	55.0	345.4	345.5	0.1	2.62
55	60.0	345.4	345.6	0.2	2.48
56	65.0	345.4	345.6	0.2	2.37
57	70.0	345.7	345.7	-0.0	2.27
58	75.0	345.7	345.7	0.0	2.19
59	80.0	345.7	345.7	0.0	2.11
60	85.0	346.0	345.8	-0.2	2.05


ASSUMPTIONS AND LIMITATIONS

THE ENCLOSED DST INTERPRETATION CALCULATIONS REQUIRE SEVERAL NECESSARY ASSUMPTIONS TO PROVIDE A QUICK ESTIMATE OF MANY OF THE FACTORS INVOLVED. AS A RESULT THE INFORMATION GAINED SHOULD BE USED TO FORM AN OPINION OR ESTIMATE ONLY, UNTIL THE ASSUMPTIONS OF RESERVOIR AND FLUID PROPERTIES CAN BE WHOLLY OR PARTIALLY CLARIFIED BY MORE COMPLETE ANALYSIS AND TESTING.


PRESSURE VS. TIME
 CANDEL MOBIL ET AL IROQUOIS I-11
 I-11
 DST NO. 1 REC. NO. 5773



HORNER PRES. EXTRAPOLATION
 CANDEL MOBIL ET AL IROQUOIS I-11
 I-11
 DST NO. 1 PW = 346.5




CANDEL MOBIL ET AL IROQUOIS I-11
INTERVAL 900 - 1010
DST NO. 1 REC. NO. 5773



DST RECORDER CHARTS

CANDEL MOBIL ET AL IROQUOIS I-11
INTERVAL 900 - 1010
DST NO. 1 REC. NO. 5979



Drilling Authority No. 584
Date Issued 01-03-72

WELL NAME ... CanDel Mobil et al Iroquois I-11
FIELD Area:
LOCATION: Unit I Section 11 Grid 67-50-129-30
Latitude 67-40-40 Longitude 129-32-05
U.W.L.R. 67.67778 -- 129.53472
U.W.I. 3001116750129300

Rig Release Date: 02-06-72
Status: D + A
Information Release Date: 02-06-74

CHANGE OF NAME:

DATE RECEIVED	INDEX
25-02-72	Application for a Drilling Authority.
	Well Completion Data.
11-10-72	Well History Report.
29-05-72	Application to Amend a Drilling Authority.
	Application to change a Well Name.
08-06-72	Application to Abandon a Well or Suspend Drilling.
	Application to Alter Condition of a Well.
	Well History Supplement.
	Well Completion Data.
	Work-over Report No.
	Application to Commingle Production before Measurement.
	Data for Back Pressure Test on Natural Gas Wells - Monograph 7 Method.
	Data for Back Pressure Test on Natural Gas Wells - Vitter's Method.
	M.P.R. - Oil - Calculations.
	New Oil Well Report.
	New Gas Well Report.
	Well Inspection Report.
	Rig Inspection Report.
	Battery Inspection Report.
	Equipment Report.
	Well Card.
	New Service Well Report.
	Monthly Water Flood Operations Report
	Monthly Water Receipts and Disposal of Fluids Report
	Logs. Large scale..... Small scale.....

DATE RECEIVED

LOGS:

Name	Run No.	Type	Interval
BHC-S	1		
SN-GR	1		
IGR	1		
FDC	1		

ANALYSES:

Sample	Lab. No.	Formation	Interval
--------	----------	-----------	----------

A.O.F. Potential	Formation	Interval	MC.F.D.	Test Date
------------------	-----------	----------	---------	-----------

DRILL STEM TESTS:

No.	Formation	Interval
-----	-----------	----------

To be submitted in duplicate within thirty days after the completion, rework, abandonment, recompletion or suspension of every well.
À présenter en double dans les trente jours suivant l'achèvement, le remaniement, l'abandon et le reconditionnement de chaque puits, ou après suspension.

Well Name & No. - Nom et n° du puits
CanDel Mobil etal Iroquois I-11

Permit No. - N° de permis
4119

Lease No. - N° de concession

(Permittee, Licensee, Lessee) - (Détenteur de permis ou de licence, du concessionnaire)
Exploratory Licence No. - N° de licence de sondage

* See Below

(Operator) - (Exécutant)
CanDel Oil Ltd.

Exploratory Licence No. - N° de licence de sondage
1938

LOCATION - EMPLACEMENT

Unit - Unité I	Section 11	Grid - Étendue quadrillée 67-50-129-30	Latitude 67° 40' 40"	Longitude 129° 32' 05"
Unique Well Identifier - Code d'ordinateur 300I116750129300			Universal Well Location Reference - Références universelles d'emplacement du puits 67.67778° 129.53472	

	Date	Depth - Profondeur	Pool(s) Gisement(s)
Spudded Début des travaux	2:30 a.m. Apr. 25/72		
Suspended Suspension des travaux			Interval(s) Open to Production Intervalle(s) de production
Resumed Operations Reprise des travaux			
Finished Drilling Forage terminé	Midnight May 27/72	6962' (Driller) 6944' (Logger)	
Deepened Approfondissement			
Complete (Gas/Oil) Achèvement (Gaz/Pétrole)			Elevation: Gr. 400' K.B. 418' Altitude du sol du carré d'entraînement
Abandoned Abandon	June 2/72		Rig No. 8 Drilling Contractor Nabors Drilling N° de la tour de forage Entrepreneur en forage Limited
Rig Released Fin des travaux	12:00 noon June 2/72		Contractor's Business Licence No. 0968 N° du permis de l'entrepreneur

CASING RECORD - TUBAGE

Casing Size (Inches) Diamètre (en pouces)	Grade Qualité	Weight Poids	Amount Longueur	Set at - Fixation à	Sacks of Cement and Additives Sacs de ciment et d'additifs
1. 16" Conductor Pipe	New, shop fabricated		Cemented full length w/100 sx fondu		
2. 9-5/8"	J-55	36#	724.91'	704'	350 sacks Fondue down 12:04 pm. Apr. 25
3.					
4.					
5.					
6.					

Geological Tops Sommet des formations	Elevation - Profondeur		Core Record - Carottes					
	Depths Sous le niveau du sol	Sub-Sea Sous le niveau de la mer	From - de	To - à	Rec. Récupérées	From - de	To - à	Rec. Recup.
Drift	Surface	-	No Cores					
Devonian-Hare/Ind	17	+ 401						
Hume	98	+ 320						
Gossage/Bear Rk.Ls.	347	+ 71						
Dol.								
Sil/Ord. Ronning	2106	- 1688	Log Record - Diagrammes					
Cherty Mbr.								
Cambrian	5665	- 5247						
Main Salt	5842	- 5424						
Main Salt Base	6087	- 5669						
Proterozoic	6428	- 6010						
T.D. Driller	6961	- 6543						

* Mobil Oil Canada, Ltd. 1432
Sun Oil Company 1941
Inexco 1929
North Canadian Oils 1973

Présenter les townships auxibles à l'indiquent en conservation au district.
Endiguer.
Forme to be prepared in duplicate and forwarded to the District Conservation

Steel, J.S. and J. E. Smith 1960

1106
1107
1108
1109
1110
1111
1112
1113
1114
1115
1116
1117
1118
1119
1120
1121
1122
1123
1124
1125
1126
1127
1128
1129
1130
1131
1132
1133
1134
1135
1136
1137
1138
1139
1140
1141
1142
1143
1144
1145
1146
1147
1148
1149
1150
1151
1152
1153
1154
1155
1156
1157
1158
1159
1160
1161
1162
1163
1164
1165
1166
1167
1168
1169
1170
1171
1172
1173
1174
1175
1176
1177
1178
1179
1180
1181
1182
1183
1184
1185
1186
1187
1188
1189
1190
1191
1192
1193
1194
1195
1196
1197
1198
1199
1200
1201
1202
1203
1204
1205
1206
1207
1208
1209
1210
1211
1212
1213
1214
1215
1216
1217
1218
1219
1220
1221
1222
1223
1224
1225
1226
1227
1228
1229
1230
1231
1232
1233
1234
1235
1236
1237
1238
1239
1240
1241
1242
1243
1244
1245
1246
1247
1248
1249
1250
1251
1252
1253
1254
1255
1256
1257
1258
1259
1260
1261
1262
1263
1264
1265
1266
1267
1268
1269
1270
1271
1272
1273
1274
1275
1276
1277
1278
1279
1280
1281
1282
1283
1284
1285
1286
1287
1288
1289
1290
1291
1292
1293
1294
1295
1296
1297
1298
1299
1300
1301
1302
1303
1304
1305
1306
1307
1308
1309
1310
1311
1312
1313
1314
1315
1316
1317
1318
1319
1320
1321
1322
1323
1324
1325
1326
1327
1328
1329
1330
1331
1332
1333
1334
1335
1336
1337
1338
1339
1340
1341
1342
1343
1344
1345
1346
1347
1348
1349
1350
1351
1352
1353
1354
1355
1356
1357
1358
1359
1360
1361
1362
1363
1364
1365
1366
1367
1368
1369
1370
1371
1372
1373
1374
1375
1376
1377
1378
1379
1380
1381
1382
1383
1384
1385
1386
1387
1388
1389
1390
1391
1392
1393
1394
1395
1396
1397
1398
1399
1400
1401
1402
1403
1404
1405
1406
1407
1408
1409
1410
1411
1412
1413
1414
1415
1416
1417
1418
1419
1420
1421
1422
1423
1424
1425
1426
1427
1428
1429
1430
1431
1432
1433
1434
1435
1436
1437
1438
1439
1440
1441
1442
1443
1444
1445
1446
1447
1448
1449
1450
1451
1452
1453
1454
1455
1456
1457
1458
1459
1460
1461
1462
1463
1464
1465
1466
1467
1468
1469
1470
1471
1472
1473
1474
1475
1476
1477
1478
1479
1480
1481
1482
1483
1484
1485
1486
1487
1488
1489
1490
1491
1492
1493
1494
1495
1496
1497
1498
1499
1500
1501
1502
1503
1504
1505
1506
1507
1508
1509
1510
1511
1512
1513
1514
1515
1516
1517
1518
1519
1520
1521
1522
1523
1524
1525
1526
1527
1528
1529
1530
1531
1532
1533
1534
1535
1536
1537
1538
1539
1540
1541
1542
1543
1544
1545
1546
1547
1548
1549
1550
1551
1552
1553
1554
1555
1556
1557
1558
1559
1560
1561
1562
1563
1564
1565
1566
1567
1568
1569
1570
1571
1572
1573
1574
1575
1576
1577
1578
1579
1580
1581
1582
1583
1584
1585
1586
1587
1588
1589
1590
1591
1592
1593
1594
1595
1596
1597
1598
1599
1600
1601
1602
1603
1604
1605
1606
1607
1608
1609
1610
1611
1612
1613
1614
1615
1616
1617
1618
1619
1620
1621
1622
1623
1624
1625
1626
1627
1628
1629
1630
1631
1632
1633
1634
1635
1636
1637
1638
1639
1640
1641
1642
1643
1644
1645
1646
1647
1648
1649
1650
1651
1652
1653
1654
1655
1656
1657
1658
1659
1660
1661
1662
1663
1664
1665
1666
1667
1668
1669
1670
1671
1672
1673
1674
1675
1676
1677
1678
1679
1680
1681
1682
1683
1684
1685
1686
1687
1688
1689
1690
1691
1692
1693
1694
1695
1696
1697
1698
1699
1700
1701
1702
1703
1704
1705
1706
1707
1708
1709
1710
1711
1712
1713
1714
1715
1716
1717
1718
1719
1720
1721
1722
1723
1724
1725
1726
1727
1728
1729
1730
1731
1732
1733
1734
1735
1736
1737
1738
1739
1740
1741
1742
1743
1744
1745
1746
1747
1748
1749
1750
1751
1752
1753
1754
1755
1756
1757
1758
1759
1760
1761
1762
1763
1764
1765
1766
1767
1768
1769
1770
1771
1772
1773
1774
1775
1776
1777
1778
1779
1780
1781
1782
1783
1784
1785
1786
1787
17

21306 b21

20210131

CSUNDER OII TEG:

STATISTICS

No of Laboratory Lab. No.	Examination Sample	Flow - 98	10 - 8	Source	Remarks - Remarks
833-5281	Water	3151	3387	DST. #3 - Running Rock	Water Analysis
833-5281	Water	3000	3010	DST. #1 - Bear Rock	Water Analysis
833-5280	Water	3300	3014	DST. #2 - Running	Water Analysis


[illegible]

CREDIT ADVANCEMENT - STUDENT MATS. LIND

[illegible]



Drilling Authority No. 584



DEPARTMENT OF INDIAN AFFAIRS AND NORTHERN DEVELOPMENT
OIL AND MINERAL DIVISION

Application to Abandon a Well on ~~Surface Drilling~~

In compliance with the "Canada Oil and Gas Land Regulations", application is hereby made for approval to abandon, to suspend drilling:—

Name and number of well..... CanDel Mobil etal Iroquois I-11
Location: Unit..... I..... Section..... 11..... Grid..... 67-50-129-30
Latitude..... 67° 40' 40"..... Longitude..... 129° 32' 05"
From Established Reference Marker..... Shot Point 478
Universal Well Location Reference..... 67.67778..... 129.53472
Permit No. 4119..... Lease No.....

Attached
(Permittee, Licencee, Lessee)

Date of commencement of proposed program..... May 31, 1972

OIL, GAS, AND WATER ENCOUNTERED
(Depths)

Oil at..... Nil
Gas at..... Nil
Water at..... 900-1010; 2121-2261
Total Depth..... 6961'..... Date of last operations..... Present
Present condition of well..... 8-3/4" hole to T.D. - Waiting on Orders

CASING RECORD

Casing Size O.D. Inches	Weight	Amount	Set At—	Sacks of Cement and Additives	Amount Pulled
1. 9-5/8"	36# J-55	704	704	350 sacks Fondue Cement	nil
2.					
3.					
4. 20"			39'	100 sacks Fondue	
5.					

PROPOSED ABANDONMENT PROGRAM

No.	Plug	Geological Formation	Number of Sacks of Cement	Remarks
	Position			
1	6861 to 6961'	Proterozoic	55	On bottom
2	3450 to 3600'	Ronning	100	Feel for after 8 hrs.
3	2000 to 2150	Bear Rock & Ronning	100	Feel for after 8 hrs.
4	630 to 780	Bear Rock	100	Feel for after 8 hrs.
5	Inside stub @ top of casing		5	Weld plate on top of casing stub with 5' riser and sign above ground

The following logs have been run I-E log, Acoustilog, Density log & Neutron Porosity
Other operations proposed..... D.S.T. from 3200 to 3450'

Operations to be carried out by Nabors Drilling Limited Contractor Licence No. 0963
Address..... 440 Bentall Building..... Address.....
Responsible Agent in field.....
Dated at..... CALGARY....., this..... 31st..... Day of..... May..... 19.72
Signed by..... [Signature]..... Company..... CanDel Oil Ltd.
Title..... Drilling Manager..... Operator's Exploratory Licence No. 1938

Note:—The District Conservation Engineer's office must be notified before work is commenced.

(For OIL AND MINERAL DIVISION use only)
APPROVAL

This application has been examined and proposed programme approved, subject to the following conditions:


Confirming oral approval given by Mr. D. A. Bohun on the 1st June 1972

Dated 8 June 1972, 19

[Signature]
District Conservation Engineer



DEPARTMENT OF INDIAN AFFAIRS AND NORTHERN DEVELOPMENT
OIL AND MINERAL DIVISION



Application to Amend a Drilling Authority

This application, in triplicate, must be submitted and approved before commencing operations. If the well location is changed, this application must be accompanied where required, with a plan of survey approved by the Surveyor General.

In compliance with the "Canada Oil and Gas Land Regulations", application is hereby made to amend Drilling Authority No. 584, concerning

CanDel Mobil et al Iroquois I-11
(Name and Number of Well)

'Expected total final depth' was listed as 6500'-. It is requested that this be changed to 7040' (9-5/8" surface casing landed @ 704' K.B.). This well is scheduled to drill into the Proterozoic, originally expected at a depth of 6450', but the lower formations are low to prognosis. Change of total depth to 7040' was approved by telephone May 27, 1972 by Mr. D. Thomas, District Oil & Gas Conservation Engineer, Calgary.

Dated at Calgary, this 29th day of May, 1972

Signed by K.E. Basaraba (K.E. Basaraba)

Title Geologist

Company CANDEL OIL LTD.

(For Oil and Mineral Division use only)

APPROVED


This application has been examined and approved subject to the following conditions:

Date May 29, 1972

District Conservation Engineer



DEPARTMENT OF INDIAN AFFAIRS AND NORTHERN DEVELOPMENT
OIL AND MINERAL DIVISION



Application for a Drilling Authority

This notice of intention to begin drilling operations, in triplicate, and where required a plan of survey approved by the Surveyor General showing the target area or the site of the well must be submitted and approved before commencing operations.

In compliance with the "Canada Oil and Gas Land Regulations", application is hereby made for approval to drill:-

Name and number of well CanDel Mobil etal Iroquois I-11
Location: Unit I Section 11 Grid 67-50-129-30
Latitude 67° 40' 40" Longitude 129° 32' 05"
Unique Well Identifier 30QI116750129300
Universal Well Location Reference 67.67778° 129.53472°
Shot Pt. 478
Elevation: Ground 400' Line 226 K.B. 415' Est. feet above sea-level.
Well is expected to produce from Devonian, Sil-Ord. Cambrian formation at a depth
of about feet. Expected total final depth 6500'
Area assigned to well
(for District Conservation Engineer's use only)

Permit No. 411 Lease No. Acreage 48,546
Permittee, licensee, or lessee as attached
Explanatory Licence No. as attached
Surface owned by Crown or Crown
(If alienated submit name and address of owner and occupant.)

Petroleum and natural gas rights owned by Crown
We propose to use the following strings of casing, either cementing or landing them as indicated below:-

Casing Size O.D. (Inches)	Weight (Lb./Ft.)	Grade	New or Used	Estimated Depth	Sacks of Cement
1. 16"		Conductor	New	40'	full length
2. 9-5/8"	36	J-55	New	700'	" "
3. Other casing - If required will be negotiated					
4.					
5.					

Expected water, gas, and oil horizons and type of control equipment
Devonian, Sil-Ord., Cambrian
BOP Stack and drilling fluid

Well will be drilled with Rotary Rig No. 8 by Nabors Drilling Limited
(Drilling Contractor or company)

Responsible agent of applicant:- Contractor's Business Licence No. 0968
At well D. R. Nelson At registered office R. K. Terrell
Address Mackenzie Mtn. Lodge, Norman Wells Address 330 - 5th Avenue S.W., Calgary 1.
It is understood that if changes become necessary, notice of the change of plan will be submitted.
Dated at Calgary this 25th day of February 19 72
Signed by Company CanDel Oil Ltd.
Title Exploration Manager Operator's Licence No. 1938

(For Oil and Mineral Division use only)

APPROVED

This application has been examined and approved subject to the following conditions:

Please see attached sheet for Conditions of Approval
Dated March 1 19 72

District Conservation Engineer
Forms to be submitted to District Conservation Engineer,
Department of Indian Affairs and Northern Development.

Exploratory Licence Nos

Mobil Oil Canada, Ltd.	1432
Sun Oil Company	1941
Inexco	1929
North Canadian Oils	1973

CONDITIONS OF APPROVAL FOR DRILLING AUTHORITY NO. 584
FOR CanDel Mobil etal Iroquois I-11

1. Copies of this Drilling Authority shall be exhibited at the Drilling Rig in both the Doghouse and the Drilling Foreman's Office between spud and rig release dates.
2. The Company will submit to this office, on Tuesday of each week, the latest reports received by radio on the progress of the well.
3. During well drilling and testing operations, every effort shall be made to ensure that drilling fluids, chemicals and wastes shall be disposed of or contained in a manner that will prevent the contamination of adjacent vegetation and surface or sub-surface waters.
4. We draw your attention to Sections 95 and 96 of the Canada Oil and Gas Land Regulations.
5. Any additional strings of casing must be approved by the District Conservation Engineer prior to running.

M. D. Thomas

M. D. Thomas
District Conservation Engineer
Districts 2 and 3

March 1, 1972

GEOLOGICAL PROGNOSIS

Well Name: CanDel Mobil etal Iroquois I-11

Location: I-11-67-50-129-30

Elevation: Ground 400' (SP. 478, Line 226)
K.B. 415' Est.

Operator: CanDel Oil Ltd.

Contractor: Nabors Drilling Limited Rig #8

<u>Markers:</u>	<u>Formation</u>	<u>Drilling Depth</u>	<u>Sub-Sea Depth</u>
	Devonian		
	Hare Indian	near surface	
	Hume	140'	+275'
	Gossage (Bear Rock)	405'	+10'
	Sil-Ord.	Ronning	2090'
			-1675'
	Cambrian		5490'
			-5075'
		Salt	5585'
			-5170'
		Base Salt	5815'
			-5400'
	Proterozoic		6450'
			-6035'
	Total Depth		6500'
			-6085'

Note: Some anhydrite and approximately 230' of salt should be present in the Cambrian section.

Samples: One bag of washed samples will be taken at 10 foot intervals from surface to total depth.

Testing: All tests at discretion of wellsite geologist.

Coring: If water free hydrocarbons are recovered on a test, a core should be cut and further tests run if warranted.

Logging:

Depends on well results.	Induction Electrolog	2" T.D. to surface casing 5" T.D. to surface casing
	BHC Acoustilog w/Caliper	2" T.D. to surface casing 5" T.D. to surface casing
	Formation Density	2" T.D. to surface casing 5" T.D. to surface casing
	Sidewall Neutron Porosity	2" T.D. to surface casing 5" T.D. to surface casing

Measurements:



Pipe must be tallied on all trips out for coring,
testing, logging or as requested by the wellsite
geologist or engineer in charge.

CanDel Oil Ltd.,
28th floor, Calgary Place One,
330, - 5th Avenue S.W.,
CALGARY 1, Alberta.


Telephone: 265-3430

K. E. Basaraba	Home Phone	282-4698
D. M. Ericson	" "	252-3277
R. K. Terrell	" "	289-7652


NABORS Drilling Rig 3



Ges. decr/70



106




THE DECLINATION OF THE COMPASS NEEDLE 1958
 Produced and printed by the SURVEYS AND MAPPING BRANCH, DEPARTMENT OF MINES AND TECHNICAL SURVEYS, 1959, from air photographs taken in 1950, 1951 and 1952.
 Transverse Mercator Projection

REFERENCE

- Wagon or winter road
- Trail or portage
- Village or settlement
- Post office
- Building or cabin
- R.C.M.P. post
- Horizontal control point
- Astronomical position
- Spot elevation (in feet)

TRAVAILLANT LAKE
 NORTHWEST TERRITORIES
 DISTRICT OF MACKENZIE

Scale 1:250,000
 1 Inch to 4 Miles Approximately



Contour interval 100 Feet


CANDEL OIL LTD.
 NOMAC AREA

PROPOSED SEISMIC PROGRAM & ACCESS ROADS


- Proposed Seismic Lines (143 miles)
- Proposed Seismic Access Roads (Mobil Seismic Lines)
- Proposed Well-site Access Road

The declination of the compass needle at any place along a broken line is the declination given on that broken line. At other places the declination is between those given on the neighbouring broken lines; thus at the place marked A, the declination is between 39°00' E and 39°30' E. The declination of the compass needle is decreasing 9 minutes annually.

2 of 2



106



Produced by the ARMY SURVEY ESTABLISHMENT
R.C.E. 1957-61. Aerial photography 1955.
Copies may be obtained from the Map Distribution Office,
Department of Mines and Technical Surveys, Ottawa,

CANOT LAKE

DISTRICT OF MACKENZIE
NORTHWEST TERRITORIES
Scale 1:250,000 Échelle

CANDEL OIL LTD.
NOMAC AREA


PROPOSED SEISMIC PROGRAM & ACCESS ROADS

..... Proposed Seismic Lines (140 miles)

———— Proposed Seismic Access Roads (Mobil Seismic Lines)

———— Proposed Well-site Access Road

- beds:**
- Loose surface, all weather... de gravier, toute saison... less than 2 lanes... moins de 2 voies... dry weather... période sèche
- cart track, trail... de terre, sentier
- spot elevation; precise, approximate... Point coté; précis, approximatif... 950 - 950:2
- boundary monument... Borne-frontière
- Butte... Buttes de terre
- depression contours... Courbes de cuvette
- high or low relief... Falaise ou relief peu accentué
- Esker... Esker



Transverse Mercator Projection
North American Datum 1927(1954)
Contour Interval 100 feet
Elevations in feet above Mean Sea Level

Projection transverse de Merc
Réseau géodésique nord-américain unifié 1927(1954)
Équidistance des courbes: 100 pieds
Élévations en pieds au-dessus du niveau moyen de la mer

Horizontal control point... Point géodésique... Tundra Polygon... Sols polygonaux
Landing ground... Piste d'atterrissage... Tundra Ponds... Étangs de toundra

2 of 2

Location

Handwritten text: *Handwritten text, possibly a signature or name, located at the bottom of the page.*

44-3866-226



THIS IS A CONCISE REPORT OF THE
OPERATIONS CONDUCTED AT THE WELL

'CANDEL MOBIL ET AL IROQUOIS I-11'

Data in this report was compiled for
CanDel Oil Ltd. by T. A. D. Haddow, P. Geol.,
Geological Consultant at the well

July 28, 1972

A handwritten signature in dark ink, appearing to read "K. E. Basaraba".

K. E. Basaraba,
CANDEL OIL LTD.

WELL HISTORY REPORT
ON
CANDEL MOBIL et al IROQUOIS I-11


Unit I Section 11, Grid 67-50-129-30
Latitude $67^{\circ} 40' 40''$ Longitude $129^{\circ} 32' 05''$

NORTHWEST TERRITORIES, CANADA

FOR
CANDEL OIL LTD.

June, 1972

Submitted by:


T.A.D. Haddow, P.Geol.

INDEX

	<u>Page</u>
SECTION I - Summary of Well Data	1
SECTION II - Geological Summary	
Formation Tops	3
Sample Descriptions	4
SECTION III - Engineering Summary	
Drill Stem Test Reports	29
Casing Report	32
Bit Record	33
Daily Mud Report	34
Daily Progress Report with Deviation Surveys	35
Abandonment Plugs	38
Lost Circulation Zones	38
SECTION IV - Logs	39
SECTION V - Analysis	39

SECTION I - SUMMARY OF WELL DATA

Well Name and Number: CanDel Mobil et al Iroquois I-11

Permittee: Mobil Oil Canada Ltd. License No. 1432
 Sun Oil Company License No. 1941
 Inexco Oil Company License No. 1929
 North Canadian Oils Ltd. " No. 1973

Operator: CanDel Oil Ltd. License No. 1938
 28th Floor - Calgary Place One
 330-5th Avenue S.W.
 Calgary, Alberta

Location: Unit I, Section 11, Grid 67-50-129-30
 Latitude 67° 40' 40" Longitude 129° 32' 05"
 Unique Well Identifier: 3001116750129300
 Universal Well Location Reference: 67.67778°
 129.53472°

Permit No.: 4119

Contractor: Nabors Drilling Limited Rig #8 Emsco JA 500

Drilling Authority: 584 - Issued March 1, 1972

Classification: Wildcat

Elevations: Ground 400' K.B. 418'

Spudded: 2:30 a.m. - April 25, 1972

Completed Drilling: May 28, 1972

Total Depth: Driller 6961' Logger 6944'

Well Status: Dry & Abandoned

Rig Released: 12:00 - noon - June 2, 1972

Hole Sizes: Surface - 704' 12 1/4"
 704' - 6961' 8 3/4"

Summary of Well Data (Cont'd)

Conductor Pipe: Ran new 20" conductor pipe, landed at 78' K.B.
Cemented with 100 sacks Fondu cement.
Finished cementing at 12:00 p.m. April 22, 1972

Surface Casing: Ran 9 5/8" (724.91') Grade J-55, 36#, Rge. 3, ST & C, 8rd,
New Mannesmann Casing. Landed at 704' K.B.
Cemented with 350 sacks of Fondu Cement.
Displaced plug with water.
Plug down at 12:04 p.m. April 29, 1972

Representative for Operator: T.A.D. Haddow, P.Geol.

Representative for Contractor: H. Martinoff

SECTION II - GEOLOGICAL SUMMARYFORMATION TOPS

<u>Formation</u>	<u>Sample Depth</u>	<u>E-Log Depth</u>	K.B. 418' <u>E-Log Sub-sea Depth</u>
Devonian			
Hare Indian	30'	17'	+ 401'
Hume	125'	98'	+ 320'
Gossage (Bear Rock)	350'	347'	+ 71'
Sil - Ord Ronning	2120'	2106'	-1688'
Cambrian	5675'	5665'	-5247'
Salt	5850'	5842'	-5424'
Base Salt	6084'	6087'	-5669'
Proterozoic	6420'	6428'	-6010'
Total Depth	6961'	6944'	-6526'

Candel Mobil et al Iroquois I-11

Sample Descriptions

K.B. 418'

<u>Interval</u>	<u>Lithology</u>
Surface - 30'	<u>Glacial drift</u> - unconsolidated sand, granules, pebbles and cobbles <u>Hare Indian 30'</u> (E-Log 17')
30 - 40'	<u>Shale</u> - grey, fissile, micromicaceous, scattered black plant spores.
40 - 80'	<u>Shale</u> - medium grey, hard, fissile, micromicaceous, slightly bituminous in part, scattered, flecks of carbonaceous material (plant spores).
80 - 90'	<u>Shale</u> - dark grey to black, fissile, micromicaceous, bituminous, rare laminae of calcareous siltstone.
90 - 110'	<u>Shale</u> - as above, scattered plant remains and plant spores, trace of scattered pyrite.
110 - 120'	<u>Shale</u> - dark grey to black, brittle, micromicaceous, bituminous for the most part, scattered plant remains and spores, scattered fossils, calcareous in part - limy streaks. <u>Hume 125'</u> (E-Log 98')
120 - 130'	<u>Shale</u> - as above <u>Limestone</u> - grey - greenish to brownish in part, microcrystalline, very fine to fine crystalline in part, dense, silty, argillaceous, thin interbedded grey-calcareous shale, some dolomitic streaks - brownish grey, microcrystalline dense, abundant fossils - ostracods, brachiopods, bryozoa.
130 - 140'	<u>Shale</u> - medium grey, hard, micromicaceous, calcareous. <u>Limestone</u> - grey - greenish to brownish in part, microcrystalline to very fine crystalline, dense, bioclastic - micritic in part, fossiliferous, scattered fractures filled with coarse calcite crystals.
140 - 150'	<u>Limestone</u> - medium brownish to greenish grey, microcrystalline, some very fine to fine crystalline, bioclastic, pelotoid in part, micritic in part, dense, argillaceous, some thin interbeds of grey calcareous shale, some cherty streaks, scattered fractures filled with crystalline calcite, fossiliferous, scattered pyrite.

- 150 - 160' Limestone - as above
Shale - medium grey, hard, micromicaceous, calcareous, pyritic in part.
- 160 - 170' Limestone - medium brownish to greenish grey, microcrystalline to very fine crystalline, bioclastic, dense, abundant fossils - brachiopods, ostracods, crinoids, some interbedded shale - medium grey, hard, micromicaceous, calcareous.
- 170 - 210' Limestone - medium brownish to greenish grey, microcrystalline to very fine crystalline, dense, argillaceous, fossiliferous.
Shale - medium grey, micromicaceous, calcareous.
- 210 - 220' Limestone - medium brownish to greenish grey, microcrystalline to very fine crystalline, bioclastic, micritic in part, dense, argillaceous, streaks, some interbedded grey calcareous shale, fossiliferous.
- 220 - 250' Limestone - medium brownish to greenish grey, microcrystalline to fine crystalline, bioclastic, micritic in part, dense, argillaceous, shaly, fossiliferous, scattered fractures filled with dog tooth spar.
- 250 - 270' Limestone - as above.
Shale - medium grey, fissile to blocky, micromicaceous, calcareous.
- 270 - 300' Limestone - greyish brown - some greenish to brownish grey, microcrystalline to fine crystalline, fragmental, micritic in part, dense, argillaceous, fossiliferous, some partings of dark grey calcareous shale and thin interbeds of medium grey calcareous shale, some scattered fractures filled with crystalline calcite.
- 300 - 350' Limestone - brownish grey, microcrystalline to very fine crystalline, micritic, dense, argillaceous, some partings of dark grey calcareous shale, some scattered pyrite, scattered fossils - brachiopods, crinoids, bryozoa.
- Gossage 350' (E-Log 347')
- 350 - 370' Limestone - light brownish grey, microcrystalline to fine crystalline, oolitic, dense, slightly argillaceous, some scattered fractures filled with crystalline calcite, rare scattered small vugs filled with crystalline calcite.
- 370 - 390' Limestone - as above and limestone - brownish to greenish grey, cryptocrystalline, micritic, dense, some scattered hairline fractures, some dolomitization along the fractures.
- 390 - 420' Limestone - brownish grey, microcrystalline, micritic, dense, argillaceous, some scattered ostracods, some scattered small patches and streaks of black carbonaceous material.
- 420 - 430' Limestone - medium dark brownish grey, cryptocrystalline to microcrystalline, micritic, dense, argillaceous, some partings of dark grey shale.

- 430 - 440' Limestone - greyish brown, microcrystalline to fine crystalline, fragmental - micritic in part, dense, argillaceous, scattered ostracods.
- 440 - 470' Limestone - light greyish brown, microcrystalline to fine crystalline - some bands of cryptocrystalline, fragmental, - organic in part, micritic in part, dense, argillaceous, some algal material, scattered ostracods, some partings of black bituminous shale.
- 470 - 480' Limestone - medium to dark greyish brown, microcrystalline to fine crystalline, micritic in part - fragmental, pelletoid and oolitic in part, dense, argillaceous, scattered stylolites, some scattered partings of black bituminous shale, ostracods.
- 480 - 490' Limestone - light greyish brown, microcrystalline to fine crystalline, bioclastic, dense, fossiliferous - ostracods, brachiopods, rare corals.
- 490 - 510' Limestone - grey brown, cryptocrystalline to very fine crystalline, micritic, dense, scattered brachiopods, some scattered fine fractures filled with calcite.
- 510 - 520' Limestone - as above - some scattered hairline fractures, some streaks of shale - bluish grey, blocky, micromicaceous, bentonitic, scattered pyrite.
- 520 - 530' Limestone - light brownish grey, microcrystalline to fine crystalline, fragmental, dense, dolomitic, argillaceous, fossiliferous - brachiopods, ostracods.
- 530 - 540' Limestone - medium dark grey, microcrystalline to very fine crystalline, algal, dense, argillaceous, scattered ostracods, partings of black bituminous shale.
- 540 - 550' Limestone - light brownish grey, microcrystalline to fine crystalline, fragmental, dense, argillaceous, scattered ostracods, some scattered corals.
- 550 - 590' Limestone - brownish grey - some greenish streaks, cryptocrystalline to microcrystalline, micritic, dense, argillaceous.
- 590 - 600' Limestone - medium greyish brown, microcrystalline to fine crystalline, fragmental, dense, argillaceous, some partings of black bituminous shale. Trace of light greenish grey waxy shale, some scattered gastropods and brachiopods.
- 600 - 630' Limestone - as above - light to medium greyish brown, micritic in part.
- 630 - 640' Limestone - as above and limestone - brownish grey, cryptocrystalline, micritic, dense.

- 640 - 650' Limestone - greyish brown, cryptocrystalline to very fine crystalline, micritic, dense, argillaceous, scattered hairline and fine fractures - filled with calcite, a few scattered fossils.
- 650 - 680' Limestone - as above - few fragmental streaks - slightly dolomitic, a few streaks of dark grey shale and bluish grey bentonitic shale.
- 680 - 690' Limestone - as above - few fragmental streaks - dolomitic in part with dead oil stain.
- 690 - 700' Limestone - brownish grey, microcrystalline to very fine crystalline, fragmental - micritic in part, dense, argillaceous, some scattered ostracods.
- 700 - 720' Limestone - medium greyish brown - dark streaks, microcrystalline to very fine crystalline, fragmental in part, micritic in part, dense, argillaceous, partings of dark grey shale and thin interbeds of grey calcareous shale, scattered ostracods.
- 720 - 740' Limestone - brownish grey, microcrystalline to very fine crystalline, micritic, fragmental in part, dense, slightly argillaceous, some thin streaks of grey calcareous shale.
- 740 - 750' Limestone - as above and limestone - brownish grey, cryptocrystalline to microcrystalline, micritic, dense, argillaceous, some laminae of shale - bluish grey, blocky, finely disseminated pyrite.
- 750 - 770' Limestone - greyish brown, microcrystalline to very fine crystalline, fragmental in part, micritic in part, dense, argillaceous, few scattered fractures filled with crystalline calcite, some scattered ostracods.
- 770 - 790' Limestone - greyish brown, microcrystalline to very fine crystalline, fragmental, dense, argillaceous, some partings of black bituminous shale and bluish grey shale with finely disseminated pyrite.
- 790 - 800' Limestone - as above, partings of grey calcareous shale.
- 800 - 810' Limestone - greyish brown, cryptocrystalline to microcrystalline, micritic, argillaceous, calcite crystals infilling some fine scattered fractures and rare small vugs.
- 810 - 830' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic, dense, argillaceous, some interbedded grey calcareous shale, some scattered brachiopods.

- 830 - 840' Limestone - greyish brown, microcrystalline to fine crystalline, micritic, organic in part, fragmental in part, dense, argillaceous, pyritic in part, some thin interbedded grey calcareous shale and partings of bluish grey shale - fossiliferous - coral, algae, brachiopods, ostracods.
- 840 - 850' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic, algal in part, dense, argillaceous, some interbedded grey calcareous shale, pyritic in part, some scattered crinoids and brachiopods.
- 850 - 860' Shale - greenish grey, hard, micromicaceous, very calcareous, finely disseminated pyrite, some scattered limestone pellets.
Limestone - greyish brown, cryptocrystalline to microcrystalline, micritic, dense, argillaceous.
- 860 - 870' Limestone - greyish brown, very fine crystalline, micritic - fragmental in part, dense, argillaceous, some interbedded shale as above.
- 870 - 910' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic, dense, argillaceous (trace of stromatoporoids at 890').
- 910 - 920' Limestone - as above, some streaks of very light grey chalky limestone, some thin interbedded dolomite (5%) - greyish brown very fine crystalline, chalky in part, slight intercrystalline porosity - non effective, slightly calcitic.
- 920 - 940' Limestone - 75% and dolomite 25% as above.
- 940 - 950' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic - fragmental in part, some cream chalky streaks, some interbedded dolomite with slight intercrystalline porosity - noneffective, some scattered coarse crystals of secondary dolomite.
- 950 - 960' Limestone - greyish brown microcrystalline to very fine crystalline with streaks of very light grey to cream - chalky, micritic; fragmental in part, some interbedded dolomite - greyish brown, very fine crystalline, earthy in part, slight intercrystalline porosity - noneffective.
- 960 - 980' Dolomite - greyish brown, very fine crystalline, slightly calcitic in part, slight intercrystalline porosity.
- 980 - 990' Limestone - cream to greyish brown, microcrystalline to very fine crystalline - chalky in part, micritic in part, fragmental in part, dense, slightly argillaceous in part, some streaks and thin interbedded dolomite as above - slight intercrystalline porosity - noneffective.

- 990 - 1010' Limestone - cream to greyish brown, microcrystalline to very fine crystalline - chalky in part, fragmental, tight, argillaceous streaks, slightly dolomitic - earthy in part.
- 1010 - 1030' Limestone - as above - micritic and fragmental.
- 1030 - 1050' Limestone - as above - micritic and fragmental, trace of milky chert.
- 1050 - 1060' Limestone - very light greyish brown - cream in part, microcrystalline, fragmental, micritic in part, some oolites, dense.
- 1060 - 1080' Limestone - very light to light greyish brown, microcrystalline to very fine crystalline - as above.
- 1080 - 1130' Limestone - very light greyish brown - cream in part, microcrystalline to very fine crystalline, fragmental and micritic, dense.
- 1130 - 1150' Limestone - light greyish brown, microcrystalline to very fine crystalline, fragmental and micritic, dolomitic streaks, tight.
- 1150 - 1160' Limestone - light greyish brown, microcrystalline to very fine crystalline, fragmental, micritic in part, dense.
Dolomite - greyish brown, very fine crystalline, slight intercrystalline porosity - noneffective.
- 1160 - 1170' Dolomite - greyish brown, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous.
- 1170 - 1180' Dolomite - as above.
Limestone - brownish grey, microcrystalline to very fine crystalline, fragmental, micritic in part, dense, argillaceous.
- 1180 - 1200' Limestone - greyish brown, microcrystalline to very fine crystalline, fragmental, micritic in part, pelletoidal in part, dolomitic streaks, tight, argillaceous.
- 1200 - 1230' Dolomite - greyish brown, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous, a few scattered fine fractures filled with calcite.
- 1230 - 1240' Dolomite - very light greyish brown - some darker streaks, microcrystalline to very fine crystalline, slight intercrystalline porosity, some argillaceous streaks, some streaks of limestone as above.
- 1240 - 1250' Dolomite - brown - greyish, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous, trace of quartz crystals.

- 1250 - 1260' Dolomite - greyish brown, microcrystalline to very fine crystalline, slight to poor intercrystalline, pinpoint and scattered small vuggy porosity, some scattered white coarse secondary dolomite crystals, argillaceous.
- 1260 - 1280' Dolomite - light greyish brown, microcrystalline to very fine crystalline, slight to poor intercrystalline, pinpoint and scattered small vuggy porosity, some scattered white coarse secondary dolomite crystals, slightly argillaceous in part.
- 1280 - 1360' Dolomite - greyish brown - some light streaks, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous.
- 1360 - 1380' Dolomite - very light greyish brown - some dark streaks - very fine to fine crystalline, slight to poor intercrystalline porosity.
- 1380 - 1400' Dolomite - greyish brown, microcrystalline to fine crystalline, slight intercrystalline porosity, argillaceous, some scattered fractures filled with crystalline calcite.
- 1400 - 1410' Dolomite - greyish brown to medium dark greyish brown, very fine to fine crystalline, slight intercrystalline porosity, argillaceous, some scattered partings of black bituminous shale, trace of quartz crystals.
- 1410 - 1420' Dolomite - greyish brown, very fine to fine crystalline, slight intercrystalline porosity, argillaceous, scattered fractures filled with crystalline calcite.
- 1420 - 1450' Dolomite - medium greyish brown, very fine to fine crystalline, slight to poor intercrystalline, pinpoint and small vuggy porosity, argillaceous, scattered fractures filled with crystalline calcite.
- 1450 - 1480' Dolomite - light greyish brown - some dark streaks, very fine to fine crystalline, poor intercrystalline & scattered small vuggy porosity, slightly argillaceous in part.
- 1480 - 1510' Dolomite - greyish brown, very fine to fine crystalline, slight to poor intercrystalline porosity, argillaceous.
- 1510 - 1540' Dolomite - light brownish grey - as above.
- 1540 - 1560' Dolomite - brownish grey - some dark streaks, very fine to fine crystalline, slight to poor intercrystalline porosity, argillaceous.
- 1560 - 1580' Dolomite - as above, trace of quartz crystals, some calcite crystals (infilling fractures).
- 1580 - 1590' Dolomite - as above - marked increase in quartz crystals & calcite crystals.

- 1590 - 1600' Dolomite - brownish grey - some dark streaks, very fine to fine crystalline, slight to poor intercrystalline porosity, argillaceous.
- 1600 - 1610' Dolomite - light to medium dark greyish brown, microcrystalline to very fine crystalline, slight streaky intercrystalline porosity, streaky argillaceous content, few scattered quartz crystals.
- 1610 - 1620' Dolomite - light greyish brown, microcrystalline to very fine crystalline, streaky slight intercrystalline porosity, slightly argillaceous.
- 1620 - 1690' Dolomite - greyish brown, microcrystalline to very fine crystalline, streaky, slight intercrystalline porosity, argillaceous, few scattered quartz crystals, some scattered calcite crystals.
- 1690 - 1700' Dolomite - greyish brown - light streaks, microcrystalline to very fine crystalline, streaky slight intercrystalline porosity - noneffective, few quartz crystals and calcite crystals.
- 1700 - 1730' Dolomite - light greyish brown, microcrystalline to very fine crystalline, tight, silty, few quartz crystals and calcite crystals.
- 1730 - 1790' Dolomite - buff, some dark streaks in part, fine to medium crystalline, dense, silty, abundant, quartz crystals.
- 1790 - 1820' Dolomite - buff, microcrystalline to very fine crystalline, dense, silty (samples powdered - difficult to interpret).
- 1820 - 1910' Dolomite - medium grey, microcrystalline to very fine crystalline, dense, argillaceous, trace of quartz crystals, trace of greenish grey shale partings - silty.
- 1910 - 1940' Dolomite - light grey, microcrystalline, dense, silty.
- 1940 - 1960' Dolomite - light grey, microcrystalline to very fine crystalline, tight, silty - very fine, rare greenish grey shaly streaks.
- 1960 - 1990' Dolomite - grey, microcrystalline, tight, some argillaceous streaks, silty, some partings of dark grey shale.
- 1990 - 2010' Dolomite - brownish grey - some dark streaks, microcrystalline to very fine crystalline, dense, argillaceous, silty, rare partings of black bituminous shale, some scattered fractures filled with crystalline calcite.
- 2010 - 2020' Dolomite - dark brownish grey - some light streaks, microcrystalline, tight very argillaceous, silty, some partings of black bituminous shale.

- 2020 - 2030' Dolomite - grey, microcrystalline, tight, argillaceous, silty, some partings of greenish grey shale.
- 2030 - 2040' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline - some fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty, some partings of dark grey shale and black bituminous shale.
- 2040 - 2050' Dolomite - light grey - slightly greenish to brownish cast, microcrystalline to very fine crystalline, tight, silty.
- 2050 - 2070' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline, tight, very argillaceous, slightly silty, scattered fractures filled with crystalline calcite, partings of dark grey shale.
- 2070 - 2090' Dolomite - medium grey - slightly brownish, microcrystalline, dense, argillaceous, silty, scattered fractures with calcite.
- 2090 - 2100' Dolomite - brownish grey - some darker streaks, microcrystalline to fine crystalline, dense, argillaceous in part, silty, scattered fractures with calcite.
- 2100 - 2120' Dolomite - grey - slightly brownish - some light streaks, microcrystalline to very fine crystalline, dense, hard, argillaceous, silty, some scattered fractures filled with crystalline calcite.
- Ronning 2120' (E-Log 2106')
- 2120 - 2140' Dolomite - greyish brown - some light streaks, microcrystalline to fine crystalline - some light colored streaks are fine to medium crystalline, tight for the most part, some streaky slight intercrystalline porosity, argillaceous, silty, some streaks of greyish green shale, scattered fractures filled with crystalline calcite - trace of quartz crystals.
- 2140 - 2150' Dolomite - buff, microcrystalline to very fine crystalline slight intercrystalline porosity, silty, some streaks of greyish green shale, scattered fractures filled with calcite.
- 2150 - 2160' Dolomite - light greyish brown, microcrystalline to very fine crystalline, streaky, slight intercrystalline porosity, argillaceous, silty, trace of quartz crystals.
- 2160 - 2190' Dolomite - as above - some light colored streaks - very fine to fine crystalline, streaky intercrystalline porosity, scattered fractures filled with crystalline calcite.

- 2190 - 2220' Dolomite - very light buff, fine to medium crystalline, poor intercrystalline and vuggy porosity - abundant loose coarse dolomite rhombs - scattered quartz crystals, slightly silty and argillaceous.
- 2220 - 2230' Dolomite - greyish brown, fine to medium crystalline, slight to poor intercrystalline porosity, argillaceous, scattered quartz crystals.
- 2230 - 2240' Dolomite - light greyish brown - some dark streaks, fine to medium crystalline, poor intercrystalline and vuggy porosity - scattered dolomite rhombs, scattered quartz crystals, slightly argillaceous, silty.
- 2240 - 2250' Dolomite - very light buff - fine to medium crystalline, poor intercrystalline and vuggy porosity, scattered dolomite rhombs and quartz crystals.
- 2250 - 2280' Dolomite - very light greyish brown - fine to medium crystalline, poor intercrystalline & vuggy porosity, scattered dolomitic rhombs and quartz crystals, slightly silty, scattered fractures filled with crystalline calcite.
- 2280 - 2300' Dolomite - medium dark to dark greyish brown, very fine to medium crystalline, slight intercrystalline and vuggy porosity, scattered dolomite rhombs and quartz crystals, argillaceous and silty.
- 2300 - 2310' Dolomite - medium greyish brown, fine to medium crystalline - euhedral, slight scattered vuggy porosity, argillaceous, silty, scattered dolomite rhombs, trace of quartz crystals.
- 2310 - 2320' Dolomite - light to medium greyish brown - as above.
- 2320 - 2380' Dolomite - greyish brown, very fine to fine crystalline, streaky, slight intercrystalline porosity, argillaceous, silty, scattered quartz crystals.
- 2380 - 2390' Dolomite - very light buff, fine to medium crystalline, slight intercrystalline porosity, scattered vugs - some coarse dolomite rhombs.
- 2390 - 2410' Dolomite - very light buff to very light brown, very fine to medium crystalline - euhedral, slight vuggy porosity - scattered coarse dolomite rhombs, streaky slight intercrystalline porosity.
- 2410 - 2440' Dolomite - medium brownish grey - some light streaks, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty, scattered fractures filled with white coarse crystalline secondary dolomite. Some fractures filled with crystalline calcite.

- 2440 - 2460' Dolomite - medium to dark brownish grey, very fine to fine crystalline, dense, argillaceous, silty, some scattered loose dolomite rhombs. (infilling fractures?)
- 2460 - 2480' Dolomite - brownish grey - some dark streaks, as above.
- 2480 - 2490' Dolomite - brownish grey, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty.
- 2490 - 2500' Dolomite - greyish brown, very fine to fine crystalline, dense, argillaceous, silty.
- 2500 - 2510' Dolomite - light greyish brown, very fine to fine crystalline, slight intercrystalline porosity, slightly argillaceous, silty, some secondary dolomite
- 2510 - 2540' Dolomite - greyish brown, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty.
- 2540 - 2580' Dolomite - light greyish brown - as above, slight intercrystalline and scattered vuggy porosity, argillaceous, silty, scattered white coarse crystals of dolomite (druses).
- 2580 - 2590' Dolomite - very light buff, very fine to medium crystalline, slight intercrystalline porosity, slightly silty.
- 2590 - 2610' Dolomite - greyish brown, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty.
- 2610 - 2620' Dolomite - greyish brown - some dark streaks, very fine crystalline, dense, argillaceous, silty.
- 2620 - 2700' Dolomite - greyish brown, very fine to fine crystalline, streaky slight intercrystalline and vuggy porosity - scattered dolomite rhombs, silty, slightly argillaceous, some scattered fractures filled with secondary dolomite.
- 2700 - 2720' Dolomite - greyish brown, microcrystalline to very fine crystalline - streaks of microsucrose with streaky slight intercrystalline porosity, argillaceous, silty.
- 2720 - 2740' Dolomite - brownish grey, microcrystalline to very fine crystalline, dense - some light buff microsucrosic streaks with slight intercrystalline porosity - noneffective, silty and sandy, abundant calcite crystals and some dolomite rhombs infilling fractures, trace of quartz crystals.
- 2740 - 2780' Dolomite - light buff - microsucrose and light greyish brown - microcrystalline to very fine crystalline; streaky slight intercrystalline porosity - noneffective, silty, argillaceous, some scattered calcite crystals, trace of quartz crystals and dolomite rhombs.

- 2780 - 2790' Dolomite - buff, microcrystalline to very fine crystalline, dense, silty.
- 2790 - 2800' Dolomite - light greyish brown, microcrystalline to very fine crystalline, tight, silty, some scattered inclusions of calcite crystals, rare quartz crystals.
- 2800 - 2850' Dolomite - greyish brown - light streaks, microcrystalline to fine crystalline, tight, silty, some scattered inclusions of calcite crystals.
- 2850 - 2880' Dolomite - brownish grey, microcrystalline to fine crystalline, dense for the most part - scattered blind vugs with coarse dolomite druses, silty, slightly argillaceous, some scattered fractures filled with secondary dolomite.
- 2880 - 2890' Dolomite - brownish grey, microcrystalline to fine crystalline, dense - scattered vugs partially to completely infilled with secondary dolomite, silty, argillaceous.
- 2890 - 2910' Dolomite - buff, microcrystalline to fine crystalline, slight intercrystalline porosity, rare drusy vugs, rare quartz crystals, some loose calcite and secondary dolomite crystals, argillaceous, silty (very fine).
- 2910 - 2920' Dolomite - greyish brown, microcrystalline to fine crystalline, dense, rare scattered vugs, argillaceous, silty, loose calcite crystals (fractures?).
- 2920 - 2940' Dolomite - as above slight scattered vuggy porosity - secondary dolomite druses.
- 2940 - 2950' Dolomite - as above, some light colored streaks and patches, slight vuggy porosity
- 2950 - 2970' Dolomite - greyish brown, microcrystalline to fine crystalline - sucrosic in part, streaky slight intercrystalline and scattered vuggy porosity, argillaceous, silty, scattered fractures filled with crystalline calcite, secondary dolomite druses.
- 2970 - 2990' Dolomite - as above, numerous fractures indicated by abundant loose white coarse calcite crystals, streaky slight intercrystalline and vuggy porosity, dolomite druses.
- 2990 - 3000' Dolomite - greyish brown, microcrystalline to fine crystalline, slight intercrystalline and vuggy porosity, coarse secondary dolomite rhombs partially to completely infilling scattered vugs, trace of quartz crystals, trace of milky chert, argillaceous, silty, some scattered fractures infilled with calcite.
- 3000 - 3010' Dolomite - light greyish brown, microcrystalline to fine crystalline, dense, some scattered fractures filled with calcite.
- 3010 - 3020' Dolomite - light buff, microcrystalline to fine crystalline, dense, silty, some scattered fractures filled with calcite.

- 3020 - 3050' Dolomite - light brownish and greenish grey, microcrystalline to fine crystalline, dense, fractures filled with calcite, a few vugs with druses of secondary dolomite, some finely disseminated pyrite.
- 3050 - 3060' Dolomite - very light greyish brown to buff, microcrystalline to fine & some medium crystalline, slight scattered vuggy porosity - druses of secondary dolomite, some fractures filled with calcite, trace of pyrobitumen.
- 3060 - 3100' Dolomite - light greyish brown, very fine to coarse crystalline, slight to poor intercrystalline and vuggy porosity, scattered slightly argillaceous streaks, some scattered pyrite.
- 3100 - 3120' Dolomite - very light to light grey - brownish in part, microcrystalline to medium crystalline, dense, a few fractures filled with calcite.
- 3120 - 3140' Dolomite - light greyish brown, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity, loose dolomite rhombs.
- 3140 - 3160' Dolomite - as above, very light buff in part, microcrystalline to coarse crystalline, a few streaks of medium dark brownish grey, very fine crystalline dolomite; a few slightly argillaceous streaks - some pyrite.
- 3160 - 3190' Dolomite - very light to light grey - brownish in part, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity, trace of green waxy shale, rare scattered glauconite.
- 3190 - 3210' Dolomite - very light grey, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity, milky & a very light bluish grey chert, trace of quartz crystals, some scattered pyrite.
- 3210 - 3230' Dolomite - very light to light brownish grey, microcrystalline to coarse crystalline, slight to poor intercrystalline and vuggy porosity, rare scattered glauconite, silty.
- 3230 - 3240' Dolomite - light grey, very fine to coarse crystalline, slight intercrystalline and small vuggy porosity - very good cavernous porosity (Kelly dropped five feet) trace of glauconite.
- 3240 - 3250' Dolomite - light grey - brownish in part, very fine to coarse crystalline, slight to poor intercrystalline and vuggy porosity, scattered pyrite.
- 3250 - 3260' Dolomite - as above, some dark streaks of microcrystalline to very fine crystalline dolomite - silty and argillaceous, some quartz crystals.

- 3260 - 3280' Dolomite - light grey - brownish in part, very fine to coarse crystalline, slight intercrystalline and vuggy porosity, siliceous in part, very light grey chert, some quartz crystals, trace of bright green shale, scattered pyrite.
- 3280 - 3290' Dolomite - as above, abundant very light grey to milky chert, quartz crystals.
- 3290 - 3400' Dolomite - light greyish brown, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity - some cavernous porosity at 3380', light grey chert, siliceous in part, quartz crystals, some scattered pyrite.
- 3400 - 3410' Dolomite - as above (trip sample)
- 3410 - 3440' Dolomite - light greyish brown, very fine to coarse crystalline, scattered slight intercrystalline and vuggy porosity, cherty - light grey.
- 3440 - 3520' Dolomite - buff to light greyish brown, as above, a few quartz crystals, cherty.
- 3520 - 3560' Dolomite - buff, very fine crystalline to coarse crystalline, scattered slight intercrystalline and vuggy porosity, cherty.
- 3560 - 3570' Dolomite - as above and dolomite - medium to dark grey - slightly brownish, microcrystalline to very fine crystalline, dense, argillaceous, streaks of dark grey to black chert, some streaks of sandy dolomite - light grey, very fine crystalline, dense, very silty to sandy (very fine grained) - grading to a dolomitic sandstone, finely disseminated pyrite.
- 3570 - 3580' Dolomite - medium to dark grey with light grey silty to sandy streaks as above.
- 3580 - 3630' Dolomite - light buff to light greyish brown, very fine to medium crystalline, streaky, slight intercrystalline and vuggy porosity, silty, very light grey chert, some quartz crystals.
- 3630 - 3650' Dolomite - light buff, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, silty, some light grey chert, some quartz crystals.
- 3650 - 3670' Dolomite - light buff, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, silty.
- 3670 - 3690' Dolomite - as above, trace of light grey chert & quartz crystals.
- 3690 - 3700' Dolomite - as above, quartz crystals and very light grey chert - faint outline of oolites.
- 3700 - 3710' Dolomite - light buff to light greyish brown, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, quartz crystals, trace of very light grey chert.

- 3710 - 3750' Dolomite - very light buff, as above.
- 3750 - 3790' Dolomite - very light buff - brownish in part, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, quartz crystals.
- 3790 - 3800' Dolomite - very light buff, trace of reddish streaks, microcrystalline to medium crystalline, slight to poor intercrystalline porosity, silty, siliceous in part, very light grey to milky chert, quartz crystals.
- 3800 - 3820' Dolomite - very light grey and buff, very fine to medium crystalline, streaky slight intercrystalline porosity, silty, some quartz crystals, trace of very light grey chert.
- 3820 - 3850' Dolomite - very light buff - brownish in part, microcrystalline to coarse crystalline, streaky, slight intercrystalline and vuggy porosity, silty, siliceous in part, some very light grey chert & rare streaks of medium to dark grey chert, some quartz crystals.
- 3850 - 3860' Dolomite - very light grey - brownish in part, very fine to medium crystalline dense, some streaks - greyish brown - microcrystalline to very fine crystalline, argillaceous, silty, tight; trace of milky and medium to dark grey chert - banded in part.
- 3860 - 3880' Dolomite - as above, some very light grey chert, some quartz crystals.
- 3880 - 3890' Dolomite - very light grey - slightly brownish in part, microcrystalline to medium crystalline, dense, silty, siliceous in part, some chert - light to very light grey, quartz crystals.
- 3890 - 3920' Dolomite - very light grey - slightly brownish in part, microcrystalline to medium crystalline, dense, silty, very cherty - very light grey (faint outline of oolites) siliceous in part, quartz crystals, trace of gypsum crystals.
- 3920 - 3950' Dolomite - as above - chert becoming slightly darker in color.
- 3950 - 3970' Dolomite - light greyish brown, microcrystalline to medium crystalline, dense, silty, abundant very light grey to very light greyish brown oolitic chert, some loose calcite crystals.
- 3970 - 3990' Dolomite - very light greyish brown, microcrystalline to medium crystalline, dense, silty, very light grey chert, some quartz crystals.
- 3990 - 4020' Dolomite - very light buff, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, some light colored chert - oolitic in part, quartz crystals.

- 4020 - 4040' Dolomite - very light buff, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, some light colored chert, some quartz crystals.
- 4040 - 4090' Dolomite - very light buff, microcrystalline to medium crystalline, slight intercrystalline porosity - dense streaks, some very light grey chert, some quartz crystals.
- 4090 - 4120' Dolomite - very light buff to very light greyish brown, microcrystalline to medium crystalline, some medium greyish brownish streaks - microcrystalline to very fine crystalline, slightly argillaceous, silty; streaky - slight intercrystalline porosity, slightly cherty - oolitic in part, some quartz crystals.
- 4120 - 4180' Dolomite - very light to medium greyish brown, microcrystalline to fine crystalline, dense, silty, argillaceous streaks, some very light grey chert, some quartz crystals, some loose calcite crystals.
- 4180 - 4210' Dolomite - very light to medium greyish brown, microcrystalline to fine crystalline, dense, silty, argillaceous streaks, cherty - very light grey to dark grey, some loose calcite crystals, some quartz crystals.
- 4210 - 4230' Dolomite - as above - abundant quartz crystals, slight vuggy porosity.
- 4230 - 4280' Dolomite - very light to medium greyish brown, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, argillaceous streaks, quartz crystals, some cherty streaks - very light brownish grey to dark grey.
- 4280 - 4290' Dolomite - very light grey - slightly brownish - some dark streaks, microcrystalline to fine crystalline, dense, for the most part, some scattered small vugs, silty, quartz crystals.
- 4290 - 4300' Dolomite - brownish grey - light streaks, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, argillaceous streaks, quartz crystals, some very light to dark grey chert.
- 4300 - 4370' Dolomite - grey - very light in part - slightly brownish, microcrystalline to fine crystalline, slight streaky intercrystalline porosity, silty, argillaceous in part, slightly cherty, few quartz crystals.
- 4370 - 4390' Dolomite - as above, few partings of dark grey shale.
- 4390 - 4430' Dolomite - very light buff, microcrystalline to medium crystalline, slight intercrystalline porosity, trace of scattered vugs, silty, pyritic in part, trace of light colored chert and quartz crystals.

- 4430 - 4490' Dolomite - very light to light grey, slightly brownish, some dark streaks, microcrystalline to coarse crystalline, streaky slight intercrystalline porosity, silty, slightly cherty, some scattered pyrite, some scattered partings of greyish green shale and dark grey shale - bituminous in part.
- 4490 - 4500' Dolomite - medium brownish grey - some light streaks microcrystalline to medium crystalline, tight, silty, argillaceous, rare light colored chert & quartz crystals, scattered pyrite.
- 4500 - 4510' Dolomite - very light grey - brownish - some dark streaks microcrystalline to medium crystalline, slight intercrystalline porosity, silty, argillaceous streaks, some quartz crystals, scattered pyrite, trace of shale partings.
- 4510 - 4540' Dolomite - very light greyish brown, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, slightly cherty - oolitic in part, some quartz crystals.
- 4540 - 4550' Dolomite - as above - some darker colored streaks.
- 4550 - 4570' Dolomite - greyish brown - microcrystalline to fine crystalline, tight, argillaceous, silty, some partings of dark grey shale, some scattered pyrite.
- 4570 - 4580' Dolomite - brownish grey, microcrystalline to fine crystalline, tight, silty.
- 4580 - 4650' Dolomite - greyish brown, microcrystalline to fine crystalline, tight, silty, argillaceous, some partings of dark grey and black bituminous shale.
- 4650 - 4670' Dolomite - light brownish grey, microcrystalline to fine crystalline, tight, silty, slightly argillaceous.
- 4670 - 4720' Dolomite - light to medium greyish brown, microcrystalline to fine crystalline, tight, silty, argillaceous, some scattered fractures filled with crystalline calcite, scattered shale partings.

- 4720 - 4740' Dolomite - very light grey to greyish brown - rare reddish streaks, microcrystalline to coarse crystalline, slight vuggy and intercrystalline porosity, silty, argillaceous streaks, some dark grey shale partings - some dark reddish coloration, trace of light grey chert and quartz crystals.
- 4740 - 4770' Dolomite - greyish brown, microcrystalline to fine crystalline, tight, silty, argillaceous, some partings of black bituminous shale and dark grey shale.
- 4770 - 4780' Dolomite - light to medium greyish brown - some streaks of very light grey, microcrystalline to fine crystalline, streaky - slight intercrystalline porosity, shale partings - dark grey - some rare purple streaks.
- 4780 - 4800' Dolomite - greyish brown, microcrystalline to fine crystalline tight, silty, argillaceous.
- 4800 - 4810' Dolomite - as above - some dolomite - very light grey to brownish grey, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity - dense streaks, silty, argillaceous in part, rare quartz crystals.
- 4810 - 4830' Dolomite - very light grey, microcrystalline to very fine crystalline, streaky slight intercrystalline porosity silty (very fine).
- 4830 - 4840' Dolomite - very light to medium greyish brown, microcrystalline to medium crystalline, streaky slight intercrystalline porosity, silty, argillaceous in part.
- 4840 - 4850' Dolomite - very light grey - slightly brownish - some dark streaks, microcrystalline to medium crystalline, slight intercrystalline porosity, slightly argillaceous in part..
- 4850 - 4860' Dolomite - as above - increase in darker streaks, streaky, slight intercrystalline porosity, argillaceous in part.
- 4860 - 4880' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline, tight, argillaceous, silty, some partings of dark grey shale.
- 4880 - 4920' Dolomite - light to medium greyish brown, microcrystalline to medium crystalline, streaky - slight intercrystalline porosity, silty, argillaceous in part, partings of dark grey shale.
- 4920 - 4930' Dolomite - greyish brown - some dark streaks, microcrystalline to fine crystalline, tight, silty, argillaceous.
- 4930 - 4980' Dolomite - light to medium greyish brown, microcrystalline to medium crystalline, streaky - slight intercrystalline porosity, silty, argillaceous in part, scattered partings of dark grey shale.

- 4980 - 5010' Dolomite - as above, microcrystalline to fine crystalline.
- 5010 - 5030' Dolomite - very light buff, microcrystalline to fine crystalline, slight intercrystalline porosity, some scattered argillaceous streaks.
- 5030 - 5050' Dolomite - as above - some greyish brown streaks, a band of slightly greenish grey dolomite - microcrystalline to very fine crystalline, silty, dense.
- 5050 - 5060' Dolomite - very light grey - brownish in part to greyish brown, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, some silty and argillaceous streaks.
- 5060 - 5070' Dolomite - as above - partings of black bituminous shale.
- 5070 - 5110' Dolomite - very light grey to greyish brown, microcrystalline to fine crystalline, trace of slight intercrystalline porosity, silty and argillaceous streaks, trace of dark grey chert at 5090'
- 5110 - 5140' Dolomite - very light grey - brownish in part to light greyish brown, microcrystalline to very fine and some fine crystalline, tight, trace of very light grey to light brown chert at the top.
- 5140 - 5150' Dolomite - light to medium grey - some dark streaks - brownish in part, microcrystalline to fine crystalline, tight, silty and argillaceous, trace of very thin streaks of very light grey chert.
- 5150 - 5180' Dolomite - very light brownish grey to greyish brown, microcrystalline to very fine crystalline, tight, silty.
- 5180 - 5220' Dolomite - very light grey - slightly brownish in part, microcrystalline to very fine crystalline, dense, silty.
- 5220 - 5230' Dolomite - as above - greyish brown in part, some partings of dark grey shale.
- 5230 - 5240' Dolomite - greyish brown - very light in part - dark in part, microcrystalline to very fine crystalline, tight, silty, slightly argillaceous in part.
- 5240 - 5280' Dolomite - greyish brown, microcrystalline to fine crystalline, trace of slight intercrystalline porosity, silty, argillaceous.
- 5280 - 5300' Dolomite - very light buff - some greyish brown, microcrystalline to fine crystalline, trace of slight intercrystalline porosity, silty, some partings of black bituminous shale.
- 5300 - 5310' Dolomite - very light grey to greyish brown, microcrystalline to very fine crystalline, tight, silty, argillaceous streaks.

- 5310 - 5340' Dolomite - very light grey, very fine crystalline, slight intercrystalline porosity, silty.
- 5340 - 5350' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline, tight, argillaceous, silty.
- 5350 - 5370' Dolomite - as above - some light brownish grey.
- 5370 - 5450' Dolomite - very light to medium grey - brownish in part, microcrystalline to very fine crystalline, dense, silty, some partings of black bituminous shale and dark grey shale.
- 5450 - 5480' Dolomite - light grey - grey, microcrystalline, dense, silty, some partings of greenish grey and black bituminous shale.
- 5480 - 5500' Dolomite - as above, some rare faint reddish streaks.
- 5500 - 5520' Dolomite - light to dark grey, brownish, microcrystalline to very fine crystalline, dense, silty, argillaceous streaks, scattered shale partings, trace of quartz crystals.
- 5520 - 5580' Dolomite - light to dark grey, microcrystalline to very fine crystalline, dense, few scattered blind vugs, banded in part, silty, argillaceous in part, trace of inclusions of gypsum, some partings of black bituminous shale.
- 5580 - 5590' Dolomite - medium to dark grey, microcrystalline to very fine crystalline, dense, silty, argillaceous, some thin interbeds of dark grey and greenish grey shale - hard, brittle, dolomitic.
- 5590 - 5620' Dolomite - light to medium grey - brownish in part, microcrystalline to very fine and some fine crystalline, dense, argillaceous, silty, some scattered pyrite, interbedded greenish grey dolomitic shale, trace of gypsum crystals.
- 5620 - 5630' Dolomite - as above, streaks of very light grey dolomite - microcrystalline to very fine crystalline - chalky in part.
- 5630 - 5640' Dolomite - light to medium greyish brown - rare reddish streaks, microcrystalline to very fine crystalline, dense, silty, argillaceous, some thin interbeds of greenish grey dolomitic shale.
- 5640 - 5650' Dolomite - as above; dolomite - light grey - reddish streaks, dense, argillaceous, trace of floating quartz grains.
Shale - greenish grey and maroon.
- 5650 - 5660' Dolomite - light brownish grey, microcrystalline, dense.
- 5660 - 5670' Dolomite - brownish grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, thin interbedded greenish grey shale.

Cambrian 5675' (E-Log 5665')

- 5670 - 5710' Dolomite - reddish and greenish grey, microcrystalline to very fine crystalline, dense, very silty, argillaceous
Shale - maroon and greyish green, hard, blocky, micromicaceous.
- 5710 - 5730' Dolomite - pink to red, and greenish grey, microcrystalline to very fine crystalline - chalky in part, silty, argillaceous, a trace of anhydrite.
Shale - maroon and greyish green, blocky, micromicaceous.
- 5730 - 5740' Shale - maroon, fissile to blocky, micromicaceous, some streaks of dolomite.
- 5740 - 5760' Shale - maroon & greyish green, fissile to blocky, micromicaceous.
Dolomite - very light grey - pink & brownish in part tight, microcrystalline to very fine crystalline, silty, some sandy streaks, trace of quartzite.
- 5760 - 5780' Dolomite - grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, some sandy streaks.
Shale - maroon and green, micromicaceous.
- 5780 - 5800' Shale - greenish grey - some maroon streaks, fissile to blocky, micromicaceous, some streaks of dolomite.
- 5800 - 5820' Shale - as above
Dolomite - grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, trace of quartz crystals, trace of gypsum.
- 5820 - 5850' Dolomite - as above.
Shale - greenish grey & maroon, fissile to blocky, micromicaceous.

Salt 5850' (E-Log 5842')

- 5850 - 5890' Salt - with shaly streaks, thin interbeds and streaks of dolomite, some slightly brownish grey anhydrite (salt not recovered in samples)
- 5890 - 5910' Samples Missing - no recovery.
- 5910 - 5920' Dolomite - grey, microcrystalline to very fine crystalline, dense, pelletoid in part, silty, some streaks of maroon and greyish green shale.
Salt - (no recovery in samples)
- 5920 - 6080' Salt - (no recovery - except 6080' sample) thin interbeds and streaks of dolomite, shale laminae, minor anhydrite and gypsum.

Base of Salt 6084' (E-Log 6087')

- 6080 - 6090' Salt - (no recovery)
Dolomite - grey, microcrystalline, dense, earthy in part, silty some scattered salt casts.

- 6090 - 6100' Dolomite - grey - slightly brownish, microcrystalline - earthy for the most part, tight, argillaceous, silty, some scattered salt casts.
- 6100 - 6110' Shale - greyish green - fine white specks, fissile to blocky, micromicaceous, slightly dolomitic, some fine veins of gypsum.
- 6110 - 6120' Shale - medium grey - trace of white specks, brittle, micromicaceous, slightly dolomitic, some streaks of dolomite - light grey, microcrystalline to very fine crystalline, tight.
- 6120 - 6150' Shale - medium grey - some greyish green and reddish streaks, brittle, micromicaceous, slightly dolomitic, some streaks of dolomite - grey to brownish grey and pink to reddish grey, microcrystalline to very fine crystalline, tight - silty and sandy streaks.
- 6150 - 6170' Shale - with interbedded dolomite as above - ochre cast in part.
- 6170 - 6190' Shale - greenish and brownish grey, brittle, micromicaceous, some interbedded dolomite - light grey to greenish and reddish grey, very fine to fine crystalline, dense, silty and sandy streaks, trace of floating quartz grains.
- 6190 - 6210' Dolomite - medium to dark grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, shale streaks, very cherty - milky and brownish grey - oolitic in part, trace of quartzite, trace of gypsum crystals.
- 6210 - 6220' Dolomite - brownish grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, some shale streaks, some inclusions of anhydrite and gypsum (also infilling fine fractures).
- 6220 - 6270' Dolomite - medium grey, microcrystalline to fine crystalline, dense, very argillaceous, silty, shale streaks, pyritic in part, scattered blebs of anhydrite, few gypsum crystals, trace of salt casts.
- 6270 - 6280 Dolomite - as above
Shale - medium grey and greenish grey, fissile to blocky, micromicaceous, slightly dolomitic.
- 6280 - 6320' Dolomite - medium grey, microcrystalline to very fine and some fine crystalline, dense, very argillaceous, very shaly, silty, few scattered blebs of anhydrite, trace of gypsum.
- 6320 - 6330' Dolomite - as above - some lighter brownish streaks.
- 6330 - 6380' Dolomite - medium to dark grey, microcrystalline, dense, very argillaceous and silty, shaly streaks, scattered blebs of anhydrite, trace of salt casts.
- 6380 - 6390' Dolomite - medium grey - slight greenish cast, microcrystalline to very fine crystalline, dense, very argillaceous

- 6380 - 6390'
(cont'd) and silty, shaly, some anhydrite and gypsum.
- 6390 - 6410' Dolomite - grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, shale streaks, scattered glauconite, pyritic in part, scattered blebs and thin interbeds of anhydrite.
- 6410 - 6420' Dolomite - medium to dark brownish grey, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty, shale streaks, glauconite & pyrite.
Proterozoic 6420' (E-Log 6428')
- 6420 - 6440' Dolomite - very light grey - brownish - greenish - pinkish in part, microcrystalline to very fine crystalline - chalky in part, streaky slight intercrystalline porosity, some scattered quartz crystals, pyritic in part, glauconitic in part, some blebs and thin streaks of anhydrite, sandy streaks, thin cherty streaks, trace of oolitic texture, some streaks of maroon and green shale.
- 6440 - 6450' Dolomite - as above; dolomite - light greyish brown, microcrystalline to very fine crystalline, dense.
- 6450 - 6470' Dolomite - very light grey, to light greyish brown - some reddish streaks and patches, microcrystalline to fine crystalline, streaky, slight intercrystalline porosity, trace of oolitic texture, scattered inclusions of gypsum crystals, scattered pyrite.
- 6470 - 6490' Dolomite - as above; dolomite - medium dark brownish grey, microcrystalline to fine crystalline, dense, argillaceous, streaks of greenish grey shale, silty, sandy streaks, glauconitic, inclusions of gypsum.
- 6490 - 6520' Dolomite - greyish brown some scattered red spots and patches, microcrystalline to very fine crystalline, dense, slightly pyritic in part, some inclusions of gypsum & dolomite rhombs, some blebs of anhydrite, silty and sandy, trace of chert.
- 6520 - 6530' Dolomite - as above - increase of red patches & streaks.
- 6530 - 6590' Dolomite - greyish brown with red streaks and patches, as above.
- 6590 - 6620' Dolomite - light to medium greyish brown, a few reddish streaks microcrystalline to very fine crystalline, dense, silty, slightly cherty, some dolomite rhombs, siliceous streaks, trace of salt casts, trace of quartz crystals.
- 6620 - 6640' Dolomite - greyish brown - pink to reddish patches - some dark streaks, microcrystalline to very fine crystalline, dense, silty, trace of quartz crystals, some dolomitic rhombs lining and infilling scattered vugs, streaks of greenish grey and some maroon shale, trace of light grey anhydrite, trace of oolitic texture.

- 6640 - 6650' Dolomite - as above - fewer reddish patches.
- 6650 - 6670' Dolomite - light brownish grey to greyish brown - some reddish patches, microcrystalline to fine crystalline, dense, slightly silty, cherty - smoky to light greyish brown, some streaks of medium brownish grey dolomite with granules of glauconite. Some dolomite rhombs, some scattered pellets of medium brownish grey dolomite.
- 6670 - 6710' Dolomite - light brownish grey to greyish brown - some pink and red streaks, microcrystalline to fine crystalline, dense, slightly silty, trace of quartz crystals, some dolomite rhombs, trace of light brownish grey anhydrite, some interbedded greyish green shale, some partings of black bituminous shale.
- 6710 - 6730' Dolomite - very light grey to greyish brown - pink and red streaks and patches, microcrystalline to fine crystalline, dense, few scattered vugs partially to completely infilled with secondary dolomite, some shale streaks, trace of salt casts.
- 6730 - 6740' Dolomite - very light grey to light and dark greyish brown, some pink and red streaks, microcrystalline to fine crystalline, dense, scattered blind vugs partially to completely infilled with secondary dolomite, silty, argillaceous streaks & shale streaks, trace of anhydrite, trace of salt casts, trace of green siltstone.
- 6740 - 6840' Dolomite - very light to medium greyish brown - pink to red streaks and patches, microcrystalline to very fine crystalline, dense, silty, some secondary dolomite infilling vugs, trace of anhydrite, trace of quartz crystals, slightly cherty - greyish brown, some streaks of greyish green shale & dull grey soft shale, some thin streaks of greyish brown anhydrite, trace of salt casts, brecciated in part (along edge of infilled fractures), trace of gypsum, trace of faint pellets.
- 6840 - 6860' Dolomite - as above - trace of green siltstone, slight increase in salt casts.
- 6860 - 6870' Dolomite - very light to medium greyish brown - pink to red streaks and patches - some dark greyish brown - argillaceous streaks, microcrystalline to fine crystalline, dense, silty, secondary dolomite, streaks of anhydrite and gypsum, trace of quartz crystals.
- 6870 - 6890' Dolomite - very light buff - brown, pink and red in part, microcrystalline to fine crystalline, dense, slightly silty, secondary dolomite infilling vugs, streaks of anhydrite and gypsum, streaks of dull grey, soft shale, scattered salt casts.

- 6890 - 6910' Dolomite - light to medium greyish brown - pink to red streaks and patches - as above.
- 6910 - 6920' Dolomite - as above - granular in part with streaky slight intercrystalline porosity.
- 6920 - 6950' Dolomite - dense, as above.
- 6950 - 6960' Dolomite - very light to medium greyish brown - some dark streaks - pink to red streaks and patches, microcrystalline to fine crystalline, dense, trace of oolites, some argillaceous streaks, white medium crystalline secondary dolomite rhombs infilling vugs, abundant shaly streaks - dull grey to medium dark grey and some greyish green, some salt casts, trace of anhydrite & gypsum, some scattered fractures infilled with dolomite.

F.T.D. -- 6961'

DRILL STEM TEST REPORT

- 29

Company Candell Oil Company Drill Stem Test No. 1

Name of Well Candell Mobil et al Iroquois I-11-67-50- Date Test Run May 2, 1972
B.J. Services 129-30 Operator Mal Moscrip

Testing Company Bob Tail Size Packer(s) 7 1/2" Choke 1/2"

Type Packer Bob Tail Interval Tested: 900' to 1010' Formation: Gossage (Bear Rock)

Test Data: Preflow: Time Tool Opened 7:33 a.m. Time Tool Closed 7:38 a.m. (elapsed) 5 mins.
 Initial shut in: Time ~~Packer set~~ ^{Tool Closed} 7:38 a.m. Time Tool Opened 8:38 a.m. (elapsed) 60 mins.
 Flow Period: Time Tool Opened 8:38 a.m. Time Tool Closed 10:08 a.m. (elapsed) 90 mins.
 Final shut in: Time Tool Closed 10:08 a.m. Time Tool Pulled 11:38 a.m. (elapsed) 90 mins.

Tight Hole Test: Yes No X Size of Chamber

Water Cushion: No Type of Hole: (Rathole) (Fullhole) (Cased)

T.D. Driller: 1010' T.D. Tester: 1010' Was Test A Misrun: No

Cause of Misrun:

Flow Data:

Description of Initial Blow: Weak initial puff - weak air blow

Did Blow die or Decrease: died in 15 minutes

Flow To Surface In mins. Initial Gas Flow MCF/Day

Stabilized Gas Flow MCF/Day Measured by: (Test) (Impact) (Side Static)

Time For Gas Flow to Stabilize mins. Gas Description: (Sweet) (Sour) (Dry) (Wet)

Gas Sample Saved After mins. Fluid To Surface In mins.

Fluid Description:

Nature of Flow:

Remarks:

Recovery:

Total fluid in (size) Collars (2-7/8" ID) 447' OD drill pipe: (3 1/2" I.F.) 443 feet Total 890'

(describe fluid) Oil: feet barrels

90' fresh water & 800' sulphurous fresh Water: feet barrels

 Mud: feet barrels

Saved Samples At: Top ft. Middle ft. Top ft. of above the test tool

Weight of mud before test lbs./gal.: Chloride content ppm

Weight of mud recovered lbs./gal.: Chloride content ppm

Weight of water recovered lbs./gal.: Chloride content ppm

Oil Recovered: *API Color Smell

Pressure Data: Recorder No. 5773 Top @ 882'

Initial Hydrostatic: (Office) (Field) 385 psi Final: (Office) (Field) 385 psi

Initial Shut In Pressure 355 psi Final: 355 psi

Initial Flow Pressure 40 psi Final: 315 psi

Well Bore Temp: 80 °F Bomb Capacity: Top 1100 Bottom 1200

Engineer T.A.D. Haddow

DRILL STEM TEST REPORT

- 30

Company CanDel Oil Company Drill Stem Test No. 2

Name of Well CanDel Mobil et al Iroquois I-11-67-50-129-30 Date Test Run May 5, 1972

Testing Company B.J. Services Operator Mel Moscrip

Type Packer Bob Tail Size Packer(s) 7 1/2" Choke 1/2"

Interval Tested: 2121' to 2261' Formation: Ronning

Test Data: reflow: Time Tool Opened 4:15 p.m. Time Tool Closed 4:20 p.m. (elapsed) 5 mins.
 Initial shut in: Time Tool Closed 4:20 p.m. Time Tool Opened 4:50 p.m. (elapsed) 30 mins.
 Flow Period: Time Tool Opened 4:50 p.m. Time Tool Closed 5:50 p.m. (elapsed) 60 mins.
 Final shut in: Time Tool Closed 5:50 p.m. Time Tool Pulled 6:50 p.m. (elapsed) 60 mins.

Tight Hole Test: Yes No X Size of Chamber

Water Cushion: No Type of Hole: (Rathole) (Fullhole) (Cased)

T.D. Driller: 2261' T.D. Tester: 2261' Was Test A Misrun: No

Cause of Misrun:

Flow Data:
 Description of Initial Blow: Weak I.P. Weak A.B.
 Did Blow die or Decrease: decreased slightly throughout

Flow To Surface In mins. Initial Gas Flow MCF/Day

Stabilized Gas Flow MCF/Day Measured by: (Test) (Impact) (Side Static)

Time For Gas Flow to Stabilize mins. Gas Description: (Sweet) (Sour) (Dry) (Wet)

Gas Sample Saved After mins. Fluid To Surface In mins.

Fluid Description:

Nature of Flow:

Remarks:

Recovery:
 Drill Collars (2-7/8" ID) 447' OD drill pipe: (3 1/2" I.F.) 853 feet Total 1300' barrels
 Total fluid in (size) Oil: feet barrels
 (describe fluid) Water: feet barrels
 90' fresh water and 1210' sulphurous fresh water: feet barrels
 Mud: feet barrels

Saved Samples At: Top ft. Middle ft. Top ft. of the test tool

Weight of mud before test lbs./gal.: Chloride content ppm
 Weight of mud recovered lbs./gal.: Chloride content ppm
 Weight of water recovered lbs./gal.: Chloride content ppm
 Oil Recovered: API Color Smell

Pressure Data: Recorder No. 5979 Bottom-2138'

Initial Hydrostatic: (Office) (Field) 915 Final: (Office) (Field) 915
 Initial Shut In Pressure 890 Final: 890
 Initial Flow Pressure 190 Final: 610
 Well Bore Temp: 84 °F Bomb Capacity: Top 1100# Bottom 1200#

Engineer T.A.D. Haddow

DRILL STEM TEST REPORT

- 31

Company Candel Oil Company Drill Stem Test No. 3

Name of Well Candel Mobil et al Iroquois I-11-67-50-129-30 Date Test Run June 2, 1972

Testing Company B.J. Services Operator Leo Penner

Type Packer Bob Tail Size Packer(s) 7 1/2" Choke 1 1/2"

Interval Tested: 3200' to 3614' Formation: Runnig

Test Data:
 Preflow: Time Packer set: 9:20 p.m. Time Tool Opened: 9:25 p.m. (elapsed) 5 mins.
 Initial shut in: Time Packer set 9:30 p.m. M. Time Tool Opened 10:00 p.m. (elapsed) 30 mins.
 Flow Period: Time Tool Closed 10:00 p.m. M. Time Tool Closed 12:00 p.m. (elapsed) 120 mins.
 Final shut in: Time Tool Closed 12:00 p.m. M. Time Tool Pulled 4:00 a.m. (elapsed) 240 mins.

Tight Hole Test: Yes No Size of Chamber

Water Cushion: no Type of Hole: (Rathole) (Fullhole) (Cased)

T.D. Driller: 3614' (plug back) T.D. Tester: 3614' Was Test A Misrun: No

Cause of Misrun:

Flow Data:

Description of Initial Blow: Fair air blow

Did Blow die or Decrease: died in 120 minutes

Gas Flow To Surface In mins. Initial Gas Flow MCF/Day

Stabilized Gas Flow MCF/Day Measured by: (Test) (Impact) (Side Static)

Time For Gas Flow to Stabilize mins. Gas Description: (Sweet) (Sour) (Dry) (Wet)

Gas Sample Saved After mins. Fluid To Surface In mins.

Fluid Description:

Nature of Flow:

Remarks: Did not get sample of recovery as pump-through-feature sheared, however 3 quarts of sw recovered from bottom hole sampler (175,000 ppm of salt)

Recovery:

Total fluid in (size) Collars (2-7/8" ID) 450' OD drill pipe: (3 1/2" I.F.) 2370' feet Total 2820' barrels

(describe fluid) Oil: feet barrels

Water: feet barrels

Mud: feet barrels

Saved Samples At: ft. ft. ft. above the test tool

Weight of mud before test lbs./gal.: Chloride content ppm

Weight of mud recovered lbs./gal.: Chloride content ppm

Weight of water recovered lbs./gal.: Chloride content ppm

Oil Recovered: *API Color Smell

Pressure Data: Recorder No. 3689 Top @ 3468'

Initial Hydrostatic: (Office) (Field) 1660 Final: (Office) (Field) 1650

Initial Shut In Pressure 1340 Final: 1340

Initial Flow Pressure 490 Final: 1340

Well Bore Temp: 68 °F Bomb Capacity: Top Bottom

Engineer T.A.D. Haddow

CASING REPORT

- 32

Well CanDel Mobil et al Iroquois I-11 Date April 29, 1972
 Type of Casing String: (surface) (intermediate) (production) (liner) (other) _____
 Drilling Contractor Nabors Rig #8

PIPE DATA

Make of Casing Mannesmann
 Type: (seamless) (welded) Size _____ No. of Joints _____
 Weight 36# Grade J-55 Range 3 Threads ST & C
 Couplings: (short) (long) Minimum I.D. 9-5/8" Maximum O.D. _____

Casing Shoe: make _____ type _____ depth _____ ft.
 Cementing Collar: make _____ type _____ depth _____ ft.
 Centralizers: No. _____ Make and Type _____
 Depths _____
 Scratchers: No. _____ Make and Type _____
 Depths _____

Welding: (electric) (acetylene) No. of Collars? _____ Casing Shoe? _____

Total amount casing run	<u>724.91</u>	ft.	Kelly Bushing elevation	<u>418</u>	ft.
Amount pipe above K.B.	<u>20.91</u>	ft.	K.B. to Rotary Table		ft.
Depth Casing Shoe landed	<u>704</u>	ft.	R.T. to Derrick Floor		ft.
Top of casing below K.B.		ft.	D.F. to Ground Level		ft.
Amount of casing in hole		ft.	Ground Level elevation	<u>400</u>	ft.
Length of Landing Joint		ft.	G.L. to (casing bowl) to (casing collar)		ft.
Length of Cut off Joint		ft.	Csg. Bowl Flange Elev.		ft.
Length of Shoe Joint overall		ft.	K.B. to top of casing		ft.

CEMENTING DATA

Time Hole Open Before Casing Started in Hole _____ hrs.
 Casing Started in Hole _____ M. Casing in _____ M. (elapsed) _____ hrs.
 Circulating: Started _____ M. Finished _____ M. (elapsed) _____ hrs.
 Mixing Cement: Started _____ M. Finished _____ M. (elapsed) _____ min.
 Displacing: Started _____ M. Plug Down 12:04 p.m. (elapsed) _____ min.

Maximum Displacement Pressure _____ psi. Final Pressure _____ psi.
 Plug Displaced to _____ ft. Displacement Fluid: (mud) (water) (other) _____
 Method of Displacement with water
 Method of Cementing _____
 Amount Cement Used 350 Sacks. Average Cement Slurry Weight _____ lbs./gal.
 Kind of Cement: (Canadian) (American) (bulk) (sack): Weight per sack _____ lbs.
 Estimated Amount Cement Returns 16 bbls. sacks. Time Cement to Set _____ hrs.
 Was Pipe Worked During Circulating? _____ Cementing? _____ How Long _____
 Additives to Cement _____
 Cementing Company B-J Service Operator Mel Moscrip
 Casing Landed in _____ hrs. Well Head Make _____
 Remarks See summary of Well Data for information on conductor pipe.

Signed _____

BIT RECORD

Well: CanDel Mobil et al Iroquois 1-11-67-50-129-30

Date Spudded: 2:30 a.m. April 25, 1972 Date Finished Drilling:
May 28, 1972

Bit No.	Size	Make & Type	Serial	Depth In	Depth Out	Footage	Hours	Condition
1A	8-3/4	HW OSC 3J	23593	60	127	67	7½	3-2-1
2A	8-3/4	Smith DT2	37621	127	424	307	16½	5-2-1
3A	8-3/4	HW ODV	14702	424	750	326	25½	3-6-1
4A RR	8-3/4	Smith DT2	37621	750	819	69	5½	
5A	12¼	Reamer	845-F	78	704	626	20½	4-8-1
6	8-3/4	HW ODV	16694	819	1010	191	10	6-5-1
7	8-3/4	HW X55R	38833	1010	2141	1131	50 3/4	8-7-1
8	8-3/4	HW RRG2BX	WF216	2141	2261	120	10	6-5-1
9 RR	8-3/4	HW RRG2BX	WF216	2261	2671	410	32½	2-3-1
10	8-3/4	HW RRG2BX	ZL998	2671	3403	732	50 3/4	7-6-1
11	8-3/4	HW RRG2BX	WF001	3403	3815	412	24 3/4	4-4-1
12	8-3/4	HW RGIX	NB121	3815	4445	630	36½	4-8-1
13	8-3/4	HW RRGIX	RT487	4445	4946	501	36½	6-8-1
14	8-3/4	HW J-88	HH341	4946	5484	538	44	6-4-1
15	8-3/4	HW RRG1	DP954	5484	5628	144	26½	6-8-1
16	8-3/4	HW X55R	37892	5628	6119	491	45	6-8-1
17	8-3/4	HW X55R	38291	6119	6285	166	26	6-8-1
18	8-3/4	HW WD7	40025	6285	6350	65	13	6-5-1
19	8-3/4	HW X55R	31208	6350	6500	150	28½	6-8-1
20	8-3/4	HW X55R	38288	6500	6923	181	22	7-8-1
21	8-3/4	HW WD7	38284	6923	6961	38	4 3/4	2-2-1

DAILY MUD RECORD

- 34

Date 1972	Depth Feet	Weight	Viscosity	Water Loss	Filter Cake	Ph.	Remarks and Additives					
		# / Gal.	Seconds	15 min. C.C.	32nds		Bapi Gel	Lost drill Circulation	Material	Caustic Salt	Remarks & Misc.	
April 25	120	8.4	52				7000#					Spud at 2:30 a.m.
26	391		67				500#					
27	662		53				1000#					
28	819											Reaming surface hole
29	819											Running Csg.
30	819											W.O.C.
May 1	819											W.O.C.
2	1010	8.4	27				24#					
3	1356	8.4	28				20#					
4	1930	8.4	28				20#					
5	2222	8.4	28									
6	2373	8.4	28				8#					
7	2630	8.4	28				12#					
8	2872	8.4	28				16#					
9	3205	8.4	28				16#					
10	3403	8.4	28				20#	Fibre Seal 6 Sx.				Partial lost circulation at 3403'
11	3763	8.4	28				8#					
12	4090	8.4	28				12#					
13	4420	8.4	28					Sawdust 15 Sx.				Losing fluid to formation.
14	4686	8.4	28				4#	Sawdust 30 Sx.				
15	4946	8.4	28					(Sawdust 12 Sx				
								(Fibre Seal 8 Sx				
								(Quick Seal 6 Sx				
16	5214	8.4	28				4000#	(Fibre Seal 15 Sx				
								(Quick Seal 11 Sx	300			
								(Sawdust 14 Sx				
17	5468	8.5	32			10.5	3900#	(Sawdust 50 Sx				
								(Cotton	100	8000		Fluid loss
								(Hulls 75 Sx				10 - 12 bbls.
								(Quick Seal 25 Sx				per hour.
								(Cell-O-Seal 25 Sx				
18	5571	9.6	31			10.5		(Cotton				
								(Hulls 6Sx				
								(Fibre Seal 2 Sx				
								(Cell-O-Seal 12 Sx	100	4000		Inhibitor 10 gal.
												DeFoamer 7 gal
19	5668	9.7	31			10.5		Cell-O-Seal 2 Sx	300	3600		Inhibitor 5 gal
												DeFoamer 2 gal
20	5882	9.7	30		2			Cell-O-Seal 10 Sx				Losing 8 bbls.
								Fibre Seal 6 Sx	250	19,000		per hour.
21	6128	10.4	30							43,000		Inhibitor 4 gal.
22	6280	10.4	30			10.5			150	18,000		DeFoamer 2 gal
23	6350	10.3	30							10,000		
24	6429	10.3	30						200	12,000		Inhibitor 7 gal
25	6570	10.3	31							10,000		
26	6740	10.3	30			10.5				20,000		
27	6886	9.3	30			11.5			150			Inhibitor 5 gal
28	6961	10.3	30			10.5						Running Logs
29	6961	10.3	30			10.5				12,000		Losing 5 bbls/hr
30	6961	10.3	30			10.5		Fibre Seal 5 Sx		28,000		W.O.O.
31	6961											Running Plugs - no more additives.

DAILY PROGRESS REPORT

DATE 1972	DEPTH		Foolage	Hours on Bottom	BIT NOS.	DEVIATION SURVEY		REMARKS
	From	To				Depth	R.D.G.	
April 25	60'	120'	60'	4 3/4	1			Drilling. Started conductor hole at 6:00 p.m. April 20, 1972 drill 20" hole with bucket - ream to 24" Ran 89' of 20" conductor pipe, landed at 78' K.B. Cemented with 100 sacks Fondu cement- Finished Cementing 12:00 p.m. April 22. Drill rat hole - gravel falling in - complete rat hole and cementing around same at 12:00 midnight April 24. Spud with 8 3/4" bit at 2:30 a.m. April 25, 1972.
						120	3/4	
						150	1/2	
						240	1/2	
						300	1/2	
April 26	120'	391'	271'	17 1/4	1 & 2	350	1/4	Drilling - Trip to remove bucket tooth from bit. Trip Bit #1 - Jets plugged. Run Bit #2 - trip out - iron from bucket wedged in cones - run #2 back in
						440	1/2	
						530	1/8	
April 27	391'	662'	271'	19 3/4	2 & 3	620	3/4	Drilling
						650	3/4	
						710	1/4	
April 28	662'	819'	(D)157' (R)207'	18	4&Reamer	800	1/2	Reaming - Drill 8 3/4" pilot hole to 819' - commence reaming 8 3/4" hole to 12 1/4"
April 29		819'	(R)419'	15 1/2	Reamer			Running Casing - Reamed to 12 1/4" to depth of 704'. Start running Csg.
April 30		819'						W.O.C. Ran 9 5/8" Casing (724.91") Mannesman Grade J-55, 36#, Rge. 3 ST C, 8 rd. Landed at 704' K.B. Cemented with 350 sacks of Fondu cement. Displaced plug w/water. 16 bbls/cement returns Plug down at 12:04 p.m. April 29, 1972
May 1		819'						W.O.C. - Nipple up - drill mouse hole - gravel falling in. Pressure test blind rams, Hydril & 3 1/2" pipe rams to 1400# for 15 mins. - o.k. Drill Out - plug @ 659'. Clean to 819' K.B. Trip out for stabilizers.
May 2	819'	1010'	191'	10	4	990	1/8	Running DST #1. Drill to 1010' - testing porosity in Bear Rock
May 3	1010'	1356'	346'	16 1/4	5			Drilling. Completed DST #1 - good test.
May 4	1356'	1930'	574'	22 3/4	5	1385 1800	1 1 3/4	Drilling

DAILY PROGRESS REPORT

DATE 1972	DEPTH		Footage	Hours on Bottom	BIT NOS.	DEVIATION SURVEY		REMARKS
	From	To				Depth	R.D.G.	
May 5	1930'	2222'	292'	19 1/2	5&6	2130	2 3/4	Drilling. Tripped for new bit at 2141'
May 6	2222'	2373'	151'	9 3/4	6	2300	2	Drilling. Drilled to 2261' and ran DST #2 in Ronning porosity Good test - drilled ahead with Bit #7
May 7	2373'	2630'	257'	22 3/4	7	2450	2	Drilling
May 8	2630'	2872'	242'	19 1/2	7 & 8	2650	1 3/4	Drilling. Tripped for new bit at 2671'
May 9	2872'	3205'	333'	19	8	2920	1 1/2	Drilling
May 10	3205'	3403'	198'	11 3/4	8	3100	1 1/2	Rig Repairs. Tripped for new bit at 3403' - slip line, repair brakes
May 11	3403'	3763'	360'	21	9	3400	1	Drilling. Partially lost circulation at 3403' - drilled 10' and regained circulation.
May 12	3763'	4090'	327'	17 3/4	9 & 10	3815	1 1/2	Drilling. Tripped for new bit at 3815'
May 13	4090'	4420'	330'	22 3/4	10	4330	1 3/4	Drilling
May 14	4420'	4686'	266'	18 3/4	10&11			Drilling - Tripped for new bit at 4445' - Losing from 10 - 20 barrels of drilling fluid to the formation.
May 15	4686'	4946'	260'	19 1/2	11 & 12	4820	1 1/2	Rig Repairs. Tripped for new bit at 4946'
May 16	4946'	5214'	268'	20 3/4	12			Drilling
May 17	5214'	5468'	254'	22 3/4	12	5360	1/2	Drilling - Fluid loss 10 - 12 bbls/hr.
May 18	5468'	5571'	103'	16 3/4	12 & 13			Drilling - Trip for new bit at 5484'
May 19	5571'	5668'	97'	18 1/2	13 & 14	5628	0	Drilling. Tripped for new bit at 5628'
May 20	5668'	5882'	214'	23 1/4	14			Drilling.
May 21	5882'	6128'	246'	17	14 & 15			Drilling - Tripped for new bit at 6119'
May 22	6128'	6280'	152'	23 1/4	15			Drilling
May 23	6280'	6350'	70'	14 1/4	15 & 16	6285	2	Tripping for new bit. Tripped for new bit at 6285' and 6350'
May 24	6350'	6429'	79'	20 1/4	17			Drilling
May 25	6429'	6570'	141'	17 3/4	17 & 18			Drilling - Tripped for new bit at 6500'
May 26	6570'	6740'	170'	23 1/4	18	6500	2	Drilling
May 27	6740'	6886'	146'	17 3/4	18 & 19	6742	2 1/8	Drilling - Tripped for new bit at 6742'
May 28	6886'	6961'	75'	10	19 & 20			Running Logs. Tripped for new bit at 6923' drilled to Final Total Depth at 6961' - started logging with Dresser Atlas.
May 29		6961'	0	0				Running Logs

DAILY PROGRESS REPORT

DATE 1972	DEPTH		Footage	Hours on Bottom	BIT NOS.	DEVIATION SURVEY		REMARKS
	From	To				Depth	R.D.G.	
May 30		6961'	0	0				Waiting on Orders. Finished running logs. Losing mud at 5 bbls/hr W.O.C. Run Plug #1 6961 - 6861' & Plug #2 3600 - 3450'
May 31		6961'	0	0				
June 1		6961'	0	0				Running DST #3. Waited 8 hrs. on Plug #2. Felt at 3614' Polished off top. Commence DST #3 3200 - 3614' Dismantle B.O.P.'s Complete DST #3 - good test. Ran Plug #3 2150 - 2000'. Felt Plug #3 at 2010' after 8 hours. Ran Plug #4 630 - 780' Felt top of Plug #4 at 623' after 8 hours.
June 2		6961'	0	0				
June 3		6961'	0	0				Clean up location. Weld plate on casing. Rig Released at 12:00 noon - June 2, 1972

ABANDONMENT PLUGS

- #1 - 6961 - 6861' - 55 sacks cement, plug down at 3:00 a.m. May 31, 1972 - no feel
- #2 - 3600 - 3450' - 100 sacks cement + 3% CaCl_2 , plug down at 5:00 a.m. May 31, 1972
Felt plug at 3614' after 10 hours
- #3 - 2150 - 2000' - 100 sacks cement + 3% CaCl_2 , plug down at 11:30 a.m. June 1, 1972
Felt plug at 2010' after 8 hours
- #4 - 780 - 630' - 100 sacks + 3% CaCl_2 , plug down at 9:00 p.m., June 1, 1972
Felt plug at 623' after 8 hours
- Five sacks of cement put in top of surface casing - plate welded on with name tag.

LOST CIRCULATION ZONES

Intercrystalline, vuggy and some cavernous porosity is present in the Ronning formation. Below 3400 feet the drilling fluid was being lost to the formation at the rate of approximately 10 barrels per hour. Lost circulation material was added daily to the system to hold this loss to a minimum. On two occasions circulation was lost following a trip for a new bit, this occurred at 3403 feet and 4445 feet. In both instances, circulation was regained after drilling a few feet.

SECTION IV - LOGS

Electrical Logs: by Dresser Atlas

Induction Electrolog	Run 1	May 27, 1972	704 - 6940'
Sidewall Neutron Gamma Ray	Run 1	May 28, 1972	704 - 6932'
Compensated Densilog	Run 1	May 28, 1972	704 - 6932'
BHC Acoustilog	Run 1	May 29, 1972	704 - 6924'

SECTION V - ANALYSIS

<u>Lab No.</u>	<u>Sample</u>	<u>From</u>	<u>To</u>	<u>Source</u>	<u>Remarks</u>
933-2670	Water	3200	3614	DST #3 Ronning	Water Analysis
933-2581	Water	900	1010	DST #1 Bear Rock	Water Analysis
933-2581	Water	2121	2261	DST #2 Ronning	Water Analysis

WELL HISTORY LOG of

CANDEL MOBIL et al IROQUOIS I-11

located at

UNIT I, SECTION 11, GRID 67-50-129-30

Latitude 67° 40' 40" Longitude 129° 32' 05"

NORTHWEST TERRITORIES, CANADA

Well Status: Dry & Abandoned

Date Spudded: April 25, 1972

Date Completed Drilling: May 28, 1972

Operator: CanDel Oil Ltd.

Geology By: T.A.D. Haddow

Elevation: Gr. 400'

K.B. 418'

Total Depth: Driller 6961' Logger 6944'

Drilling Contractor: Nabor Drilling Limited

Rig No. 8

LEGEND

	SIDERITE, bedded		GYPSUM		ANHYDRITE, secondary		GRANITE WASH
	SANDSTONE		MARLSTONE, limy-dolomitic		SHALE		IGNEOUS, basic
	SILTSTONE		LIMESTONE		CLAYSTONE		IGNEOUS, acidic
	BENTONITE		DOLOMITE, primary		GLACIAL TILL		VOLCANIC
	COAL		DOLOMITE, secondary		CONGLOMERATE, ie. 40% chert, 40% ls., etc.		METAMORPHIC
	SALT		ANHYDRITE, primary		BRECCIA		
	ARKOSIC		FLOATING SAND GRAIN		CHERT, sandy & oolitic		SIDERITE PELLETS
	ARGILLACEOUS, disseminated		SILTY		NODULES, Fe-st		GLAUCONITIC
	DOLOMITIC		SANDY		NODULES, limy		SALT CAST or INFILL
	CALCAREOUS		ARGILLITE GRAIN		NODULES, dolomitic		
	ANHYDRITIC		CHERT, light & dark		NODULES, phosphatic		
	GYPSIFEROUS		CHERT, tripolitic		NODULES, siderite		
	LITHOGRAPHIC		CRYPTOCRYSTALLINE		EARTHY		CHALKY
	KARST TOPOGRAPHY		VERY POOR SAMPLES, questionable		CAVINGS, cannot interpret		NO SAMPLES
	ALGAL, nondescript		BIOCLASTIC or FRAGMENTAL		BRYOZOA		MOLLUSKS
	ALGAL, encrusting		PSEUDO OOLITES or PELLETS		FORAMINIFERA		OSTRACODS
	ALGAL, ooloid		CORAL		CRINOID		
	ALGAL, coralline		STROMATOPOROID		OOBITES		
	MARL, limy		PYRITE		SIDERITE CEMENT		PLANT REMAINS
	MARL, dolomitic		BENTONITIC		PLANT SPORES		FISH REMAINS
	LIMESTONE STREAKS		SILICEOUS		MINERAL CRYSTALS		FOSSILS
	DOLOMITE STREAKS		SHALE, laminae		CALCITE or secondary DOLOMITE crystals		CARBONACEOUS

104

located at

UNIT I, SECTION 11, GRID 67-50-129-30

Latitude 67° 40' 40" Longitude 129° 32' 05"

NORTHWEST TERRITORIES, CANADA

Well Status: Dry & AbandonedDate Spudded: April 25, 1972Date Completed Drilling: May 28, 1972Operator: CanDel Oil Ltd.Geology By: T.A.D. HaddowElevation: Gr. 400'K.B. 418'Total Depth: Driller 6961' Logger 6944'Drilling Contractor: Nabor Drilling LimitedRig No. 8

LEGEND

 SIDERITE, bedded	 GYPSUM	 ANHYDRITE, secondary	 GRANITE WASH
 SANDSTONE	 MARLSTONE, limy-dolomitic	 SHALE	 IGNEOUS, basic
 SILTSTONE	 LIMESTONE	 CLAYSTONE	 IGNEOUS, acidic
 BENTONITE	 DOLOMITE, primary	 GLACIAL TILL	 VOLCANIC
 COAL	 DOLOMITE, secondary	 CONGLOMERATE, ie. 40% chert, 40% ls., etc.	 METAMORPHIC
 SALT	 ANHYDRITE, primary	 BRECCIA	
 ARKOSIC	 FLOATING SAND GRAIN	 CHERT, sandy & oolitic	 SIDERITE PELLETS
 ARGILLACEOUS, disseminated	 SILTY	 NODULES, Fe-st	 GLAUCONITIC
 DOLOMITIC	 SANDY	 NODULES, limy	 SALT CAST or INFILL
 CALCAREOUS	 ARGILLITE GRAIN	 NODULES, dolomitic	
 ANHYDRITIC	 CHERT, light & dark	 NODULES, phosphatic	
 GYPSIFEROUS	 CHERT, tripolitic	 NODULES, siderite	
 LITHOGRAPHIC	 CRYPTOCRYSTALLINE	 EARTHY	 CHALKY
 KARST TOPOGRAPHY	 VERY POOR SAMPLES, questionable	 CAVINGS, cannot interpret.	 NO SAMPLES
 ALGAL, nondescript	 BIOCLASTIC or FRAGMENTAL	 BRYOZOA	 MOLLUSKS
 ALGAL, encrusting	 PSEUDO OOLITES or PELLETS	 FORAMINIFERA	 OSTRACODS
 ALGAL, ooloid	 CORAL	 CRINOID	
 ALGAL, coralline	 STROMATOPOROID	 OOLITES	
 MARL, limy	 PYRITE	 SIDERITE CEMENT	 PLANT REMAINS
 MARL, dolomitic	 BENTONITIC	 PLANT SPORES	 FISH REMAINS
 LIMESTONE STREAKS	 SILICEOUS	 MINERAL CRYSTALS	 FOSSILS
 DOLOMITE STREAKS	 SHALE, laminae	 CALCITE or secondary DOLOMITE crystals	 CARBONACEOUS

2 of 2

OIL STAIN OR RECOVERY 

GAS SHOW OR RECOVERY 


FLOURESCENCE 

BITUMIN 

FORMATION WATER RECOVERY - exponent shows ppm Cl. 

FORMATION TESTS

- A. BOTTOM HOLE
- B. DUAL PACKERS
- C. PACKER SET IN CASING
- D. F.I.T. SCHLUMBERGER





BHC

Acoustilog

FILE NO. 1760-E

COMPANY CANDEL OIL LIMITED

WELL CANDEL MOBILE ET AL IROUOIS 1-11

FIELD WILDCAT

PROVINCE NORTH WEST TERRITORIES

LOCATION:

67° 50' 40"N
129° 30' 05"W

Other Services
I/L-GR
S/N-GR
COMP DENS/L

Permanent Datum GROUND LEVEL Elev. 400'

Log Measured from KELLY BUSHING 18.0 Ft. Above Permanent Datum

Drilling Measured from KELLY BUSHING

	Elevations
KB	418
DF	
GL	400

Date	5-29-72
Run No.	ONE
Depth—Driller	6961'
Depth—Logger	6934'
Bottom Logged Interval	6924'
Top Logged Interval	SURF.
Casing—Driller	9 5/8'@704'
Casing—Logger	704
Bit Size	8 3/4"
Type Fluid in Hole	SALT WATER

Density and Viscosity						
pH and Fluid Loss		cc		cc		cc
Source of Sample	CIRC.					
Rm @ Meas. Temp.	.06 @ 65 °F	@ °F	@ °F	@ °F	@ °F	@ °F
Rmf @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F	@ °F	@ °F
Rmc @ Meas. Temp.	@ °F	@ °F	@ °F	@ °F	@ °F	@ °F
Source of Rmf and Rmc						
Rm @ BHT	0.49 @ 85 °F	@ °F	@ °F	@ °F	@ °F	@ °F
Time Since Circ.	22HRS.					
Max. Rec. Temp. Deg. F.	85°	°F	°F	°F	°F	°F
Equip. No. and Location	1300 EDM					
Recorded By	MACLEAN	FAYE				
Witnessed By	HADDOW					

THIS HEADING AND LOG CONFORMS TO API RECOMMENDED STANDARD PRACTICES AND IS

REMARKS

Changes in Mud Type or Additional Samples				Scale Changes			
Date	Sample No			Type Log	Depth	Scale Up Hole	Scale Down Hole
Depth-Driller							
Type Fluid in Hole							
Dens	Visc.						
pH	Fluid Loss		cc				
Source of Sample				Equipment Data			
Rm @ Meas. Temp	@	°F		Run No.	Tool Type	Pad Type	Tool Position
Rmf @ Meas. Temp.	@	°F		ONE	1601-24885		CENTERED
Rmc @ Meas. Temp.	@	°F					
Source Rmf	Rmc						
Rm @ BHT	@	°F					
Rmf @ BHT	@	°F					
Rmc @ BHT	@	°F					

GAMMA RAY
API UNITS

DEPTH

ACOUSTILOG


 $T, \underline{4R}, \underline{1R}, \underline{4T}$

SPECIFIC ACOUSTIC TIME

Micro Seconds Per Fool

Year	Percentage of Population 15 and Over with High School Diploma or Higher
1960	35
1965	55
1970	75
1975	85
1980	95
1985	100
1990	100

	80	70	60	50	40
1990	80	70	60	50	40
1991	80	70	60	50	40
1992	80	70	60	50	40
1993	80	70	60	50	40
1994	80	70	60	50	40
1995	80	70	60	50	40
1996	80	70	60	50	40
1997	80	70	60	50	40
1998	80	70	60	50	40
1999	80	70	60	50	40
2000	80	70	60	50	40
2001	80	70	60	50	40
2002	80	70	60	50	40
2003	80	70	60	50	40
2004	80	70	60	50	40
2005	80	70	60	50	40
2006	80	70	60	50	40
2007	80	70	60	50	40
2008	80	70	60	50	40
2009	80	70	60	50	40
2010	80	70	60	50	40
2011	80	70	60	50	40
2012	80	70	60	50	40
2013	80	70	60	50	40
2014	80	70	60	50	40
2015	80	70	60	50	40
2016	80	70	60	50	40
2017	80	70	60	50	40
2018	80	70	60	50	40
2019	80	70	60	50	40
2020	80	70	60	50	40
2021	80	70	60	50	40
2022	80	70	60	50	40
2023	80	70	60	50	40
2024	80	70	60	50	40
2025	80	70	60	50	40
2026	80	70	60	50	40
2027	80	70	60	50	40
2028	80	70	60	50	40
2029	80	70	60	50	40
2030	80	70	60	50	40
2031	80	70	60	50	40
2032	80	70	60	50	40
2033	80	70	60	50	40
2034	80	70	60	50	40
2035	80	70	60	50	40
2036	80	70	60	50	40
2037	80	70	60	50	40
2038	80	70	60	50	40
2039	80	70	60	50	40
2040	80	70	60	50	40
2041	80	70	60	50	40
2042	80	70	60	50	40
2043	80	70	60	50	40
2044	80	70	60	50	40
2045	80	70	60	50	40
2046	80	70	60	50	40
2047	80	70	60	50	40
2048	80	70	60	50	40
2049	80	70	60	50	40
2050	80	70	60	50	40
2051	80	70	60	50	40
2052	80	70	60	50	40
2053	80	70	60	50	40
2054	80	70	60	50	40
2055	80	70	60	50	40
2056	80	70	60	50	40
2057	80	70	60	50	40
2058	80	70	60	50	40
2059	80	70	60	50	40
2060	80	70	60	50	40
2061	80	70	60	50	40
2062	80	70	60	50	40
2063	80	70	60	50	40
2064	80	70	60	50	40
2065	80	70	60	50	40
2066	80	70	60	50	40
2067	80	70	60	50	40
2068	80	70	60	50	40
2069	80	70	60	50	40
2070	80	70	60		



100

200

300

400

500


600

One Millisecond Travel Time




DRILLING TIME Total Time for 5 Feet 10 20 30 40		DST & CORE	GRAPHIC LOG	DEPTH	FORMATION	LITHOLOGY	CSC PER PLUGS
					DEV - HARE INDIAN	Glacial drift - unconss sd, gran, peb & cob Sh - gy, fis, mic-mic, scat blk plnt spr Sh - m gy, hd, fis, mic-mic, sli bit/prt, scat flk/carb, mat (plnt spr) Sh - dk gy-blk, fis, mic-mic, bit, rr lam/calc sltst. Sh - aa, scat plnt run & spr, tr/scat py Sh - dk gy - blk, brit, mic-mic, bit/mat prt, scat plnt rmb & spr, scat fos, calc/ prt-lmy stks Sh - aa; Ls - gy-grnsh-brnsh/prt, mix-vf-fx/prt, dns, alty, arg, thn inbd gy calc sh, sm dol stks-brnsh gy, mix, dns, shun fos - ost, brach, bry Sh - m gy, hd, mic-mic, calc; Ls - gy - grnsh-brnsh/prt, mix-vfx, dns, bioc-micritio in prt, fos, scat frac fld w/c calc xtls Ls - m brnsh-grnsh gy, mix-sm vf-fx, bioc, pel/prt, micritio/prt, dns, arg, sm thn inbd of gy calc sh, sm ch stks, scat frac fld, xtlr calc, fos, scat py Ls - aa; Sh - m gy, hd, mic-mic, calc, py/prt Ls - m brnsh-grnsh gy, mix-vfx, bioc, dns, shun fos-brach ost crin sm inbd/sh - m gy, hd, mic-mic, calc. Ls - m brnsh to grnsh gy, mix-vfx, dns, arg, fos; Sh - m gy, mic-mic, calc. Ls - m brnsh-grnsh gy, mix-vfx, bioc-micritio/prt, dns, arg stks, sm inbd gy calc sh, fos Ls - m brnsh-grnsh gy, mix-fx, bioc-micritio/prt, dns, arg, shly, fos, scat frac fld w/dog tooth spar Ls - aa; sh - m gy, fis-blky, mic-mic, calc. Ls - gysh brn-sm grnsh-brnsh gy, mix-fx, frag, micritio/prt, dns, arg, fos, sm prtg/ dk gy calc sh & thn inbd/m gy calc sh Ls - brnsh gy, mix-vfx, micritio, dns, arg, sm prtg/dk gy calc sh, sm scat py, scat fos - brach, crin, bry Ls - lt brnsh gy, mix-fx, pol, dns, sli arg, sm scat frac fld w/xtln calc, rr scat sml vf fld w/xtln calc. Ls - aa; ls-brnsh-grnsh gy, orpx, micritio, dns, sm scat hrln frac - sm dol - asoc w/frac Ls - brnsh gy, mix, micritio, dns, arg, sm scat ost, sm scat sml pth & stks/blk - carb mat Ls - m dk brnsh gy, orpx-mix, micritio, dns, arg, sm prtg/dk gy sh Ls - gysh brn, mix-fx, frag-micritio/prt, dns, arg, scat ost Ls - lt gysh brn, mix-fx-sm bnd orpx, frag-arg/prt, micritio/prt, dns, arg, sm alg mat, scat ost, sm prtg/blk-bit sh Ls - m-dk gysh brn, mix-fx, micritio/prt-frag, pel & col/prt, dns, arg, scat styl prtg-bit sh, ost. Ls - lt gysh brn, mix-fx, bioc, dns, fos-ost, brach, rr cor Ls - gysh brn, orpx-vfx, micritio, dns, scat brach, sm scat f frac fld w/calc. Ls - aa-sm scat hrln frac, sm stks/sh-blsh gy, blky, mic-mic bent, scat py Ls - lt brnsh gy, mix-fx, frag, dns, dol, arg, fos-brach ost Ls - m dk gy, mix-vfx, alg, dns, arg, scat ost, prtg/blk bit sh Ls - lt brnsh gy, mix-fx, frag, dns, arg, scat ost, sm scat cor Ls - brnsh gy - sm grnsh stks, orpx - mix, micritio dns, arg Ls - m gysh brn, mix-fx, frag, dns, arg, prtg/bit sh, tr/lt grnsh gy wxy sh, sm scat gast & brach Ls - aa - lt - m gysh brn, micritio/prt Ls - aa & ls - brnsh gy orpx, micritio, dns Ls - gysh brn, orpx-vfx, micritio, dns, arg, scat hrln & f frac-fld/calc, fw scat fos Ls - aa - fw frag stk - sli dol, fw stks/dk gy sh & blsh gy bent sh	

SURFACE CASING 9 5/8 X 704 W 100 SACKS

107



100
200
300
400
500
600



DEVONIAN - HUMER
DEVONIAN - GOSAGE (BEAR ROCK)


Sh - dk gy-blk, fis, mic-mic, bit, rr lam/calc sltst.
Sh - aa, seat pint rm & spr, tr/seat py
Sh - dk gy - blk, brit, mic-mic, bit/mst prt, seat pint rmis & spr, seat ros, calc/prt-lay stks
Sh - aa; Ls - gy-grnsh-brnsh/prt, micx-vf-fx/prt, dns, slty, arg, thn inbd gy calc
Sh - m gy, hd, mic-mic, calc; Ls - gy - grnsh-brnsh/prt, micx-vfx, dns, bioc-micritio
in prt, fos, seat frac fld w/c calc xtlr.
Ls - m brnsh-grnsh gy, micx-sm vf-fx, bioc, pel/prt, micritio/prt, dns, arg, sm thn
inbd of gy calc sh, sm ch stks, seat frac fld, xtlr calc, fos, seat py
Ls - aa; Sh - m gy, hd, mic-mic, calc, py/prt
Ls - m brnsh-grnsh gy, micx-vfx, bioc, dns, abun ros-brach ost crin sm inbd/sh -
m gy, hd, mic-mic, calc.
Ls - m brnsh to grnsh gy, micx-vfx, dns, arg, fos; Sh - m gy, mic-mic, calc.
Ls - m brnsh-grnsh gy, micx-vfx, bioc-micritio/prt, dns, arg stks, sm inbd gy calc
sh, fos
Ls - m brnsh-grnsh gy, micx-fx, bioc-micritio/prt, dns, arg, shly, fos, seat frac
fld w/dog tooth spar
Ls - aa; sh - m gy, fis-blky, mic-mic, calc.
Ls - gysh brn-sm grnsh-brnsh gy, micx-fx, frag, micritio/prt, dns, arg, fos, sm prtq/
dk gy calc sh & thn inbd/m gy calc sh
Ls - brnsh gy, micx-vfx, micritio, dns, arg, sm prtq/dk gy calc sh, sm seat py, seat
fos - brach, crin, bry
Ls - lt brnsh gy, micx-fx, ool, dns, sli arg, sm seat frac fld w/xtln calc, rr
- seat, sm vf fld w/xtln calc.
Ls - aa; ls-brnsh-grnsh gy, orpx, micritio, dns, sm seat hrln frac - sm dol
- asoc w/frac.
Ls - brnsh gy, micx, micritio, dns, arg, sm seat ost, sm seat sm pth & stks/black
- carb mat
Ls - a dk brnsh gy, orpx-micx, micritio, dns, arg, sm prtq/dk gy sh
Ls - gysh brn, micx-fx, frag-micritio/prt, dns, arg, seat ost
Ls - lt gysh brn, micx-fx, sm bnd orpx, frag-arg/prt, micritio/prt, dns, arg, sm
- alg mat, seat ost, sm prtq/blk-bit sh
Ls - m-dk gysh brn, micx-fx, micritio/prt-frag, pel & ool/prt, dns, arg, seat styl
prtq/bit sh, ost.
Ls - lt gysh brn, micx-fx, bioc, dns, fos-ost, brach, rr ool
Ls - gysh brn, orpx-vfx, micritio, dns, seat brach, sm seat f frac fld w/o ool.
Ls - aa-sm seat hrln frac, sm stks/sh-blsh gy, blk, mic-mic bent, seat py
Ls - lt brnsh gy, micx-fx, frag, dns, dol, arg, fos-brach ost.
Ls - m dk gy, micx-vfx, alg, dns, arg, seat ost, prtq/blk bit sh
Ls - lt brnsh gy, micx-fx, frag, dns, arg, seat ost, sm seat ool
Ls - brnsh gy - sm grnsh stks, orpx - micx, micritio dns, arg
Ls - m gysh brn, micx-fx, frag, dns, arg, prtq/bit sh, tr/lt grnsh gy wxy sh, sm seat
east & brach
Ls - aa - lt - m gysh brn, micritio/prt
Ls - aa & ls - brnsh gy orpx, micritio, dns
Ls - gysh brn, orpx-vfx, micritio, dns, arg, seat hrln & f frac-fld/calc, fw seat fos
Ls - aa - fw frag stks - sli dol, fw stks/dk gy sh & blsh gy bent sh
Ls - aa - fw frag stks - dol/prt w/d o stn
Ls - brnsh, gy, micx-vfx, frag-micritio/prt, dns, arg, sm seat ost

Well name CanDel Mobil etal Iroquois I-11
Location I-11 67-50 129-30

K.B. elev. 418
Geologist T.A.D. Haddow

Sheet No. 1

2 of 2



704'

800

900

1000

1100

1200

1300

Ten Minutes Travel Time

DRILLING TIME
Total Time for 5 Feet
10 20 30 40

DST
&
CORE

GRAPHIC
LOG

DEPTH

FORMATION

LITHOLOGY

CSC-857
PLUS

New Bit DT2RR

New Bit DDV

REPAIR
DRILLING
RECORDER

New Bit X55

DST No 1 @

DEVONIAN - GOSSAGE (BEAR ROCK)

700
Ls - m gysh brn - dk stks, micx-vfx, frag/prt, micritio/prt, dns, arg, prt, dk
gy sh & tan inbd/gy oalc sh, scat ost.
Ls - brnsh gy, micx-vfx, micritio, frag/prt, dns, sli arg, sm tan stks of
gy oalc sh
Ls - aa & ls - brnsh gy, orpx-micx, micritio, dns, arg, sm sh tan - blsh gy brnsh,
f dism py
Ls - gysh brn, micx-vfx, frag/prt, micritio/prt, dns, arg, fw scat frac fld w/xtln
oalc sm scat ost
Ls - gysh brn, micx-vfx, frag, dns, arg, sm prt, blk bit sh & blsh gy sh w/f
dism py
Ls - aa, prt/gy oalc sh
Ls - gysh brn, orpx-micx, micritio, arg, oalc xtln infg sm f frac & rr sml vg
Ls - gysh brn, micx-vfx, micritio, dns, arg, sm inbd gy oalc sh, sm scat brach
Ls - gysh brn, micx-vfx, micritio, arg, prt, frag/prt, dns, arg, w/prt, sm tan inbd gy
oalc sh & prt, blsh gy sh, f os - act, alg, brach, ost.
Ls - gysh brn, micx-vfx, micritio, arg, prt, dns, arg, sm inbd gy oalc sh, gy/prt,
sm scat orin brach
Sh - gysh gy, hrd, mic-mio, v oalc, f dism py, sm scat ls f sl, Ls - gysh brn, orpx-
micx, micritio, dns, arg
Ls - gysh brn, vfx, micritio-frag/prt, dns, arg, sm inbd sh aa
Ls - gysh brn, micx-vfx, micritio, dns, arg, (tr/strom @ 890')

800
Ls - aa sm stks/v lt gy chky ls, sm tan inbd dol (5%) - gysh brn vfx, chky/prt,
sli inx por-noneff, sli oalc
Ls - (75%) & dol (25%) aa
Ls - gysh brn, micx-vfx, morto-frag/prt, sm crm chky stks, sm inbd dol w/sli inx
por - noneff, sm sec dol xtln.
Ls - gysh brn, micx-vfx w/stks/v lt gy - crm - chky, morto, frag/prt, sm inbd dol
gysh brn, vfx, earthy/prt sli inx por - noneff.
Dol - gysh brn, vfx, sli oalc/prt, sli inx por
Ls - crm - gysh brn, micx-vfx, chky/prt, morto/prt, frag/prt, dns, sli arg/prt, sm
dol aa - sli in x por noneff
Ls - crm - gysh brn, micx-vfx - chky/prt, frag, ti, arg stks, sli dol - earthy/prt.
Ls - aa morto & frag
Ls - aa morto & frag, tr/mlky ch
Ls - v lt gysh brn - crm/prt, micx, frag, morto/prt, sm ool, dns
Ls - v lt - lt gysh brn, micx-vfx aa
Ls - v lt gysh brn - crm/prt, micx-vfx, frag & morto, dns

900
Ls - lt gysh brn, micx-vfx, frag & morto, dol stks, ti
Ls - lt gysh brn, micx-vfx, frag, morto/prt, dns; Dol - gysh brn, vfx, sli inx por-
noneff.
Dol - gysh brn, micx-vfx, sli inx por, arg
Dol - aa; Ls - brnsh gy, micx-vfx, frag, morto/prt, dns, arg.
Ls - gysh brn, micx-vfx, frag, morto/prt, pel/prt, dol stks, ti, arg
Dol - gysh brn, micx-vfx, sli inx por, arg, fw scat f frac fld w/oalc
Dol - v lt gysh brn - sm drkr stks, micx-vfx, sli inx por, sm arg stks, sm stks/ls aa
Dol - gysh brn, micx-vfx, sli inx por, arg, tr/qtz xtln
Dol - gysh brn, micx-vfx, sli p inx pp & scat sml vg por, sm scat wh c sec dol
xtln, arg.
Dol - lt gysh brn, micx-vfx, sli-p inx pp & scat sml vg por oalc xtln (from frac)
sli arg/prt
Dol - gysh brn - sm lt stks, micx-vfx, sli inx por, arg.




1000
Ls - v lt gysh brn - crm/prt, micx, frag, morto/prt, sm ool, dns
Ls - v lt - lt gysh brn, micx-vfx aa
Ls - v lt gysh brn - crm/prt, micx-vfx, frag & morto, dns

1100
Ls - lt gysh brn, micx-vfx, frag & morto, dol stks, ti
Ls - lt gysh brn, micx-vfx, frag, morto/prt, dns; Dol - gysh brn, vfx, sli inx por-
noneff.
Dol - gysh brn, micx-vfx, sli inx por, arg
Dol - aa; Ls - brnsh gy, micx-vfx, frag, morto/prt, dns, arg.
Ls - gysh brn, micx-vfx, frag, morto/prt, pel/prt, dol stks, ti, arg
Dol - gysh brn, micx-vfx, sli inx por, arg, fw scat f frac fld w/oalc
Dol - v lt gysh brn - sm drkr stks, micx-vfx, sli inx por, sm arg stks, sm stks/ls aa
Dol - gysh brn, micx-vfx, sli inx por, arg, tr/qtz xtln
Dol - gysh brn, micx-vfx, sli p inx pp & scat sml vg por, sm scat wh c sec dol
xtln, arg.
Dol - lt gysh brn, micx-vfx, sli-p inx pp & scat sml vg por oalc xtln (from frac)
sli arg/prt
Dol - gysh brn - sm lt stks, micx-vfx, sli inx por, arg.

1200
Ls - v lt gysh brn - crm/prt, micx, frag, morto/prt, sm ool, dns
Ls - v lt - lt gysh brn, micx-vfx aa
Ls - v lt gysh brn - crm/prt, micx-vfx, frag & morto, dns

1300
Ls - lt gysh brn, micx-vfx, frag & morto, dol stks, ti
Ls - lt gysh brn, micx-vfx, frag, morto/prt, dns; Dol - gysh brn, vfx, sli inx por-
noneff.
Dol - gysh brn, micx-vfx, sli inx por, arg
Dol - aa; Ls - brnsh gy, micx-vfx, frag, morto/prt, dns, arg.
Ls - gysh brn, micx-vfx, frag, morto/prt, pel/prt, dol stks, ti, arg
Dol - gysh brn, micx-vfx, sli inx por, arg, fw scat f frac fld w/oalc
Dol - v lt gysh brn - sm drkr stks, micx-vfx, sli inx por, sm arg stks, sm stks/ls aa
Dol - gysh brn, micx-vfx, sli inx por, arg, tr/qtz xtln
Dol - gysh brn, micx-vfx, sli p inx pp & scat sml vg por, sm scat wh c sec dol
xtln, arg.
Dol - lt gysh brn, micx-vfx, sli-p inx pp & scat sml vg por oalc xtln (from frac)
sli arg/prt
Dol - gysh brn - sm lt stks, micx-vfx, sli inx por, arg.


104



LITHOLOGY

Del - gysh brn - m dk gysh brn,vf-fx,slt inx por,arg,sm scat prtg/blt bit sh, tr/qtz xtls.
 Del - gysh brn,vf-fx,slt inx por,arg,scat frac fld w/xtln calc.
 Del - m gysh brn, vf-fx,slt-p inx pp & sm vg por,arg,scat frac fld w/xtln calc
 Del - lt gysh brn-sm dk stks,vf-fx,p inx & scat sm vg por,slt arg/prt
 Del - gysh brn, vf-fx,slt-p inx por, arg
 Del - lt brnsh gy - aa
 Del - brnsh gy - sm dk stks,vf-fx,slt- p inx por, arg
 Del - aa tr/qtz xtls, sm calc xtls (infg frac)
 Del - aa, inars qtz xtls & calc xtls
 Del - brnsh gy - sm dk stks,vf-fx,slt-p inx por, arg
 Del - lt-m dk gysh brn,miox-vfx,slt stky inx por,arg stks,fw scat qtz xtls
 Del - lt gysh brn,miox-vfx,stky slt inx por, slt arg
 Del - gysh brn,miox-vfx,stky slt inx por,arg,fw scat qtz xtls, sm scat calc xtls
 Del - gysh brn - lt stks,miox-vfx,stky slt inx por-noneff,fw qtz xtls, & calc xtls
 Del - lt gysh brn,miox-vfx,ti; slty,fw qtz xtls & calc xtls.
 Del - buff - sm dk stks/prt,dns,slty,sm scat qtz xtls
 Del - buff,miox-vfx,dns,slty, (smpl powdered difficult to interpret)
 Del - m gy,miox-vfx,dns,arg,tr/qtz xtls,tr/grnsh gy sh prt, slty
 Del - lt gy, miox,dns, slty
 Del - lt gy,miox-vfx,ti,slty (v fine) rr grnsh gy shly stks
 Del - brnsh gy - sm dk stks,miox-vfx,dns,arg,slty, rr prt,blt bit sh, sm scat frac fld w/xtln calc.
 Del - dk brnsh gy-sm lt stks,miox,ti,v arg,slty sm prt,blt bit sh
 Del - gy, miox,ti, arg, slty sm prt/grnsh gy sh
 Del - m dk brnsh gy, miox-vfx-sm fx,stky slt inx por,arg,slty,sm prt/dk gy sh & blt bit sh

107



1500

1600



1700

1800

1900

2000

2100



DEVONIAN - GOSAGE (BEAR ROCK)

Dol - lt gysh brn-sm dk stks,vf-fx,slx & scat sml vg por,slx arg/prt

Dol - gysh brn, vf-fx,slx-p inx por, arg

Dol - lt brnsh gy - aa

Dol - brnsh gy - sm dk stks,vf-fx,slx-p inx por, arg

Dol - aa tr/qtz xtls, sm calc xtls (inflg frac)

Dol - aa, iners qtz xtls & calc xtls

Dol - brnsh gy - sm dk stks,vf-fx,slx-p inx por, arg

Dol - lt-m dk gysh brn,micx-vfx,slx stky inx por,arg stks,fv scat qtz xtls

Dol - lt gysh brn,micx-vfx,slx inx por, slx arg

Dol - gysh brn,micx-vfx,slx inx por,arg,fv scat qtz xtls, sm scat calc xtls

Dol - gysh brn - lt stks,micx-vfx,slx inx por-noneff,fv qtz xtls, & calc xtls

Dol - lt gysh brn,micx-vfx,ti; slty,fv qtz xtls & calc xtls.

Dol - buff - sm dk stks/prt,dns,slty,sm scat qtz xtls

Dol - buff,micx-vfx,dns,slty, (smpl powdered difficult to interpret)

Dol - m gy,micx-vfx,dns,arg,tr/qtz xtls,tr/grnsh gy sh prt, slty

Dol - lt gy, micx,dns, slty

Dol - lt gy,micx-vfx,ti,slty (v fine) rr grnsh gy shly stks

Dol - brnsh gy - sm dk stks,micx-vfx,dns,arg,slty, rr prt/blk bit sh, sm scat frac fld w/xtln calc.

Dol - dk brnsh gy-sm lt stks,micx,ti,v arg,slty sm prt/blk bit sh

Dol - gy, micx,ti, arg, slty sm prt/grnsh gy sh

Dol - m dk brnsh gy, micx-vfx-sm fx,slx inx por,arg,slty,sm prt/dk gy sh & blk bit sh

Dol - lt gy - slx grnsh - brnsh est, micx - vfx, ti, slty

Dol - m - dk brnsh gy,micx-vfx,ti, v arg, slx slty,scat frac fld w/xtln calc prt/dk gy sh

Dol - m gy - slx brnsh, micx,dns,arg,slty,scat frac w/calc.

Dol - brnsh gy - sm dkr stks,micx-fx,dns, arg/prt,slty,scat frac w/calc

Well name CanDel Mobil etol Iroquois I-II


Location I-II 67-50 129-30

K.B. elev. 418'

Geologist T.A.D. Haddow

Sheet No. 3

2 of 2



2200

2300



2400

2500

2600


2700

28



OST No 2

New Bit RRG28x



SILURIAN - ORDOVICIAN
RONNING


Dol - aa sm lt col stks - vf-fx, stky inx por, scat frac fld/xlin calc
Dol - v lt buff, f-mx, p inx & vug por-abun lss o dol rhmb, scat qtz xtls, sli slty & arg
Dol - gysh brn, f-mx, sli-p inx por, arg, scat qtz xtls
Dol - lt gysh brn-sm dk stks, f-mx, p inx & vug por-scat dol rhmb, qtz xtls, arg, slty
Dol - v lt buff, f-mx, p inx & vug por, scat dol rhmb & qtz xtls
Dol - v lt gysh brn-f-mx p inx & vug por, scat dol rhmb & qtz xtls, sli slty, scat frac fld/calc
Dol - m-dk gysh brn, vf-mx, sli inx & vug por, scat dol rhmb & qtz xtls, arg & slty
Dol - m gysh brn f-mx-euhedral, sli scat vug por, arg, slty, scat dol rhmb, tr/qty xtls
Dol - lt - m gysh brn aa
Dol - gysh brn, vf-fx, stky sli inx por, arg, slty, scat qtz xtls
Dol - v lt buff, f-mx, sli inx por, scat vug - sm o dol rhmb
Dol - v lt buff - v lt brn, vf-m xlin - euhedral, sli vug por - scat o dol rhmb
Dol - m brnsh gy - sm lt stks, vf-fx, stky sli inx por, arg, slty, scat frac fld/wh cx sec dol, sm frac fld/xlin calc
Dol - m - dk brnsh gy, vf-fx, dns, arg, slty, sm lss dol rhmb (inflg frac?)
Dol - brnsh gy - sm dk stks aa
Dol - brnsh gy, vf-fx, stky sli inx por, arg, slty
Dol - gysh brn, vf-fx, dns, arg, slty
Dol - lt gysh brn, vf-fx, sli inx por, sli arg, slty, sm sec dol
Dol - gysh brn, vf-fx, stky sli inx por, arg, slty
Dol - lt gysh brn, aa, sli inx & scat vug por, arg, slty, scat wh o xtls/dol (druses)
Dol - v lt buff, vf-mx, sli inx por, sli slty
Dol - gysh brn, vf-fx, stky sli inx por, arg, slty
Dol - gysh brn - sm dk stks, vfx, dns, arg, slty
Dol - gysh brn, vf-fx, stky sli inx & vug por, scat dol rhmb, slty, sli arg, sm scat frac fld/sec dol
Dol - gysh brn, micx-vfx-stks/mic-suc w/stky sli inx por, arg, slty
Dol - brnsh gy, micx-vfx, dns-sm lt buff mic-suc stks w/sl inx por - noneff slty & ady, abund calc xtls & sm dol rhmb inflg frac, tr qtz xtls
Dol - lt buff - microsuc & lt brn-gysh-micx-vfx, stky sli inx por-noneff, slty arg, sm scat calc xtls, tr/qty xtls & dol rhmb
Dol - buff micx-vfx, dns, slty
Dol - lt gysh brn, micx-vfx, ti, slty, sm scat inclus/calc xtls, rr qtz xtls

Well name CanDel Mobil et al Iroquois I-II
Location I-II 67-50 129-30


K.B. elev. 418
Geologist J.A.D. Haddow

Sheet No. 4

2 of 2



DRILLING TIME Total Time for 5 Feet 10 20 30 40				DST B CORE	POROSITY % GRAIN % PVT % GAS %	GRAPHIC LOG	DEPTH	FORMATION	LITHOLOGY	CSC-PEER PLUGS
							2800		Dol - gysh brn - lt stks, micx-fx, ti, slty, sm scat incl/calco xtls	
									Dol - brnsh gy, micx-fx, dns/mst prt - scat blind vug w/o dol druses, slty, sli arg sm scat frac fld/sec dol	
									Dol - brnsh gy, micx-fx, dns - scat vugs w/sec dol, slty, arg	
							2900		Dol - buff, micx-fx, sli inx por, rr drusy vug, rr qtz xtls, sm lse calc & sec dol xtls, arg, slty (vf)	
									Dol - gysh brn, micx-fx, dns, rr scat vug, arg, slty, lse calc xtls (frac?)	
									Dol - aa, sli scat vug por - sec dol druses	
									Dol - aa, sm lt col stks & pths, sli vug por	
									Dol - gysh brn, micx-fx-suc/prt, stky sli inx & scat vug por, arg, slty, scat frac fld/calco xtls, sec dol druses	
									Dol - aa, abun frac w/calco xtls, stky sli inx & vug por, dol druses	
							3000		Dol - gysh brn, micx-fx, sli inx & vug por, c sec dol rhmos inf'g vugs, tr/qty xtls, tr/mlky ch, arg, slty, sm scat frac infld/calco	
									Dol - lt gysh brn, micx-fx, dns, sm scat frac fld/calco	
									Dol - lt buff, micx-fx, dns, slty, sm scat frac fld/calco	
									Dol - lt brnsh & grnsh gy - micx - fx, dns, frac fld/calco, fv vugs w/druses of sec dol sm f diam py	
									Dol - v lt gysh brn-buff, micx-f & sm mx, sli scat vug por-druses, frac w/calco pych	
									Dol - lt gysh brn, vf-ox, sli p inx & vug por, scat sli arg stks, sm scat py	
							3100			
									Dol - v lt - lt gy - brnsh/prt, micx-mx, dns, fw frac fld/calco	
									Dol - lt gysh brn, micx-ox, sli inv & vug por, lse dol rhms	
									Dol - aa - v lt buff/prt, fw stks/m dk brnsh gy vfx dol; fv sli arg stks, sm py	
									Dol - v lt - lt gy - brnsh/prt, micx - ox, sli inx & vug por, tr/grn wxy sh, rr scat glaue	
							3200		Dol - v lt gy, micx-ox, sli inx & vug por, mlky & v lt blsh gy ch, tr qtz xtls, sm scat py	
									Dol - v lt - lt brnsh gy, micx-ox, sli-p inx & vug por, rr scat glaue, slty	
									Dol - lt gy, vf-ox, sli inx & sml vug por, v g ovrn por (kelly dropped 5') tr/glaue	
									Dol - lt gy - brnsh/prt, vf-ox, sli p inx & vug por, scat py	
									Dol - aa, sm dk stks of micx - vfx dol - slty & arg; sm qtz xtls	
									Dol - lt gy - brnsh/prt, vf-ox, sli inx & vug por, sil/prt, v lt gy ch, sm qtz xtls, tr/bright-grn sh, scat py	
							3300		Dol - aa, abun v lt gy - mlky ch, qtz xtls	
									Dol - lt gysh brn, micx-ox, sli inx & vug por - sm ovrn por at 3380', lt gy ch, sil/prt, qtz xtls, sm scat pyr	
							3400			
									Dol - aa (trip sample)	
									Dol - lt gysh brn, vf-ox, scat sli inx por & vug por, lt gy ch	



2900

3000



3100

3200

3300

3400

3500



DST No. 3 (plug back) ⊕

New Br. RRG25A

SILURIAN - ORDOVICIAN
RONNING

- Dol - brnsh gy, micx-fx, dns/mst prt - spat blind vug w/o dol druses, slty, ali arg sm scat frac fld/sec dol
- Dol - brnsh gy, micx-fx, dns - scat vugs w/sec dol, slty, arg
- Dol - buff, micx-fx, slt inx por, rr drusy vug, rr qtz xtls, sm lse calc & sec dol xtls, arg, slty (vr)
- Dol - gysh brn, micx-fx, dns, rr scat vug, arg, slty, lse calc xtls (frac?)
- Dol - aa, slt scat vug por - sec dol druses
- Dol - aa, sm lt ool stks & ptohs, slt vug por
- Dol - gysh brn, micx-fx-suc/prt, stky slt inx & scat vug por, arg, slty, scat frac fld/calc xtls, sec dol druses
- Dol - aa, abun frac w/calc xtls, stky slt inx & vug por, dol druses
- Dol - gysh brn, micx-fx, slt inx & vug por, c sec dol rhmbs infg vugs, tr/qty xtls, tr/mlky ch, arg, slty, sm scat frac fld/calc
- Dol - lt gysh brn, micx-fx, dns, sm scat frac fld/calc
- Dol - lt buff, micx-fx, dns, slty, sm scat frac fld/calc
- Dol - lt brnsh & grnsh gy - micx - fx, dns, frac fld/calc, fw vugs w/druses of sec dol sm f diam py
- Dol - v lt gysh brn-buff, micx-f & sm mx, slt scat vug por-druses, frac w/calc
- Dol - lt gysh brn, vf-ox, slt p inx & vug por, scat slt arg stks, sm scat py
- Dol - v lt - lt gy - brnsh/prt, micx-ox, dns, fw frac fld/calc
- Dol - lt gysh brn, micx-ox, slt inv & vug por, lse dol rhmbs
- Dol - aa - v lt buff/prt, fw stks/m dk brnsh gy vfx dol; fw slt arg stks, sm py
- Dol - v lt - lt gy - brnsh/prt, micx - ox, slt inx & vug por, tr/grn wxy sh, rr scat glauc
- Dol - v lt gy, micx-ox, slt inx & vug por, mlky & v lt blsh gy ch, tr qtz xtls, sm scat py
- Dol - v lt - lt brnsh gy, micx-ox, slt-p inx & vug por, rr scat glauc, slty
- Dol - lt gy, vf-ox, slt inx & sml vug por, v g evrn por (kelly dropped 5') tr/glauc
- Dol - lt gy - brnsh/prt, vf-ox, slt p inx & vug por, scat py
- Dol - aa, sm dk stks of micx - vfx dol - slty & arg; sm qtz xtls
- Dol - lt gy - brnsh/prt, vf-ox, slt inx & vug por, sil/prt, v lt gy ch, sm qtz xtls, tr/bright-grn sh, scat py
- Dol - aa, abun v lt gy - mlky ch, qtz xtls
- Dol - lt gysh brn, micx-ox, slt inx & vug por - sm evrn por at 3380', lt gy ch, sil/prt, qtz xtls, sm scat pyr
- Dol - aa (trip sample)
- Dol - lt gysh brn, vf-ox, scat slt inx por & vug por, lt gy ch
- Dol - buff - lt gysh brn, aa, fw qtz xtls, ch


Well name CanDel Mobil et al. Ingois I-II
Location I-II 67-50 129-30

2 of 2


K.R. elev. 418'
Geologist T.A.D. Haddow

Sheet No. 5

PLUG No. 2





3600
3700
3800
3900
4000
4100



DRILLING TIME Total Time for 5 Feet 10 20 30 40		DST CORE	GRAPHIC LOG	DEPTH	FORMATION	LITHOLOGY		CSC - PERC PLUGS
		DST No 3 (plug back) @		3500		Dol - buff,vf-ex,scat sli inx & vug por, ch		PLUG No 2
						Dol - aa & dol - m-dk gy - sli brnsh,micx-vfx,arg,dns,stks/dk gy-blk ch,sm stks/ady dol-lt gy,vfx,dns,v slty-ady(vfx)-grdg/dol ss,f diam py Dol - m - dk gy /lt gy slty - sdy stks aa		
				3600		Dol - lt buff - lt gysh brn,vf-mx,slty sli inx & vug por,slty,v lt gy ch sm qtz xtls		
						Dol - lt buff,vf-ex,stky sli inx & vug por,slty,sm lt gy ch,sm qtz xtls		
						Dol - lt buff,vf-ex,stky sli inx & vug por,slty		
						Dol - aa, tr/lt gy ch & qtz xtls		
				3700		Dol - aa, qtz xtls & v lt gy ch - fnt outline/ool		
						Dol - lt buff,lt gysh brn,vf-ex,stky sli inx & vug por,qtz xtls,tr/v lt gy ch		
						Dol - v lt buff, aa		
						Dol - v lt buff-brnsh/prt,vf-ex,stky sli inx & vug por,qtz xtls		
				3800		Dol - v lt buff - tr/rdsh stks,micx-mx,sli-p inx por,slty,sil/prt,v lt gy -mlky ch,qtz xtls		
						Dol - v lt gy & buff,vf-mx,stky sli inx por,slty,sm qtz xtls,tr/v lt gy ch		
						Dol - v lt buff - brnsh/prt,micx-ex,stky sli inx & vug por,slty,sil/prt,sm v lt gy ch & tr stks/m-dk gy ch,sm qtz xtls		
						Dol - v lt gy-brnsh/prt,vf-mx,dns,sm stks-gysh brn-micx-vfx,arg,slty,ti: tr ch		
						Dol - aa, sm v lt gy ch sm qtz xtls		
				3900		Dol - v lt gy - sli brnsh/prt,micx-mx,dns,slty sil/prt,sm ch-lt-v lt gy,qtz xtls		
						Dol - v lt gy-sli brnsh/prt,micx-mx,dns,slty,v ch-v lt gy(fnt ool) sil/prt, qtz xtls, tr/gyp xtls.		
						Dol - aa - ch being sli drkr/ool		
						Dol - lt gysh brn,micx-mx,dns,slty,abun v lt gy-v lt gysh brn ool ch,sm lse calc xtls		
						Dol - v lt gysh brn,micx-mx,dns,slty,v lt gy ch,sm qtz xtls		
				4000		Dol - v lt buff,micx-fx,stky sli inx por,slty sm lt ool ch-ool/prt,qtz xtls		
						Dol - v lt buff,micx-fx,stky sli inx por,slty,sm lt ool ch,sm qtz xtls		
						Dol - v lt buff,micx-mx,sli inx por-dns stks,sm v lt gy ch,sm qtz xtls		
				4100		Dol - v lt buff-v lt gysh brn,micx-mx,sm m gysh brn stks-micx-vfx,sli arg slty; stky sli inx por,sli ch - ool/prt, sm qtz xtls.		
						Dol - v lt - m gysh brn,micx-fx,dns,slty,arg stks,m sm v lt gy ch, sm qtz xtls, sm lse calc xtls		

10f




Dol - aa & dol - m-dk gy - sli brnsh, micx-vfx, arg, dns, stks/dk gy-bik ch, sm stks/edy dol-lt gy, vfx, dns, v slty-edy(vfg)-grdg/dol ss, f diam py
Dol - m - dk gy -/lt gy slty - sdy stks aa
Dol - lt buff - lt gysh brn, vf-mx, slty sli inx & vug por, slty, v lt gy ch sm qtz xtls
Dol - lt buff, vf-ox, stky sli inx & vug por, slty, sm lt gy ch, sm qtz xtls
Dol - lt buff, vf-ox, stky sli inx & vug por, slty
Dol - aa, tr/lt gy ch & qtz xtls
Dol - aa, qtz xtls & v lt gy ch - fnt outline/ool
Dol - lt buff, lt gysh brn, vf-ox, stky sli inx & vug por, qtz xtls, tr/v lt gy ch
Dol - v lt buff, aa
Dol - v lt buff-brnsh/prt, vf-ox, stky sli inx & vug por, qtz xtls
Dol - v lt buff - tr/rdash stks, micx-mx, sli-p inx por, slty, sil/prt, v lt gy -mky ch, qtz xtls
Dol - v lt gy & buff, vf-mx, stky sli inx por, slty, sm qtz xtls, tr/v lt gy ch
Dol - v lt buff - brnsh/prt, micx-ox, stky sli inx & vug por, slty, sil/prt, sm v lt gy ch & tr stks/m-dk gy ch, sm qtz xtls
Dol - v lt gy-brnsh/prt, vf-mx, dns, sm stks-gysh brn-micx-vfx, arg, slty, ti: tr ch
Dol - aa, sm v lt gy ch sm qtz xtls
Dol - v lt gy - sli brnsh/prt, micx-mx, dns, slty sil/prt, sm ch-lt-v lt gy, qtz xtls
Dol - v lt gy-sli brnsh/prt, micx-mx, dns, slty, v ch-v lt gy(fnt ool) sil/prt, qtz xtls, tr/gyp xtls.
Dol - aa - ch being sli drkr/ool
Dol - lt gysh brn, micx-mx, dns, slty, abun v lt gy-v lt gysh brn ool ch, sm lse calc xtls
Dol - v lt gysh brn, micx-mx, dns, slty, v lt gy ch, sm qtz xtls
Dol - v lt buff, micx-fx, stky sli inx por, slty sm lt ool ch-ool/prt, qtz xtls
Dol - v lt buff, micx-fx, stky sli inx por, slty, sm lt ool ch, sm qtz xtls
Dol - v lt buff, micx-mx, sli inx por-dns stks, sm v lt gy ch, sm qtz xtls
Dol - v lt buff-v lt gysh brn, micx-mx, sm m gysh brn stks-micx-vfx, sli arg slty; stky sli inx por, sli ch - ool/prt, sm qtz xtls.
Dol - v lt - m gysh brn, micx-fx, dns, slty, arg stks, m sm v lt gy ch, sm qtz xtls, sm lse calc xtls
Dol - v lt - m gysh brn, micx-fx, dns, slty, arg stks, ch - v lt gy - dk gy, sm lse calc xtls, sm qtz xtls

Well name CanDel Mobil et al Iroquois I-II
Location I-II 67-50 129-30

2 of 2

K.B. elev. 418'
Geologist T.A.D. Haddow


Sheet No. 6





4200
4300
4400
4500
4600
4700
4800

DRILLING TIME Total Time for 5 Feet 0 20 30 40		D.S.T & CORE	POROSITY % GRAVITY % WATER %	GRAPHIC LOG	DEPTH FEET	FORMATION	LITHOLOGY	SEC. FEE PLUS
					4200		Dol - aa - abun qtz xtls, sli vug por	
							Dol - v lt - m gysh brn, micx-fx, stky sli inx por, slty, arg stks, qtz xtls, sm stk/oh v lt brnsh gy - dk gy	
							Dol - v lt gy-sli brnsh-sm dk stks, micx-fx, dns/mst prt, sm soat sm/vug, slty, qtz xtls	
					4300		Dol - brnsh gy - lt stks, micx-fx, stky sli inx por, slty, arg stks, qtz xtls, sm v lt - dk gy oh	
							Dol - gy - v lt/prt - sli brnsh, micx-fx, sli inx por-stky, slty, arg/prt, sli oh f w qtz xtls	
							Dol - aa fv prt/dk gy sh	
					4400		Dol - v lt buff, micx-mx, sli inx por, tr/soat vug, slty, py/prt, tr/lt ool ch & qtz xtls	
							Dol - v lt - lt gy - sli brnsh - sm dk stks, micx-ox, stky sli inx por, slty, sli oh, sm soat py, sm soat prt/gysh grn sh & dk gy sh - bit/prt	
					4500		Dol - m brnsh gy-sm lt stks, micx-mx, ti, slty, arg, rr lt ool ch & qtz xtls, soat py	
							Dol - v lt gy-brnsh stks, micx-mx, sli inx por, slty, arg stks, sm qtz xtls, py, tr sh prt	
							Dol - v lt gysh brn, vf-ox, stky sli inx & vug por, sli oh-ool/prt, sm qtz xtls	
							Dol - aa - sm drkr ool stk	
							Dol - gysh brn-micx-fx, til arg, slty, sm prt/dk gy sh, sm soat py	
							Dol - brnsh gy, micx-fx, ti, slty	
					4600		Dol - gysh brn, micx-fx, ti, slty, arg, sm prt/dk gy & blk bit sh	
							Dol - lt brnsh gy, micx-fx, ti, slty, sli arg	
							Dol - lt-m gysh brn, micx-fx, ti, slty, arg, sm soat frac fld w/xtln calc, soat sh prt	
					4700			
							Dol - v lt gy - gysh brn - rr rdsh stks, micx-ox, sli vug & inx por, slty, arg stk sm dk gy sh prt - sm dk rdsh ool, tr/lt gy oh & qtz xtls	
							Dol - gysh brn, micx-fx, ti, slty, arg, sm prt/blk bit sh & dk gy sh	
							Dol - lt - m gysh brn, sm stks/v lt gy, micx-fx, stky sli inx por, sh prt-dk gy, rr prt-stk	
							Dol - gysh brn, micx-fx, ti, slty, arg.	
					4800		Dol - aa, sm dol - v lt gy-brnsh gy, micx-ox, sli inx & vug por - dns stk, slty, arg/prt, rr qtz xtls.	
							Dol - v lt gy, micx-vfx, stky sli inx por, slty (vf)	
							Dol - v lt - m gysh brn, micx-mx, stky, sli inx por, slty, arg/prt	
							Dol - v lt gy - sli brnsh - sm dk stks, micx-mx, sli inx por, sli arg/prt.	
							Dol - aa - incr drkr stks, stky sli inx por, arg/prt.	
							Dol - m - dk brnsh gy, micx-vfx, ti, arg, slty, sm prt/dk gy sh	

10f



4300
4400
4500
4600
4700
4800
4900




stk/ch v lt brnsh gy - dk gy
Dol - v lt gy-sli brnsh-sm dk stks,miox-fx,dns/mat prt,sm scat sm/vug,slty,qtz
Dol - brnsh gy - lt stks,miox-fx,stkly sli inx por,slty,arg stks,qtz xtls,sm v
lt - dk gy ch
Dol - gy - v lt/prt - sli brnsh,miox-fx,sli inx por-stky,slty,arg/prt,sli ch
f w qtz xtls
Dol - aa fw prt/dk gy sh
Dol - v lt buff,miox-mx,sli inx por,tr/scat vug,slty,py/prt, tr/lt col ch &
qtz xtls
Dol - v lt - lt gy - sli brnsh - sm dk stks,miox-ox,stkly sli inx por,slty,sli
ch,sm scat py, sm scat prtgysh grn sh & dk gy sh - bit/prt
Dol - m brnsh gy-sm lt stks,miox-mx,ti,slty,arg,rr lt col ch & qtz xtls,scat py
Dol - v lt gy-brnsh stks,miox-mx,sli inx por,slty,arg stks,sm qtz xtls,py, tr
sh prt
Dol - v lt gysh brn,vf-ox,stkly sli inx & vug por,sli ch-col/prt,sm qtz xtls
Dol - aa - sm drkr col stk
Dol - gysh brn-miox-fx,til arg,slty,sm prt/dk gy sh,sm scat py
Dol - brnsh gy,miox-fx,ti,slty
Dol - gysh brn,miox-fx,ti,slty,arg,sm prt/dk gy & blk bit sh
Dol - lt brnsh gy,miox-fx,ti,slty,sli arg
Dol - lt-m gysh brn,miox-fx,ti,slty,arg,sm scat frac fld w/xtln calc,scat
sh prt
Dol - v lt gy - gysh brn - rr rdsh stks,miox-ox,sli vug & inx por,slty,arg stk
sm dk gy sh prt - sm dk rdsh col,tr/lt gy ch & qtz xtls
Dol - gysh brn,miox-fx,ti,slty,arg,sm prt/dk blk bit sh & dk gy sh
Dol - lt - m gysh brn,sm stks/v lt gy,miox-fx,stkly sli inx por,sh prt-dk gy,rr
prt stks
Dol - gysh brn,miox-fx,ti,slty,arg.
Dol - aa, sm dol - v lt gy-brnsh gy,miox-ox,sli inx & vug por - dns stk, slty,
arg/prt,rr qtz xtls
Dol - v lt gy, miox-vfx,stkly sli inx por, slty (vf)
Dol - v lt - m gysh brn,miox-mx,stkly,sli inx por, slty, arg/prt
Dol - v lt gy - sli brnsh - sm dk stks,miox-mx,sli inx por,sli arg/prt.
Dol - aa - incr dkr stks,stkly sli inx por, arg/prt.
Dol - m - dk brnsh gy,miox-vfx,ti, arg, slty, sm prt/dk gy sh
Dol - lt - m gysh brn,miox-mx,stkly sli inx por,slty,arg/prt,prt/dk gy sh

Well name Candel Mobil etal Iroquois I-II
Location I-II 67-50 129-30

2 of 2

K.B. elev. 418'
Geologist T.A.D. Haddow


Sheet No. 7






00
5000
5100
5200
5300
5400
5500

DRILLING TIME Total Time for 5 Feet 10 20 30 40				DST & CORE	POROSITY % GRAIN % PVT % GAS %	GRAPHIC LOG	DEPTH	FORMATION	LITHOLOGY	CSC-JEP PLUS
New Bit J88							4900		Dol - gysh brn - sm dk stks, micx-fx, ti, slty, arg.	
									Dol - lt - m gysh brn, micx-mx, stky sli inx por, slty, arg/prt, scat prt/dk gy sh	
									Dol - aa micx - fx	
							5000		Dol - v lt buff, micx-fx, sli inx por, sm scat arg stks	
									Dol - aa - sm gysh brn stks, bnd/sli grnsh gy dol-micx-vfx, slty, dns	
									Dol - v lt gy-brnsh/prt-gysh brn, micx-fx, stky sli inx por, sm slty & arg stks	
									Dol - aa - prt/dk blk bit sh	
									Dol - v lt gy - gysh brn, micx-fx, tr sli inx por, slty & arg stks, tr/dk gy sh	
							5100		Dol - v lt gy-brnsh/prt-lt gysh brn, micx-vf & sm fx, ti, tr/v lt gy-lt brn sh	
									Dol - lt-m gy-sm dk stks-brnsh/prt, micx-fx, ti, slty & arg, tr/v lt gy sh	
									Dol - v lt brnsh gy - gysh brn, micx-vfx, ti, slty	
									Dol - v lt gy - sli brnsh/prt, micx-vfx, dns, slty	
							5200		Dol - aa - gysh brn/prt, sm prt/dk gy sh	107
									Dol - gysh brn- v lt/prt-dk/prt micx-vfx, ti, slty, sli arg/prt	
									Dol - gysh brn, micx-fx, tr/sli inx por, slty, arg	
									Dol - v lt buff - sm gysh brn, micx-fx, tr/sli inx por, slty, sm prt/dk blk bit sh	
							5300		Dol - v lt gy - gysh brn, micx-vfx, ti, slty, arg stk	
									Dol - v lt gy, v fx, sli inx por, slty	
									Dol - m - dk brnsh gy, micx-vfx, ti, arg, slty	
									Dol - aa - sm lt brnsh gy	
									Dol - v lt - m gy-brnsh/prt, micx-vfx, dns, slty, sm prt/dk blk bit & dk gy sh	
							5400			
									Dol - lt gy, micx, dns, slty, sm prt/dk grnsh gy & blk bit sh	
									Dol - aa, sm rr fnt rdsh stks	
							5500		Dol - lt - dk gy - brnsh, micx-vfx, dns, slty, arg stks, scat sh prtgs, tr/qtz xtls.	
									Dol - lt - dk gy, micx-vfx, dns, fw scat blind vug, bnd/prt, slty, arg/prt, tr/gy incl, sm prt/dk blk bit sh	

10f



5000
5100
5200
5300
5400
5500
560



SILURIAN - ORDOVICIAN
RONNING


Dol - aa micx - fx
Dol - v lt buff, micx-fx, sli inx por, sm scat arg stks
Dol - aa - sm gysh brn stks, bnd/sli grnsh gy dol-micx-vfx, slty, dns
Dol - v lt gy-brnsh/prt-gysh brn, micx-fx, stky sli inx por, sm slty & arg stks
Dol - aa - prtg blk bit sh
Dol - v lt gy - gysh brn, micx-fx, tr sli inx por, slty & arg stks, tr/dk gy ch
Dol - v lt gy-brnsh/prt-lt gysh brn, micx-vf & sm fx, ti, tr/v lt gy-lt brn ch
Dol - lt-m gy-sm dk stks-brnsh/prt, micx-fx, ti, slty & arg, tr/v lt gy ch
Dol - v lt brnsh gy - gysh brn, micx-vfx, ti, slty
Dol - v lt gy - sli brnsh/prt, micx-vfx, dns, slty
Dol - aa - gysh brn/prt, sm prtg/dk gy sh
Dol - gysh brn- v lt/prt-dk/prt micx-vfx, ti, slty, sli arg/prt
Dol - gysh brn, micx-fx, tr/sli inx por, slty, arg
Dol - v lt buff - sm gysh brn, micx-fx, tr/sli inx por, slty, sm prtg/blk bit sh
Dol - v lt gy - gysh brn, micx-vfx, ti, slty, arg stk
Dol - v lt gy, v fx, sli inx por, slty
Dol - m - dk brnsh gy, micx-vfx, ti, arg, slty
Dol - aa - sm lt brnsh gy
Dol - v lt - m gy-brnsh/prt, micx-vfx, dns, slty, sm prtg/blk bit & dk gy sh
Dol - lt gy, micx, dns, slty, sm prtg/grnsh gy & blk bit sh
Dol - aa, sm rr fnt rdsh stks
Dol - lt - dk gy - brnsh, micx-vfx, dns, slty, arg stks, scat sh prtgs, tr/qtz xtls.
Dol - lt - dk gy, micx-vfx, dns, fw scat blnd vug, bnd/prt, slty, arg/prt, tr/gyp
incl, sm prtg/blk bit sh
Dol - m - dk gy, micx-vfx, dns, slty, arg, sm thz inbds/dk gy &
grnsh gy sh - hrd brit dol
Dol - lt - m gy - brnsh/prt, micx-vf & sm fx, dns, arg, slty, sm scat py, inbd grnsh

Well name CanDel Mobil et al Iroquois I-II
Location I-II 67-50 129-30


2 of 2

K.B. elev. 418'
Geologist T.A.D. Haddow

Sheet No. 8



00
6400
6500
6600
6700
6800
6900



One Millisecond Travel Time


Ten Milliseconds Travel Time

6924
6934

First Rdg. Dresser Atlas
Total Depth Dresser Atlas

DRILLING TIME Total Core	POSSIBILITY OF CORE	GRAPHIC LOG	DEPTH	FORMATION	LITHOLOGY	PLUG NO.
			6300	CAMBRIAN	Dol - aa - sm lighter brnsh stks Dol - m - dk gy, micx, dns, v arg & slty, shly stks, scat blebs/any, tr/salt ost	
			6400		Dol - m gy - sli grnsh ost, micx-vfs, dns, v arg & slty, shly, sm anhy & gyp Dol - gy micx-vfx, dns, arg, slty, sh stk, scat glauc, py/prt, scat bleb & thn inbd of anhy Dol - m - dk brnsh gy, vf-fx, stky sli inx por, arg, slty, sh stks, scat glauc & py Dol - v lt gy - brnsh-grnsh-pnksh/prt, micx-vfx-ahky/prt, stky sli inx por, sm scat qtz xtls, py/prt, glauc/prt, sm bleb & thn stk/any, sdy stk thn oh stk, tr ool tex, sm stk/mar & grn sh; Dol - lt gysh brn, micx-vfx, dns	
			6500		Dol - v lt gy - lt gysh brn - sm rdsh stks & ptoh, micx-fx, stky sli inx por, tr/ool tex scat inol/gyp xtls, scat py Dol - aa; dol - m dk brnsh gy, micx-fx, dns, arg, stks/grnsh gy sh, slty, sdy stks, glauc, inol/gyp Dol - gysh brn - sm scat rd spts & ptoh, micx - vfx, dns, sli py/prt, sm inol/gyp & dol rhomb, sm bleb/any, slty & sdy, tr/ch Dol - aa - inor/rd stk & ptoh Dol - gysh brn w/rd stks & ptoh - aa	
			6600		Dol - lt - m gysh brn - fw rdsh stks, micx-vfx, dns, slty, sli ch, sm dol rhombs, sli stks, tr/salt osts, tr/qty xtls Dol - gysh br - pnk-rd ptoh-sm dk stk, micx-vfx, dns, slty, tr/qty xtls, sm dol rhomb lng & infig scat vug, stk grnsh gy & sm mar sh, tr/lt gy anhy, tr ool tex Dol - aa less rd Dol - lt brnsh gy - gysh brn - sm rd ptoh, micx-fx, dns, sli slty, ch - smky - lt gysh brn, sm stk/m gy-brnsh w/glauc, sm dol rhombs, sm pel/m brnsh gy dol Dol - lt brnsh gy - gysh brn-sm pnk & rd stks, micx-fx, dns, sli sli, tr qtz xtls, sm dol rhombs, tr/lt brnsh gy anhy, sm inbd gysh grn sh, sm prtq/blk bit sh	
			6700	PROTEROZOIC	Dol - v lt gy - gysh brn-pnk & rd stks & ptoh, micx-fx, dns, fw scat vug part to oomplt infl w/sec dol, sm sh stk, tr/salt ost Dol - v lt gy - lt & dk gysh brn-sm pnk & rd stks, micx-fx, dns, scat blind vug part - oomplt infl w/sec dol, slty, arg stks, sh stks, tr/any, tr salt ost, tr/grn sltst Dol - v lt - m gysh brn - pnk - rd stks & ptoh, micx-vfx, dns, slty, sm sca dol infig vug, tr/any, tr/qty xtls, sli ch - gysh brn, sm stks/gysh grn sh & dull gy sft sh, sm thn stks/gysh brn anhy, tr/slt osts, bree/prt (along frac), tr/gyp, tr/rnt pel	
			6800		Dol - aa - tr/grn sltst, sli inor/salt ost Dol - v lt-m gysh brn - pnk-rd stk & ptoh, sm dk gysh brn arg stk, micx-fx, dns, slty, sca dol, stk/any & gyp, tr qtz xtls. Dol - v lt buff-brn pnk rd/prt, micx-fx, dns, sli slty, sca dol infig vug, stks/any & gyp, stk/dull gy sft sh, scat salt ost Dol - lt - m gysh brn - pnk - rd ptoh aa Dol - aa gran/prt w/stky sli inx por Dol - dns aa	
			6900		Dol - v lt - m dk gysh brn - sm dk stks - pnk-rd stks & ptoh, micx-fx, dns, tr/ool, sm arg stk, wh mx sca dol rhomb infig vug, abun sh stk - dull gy, m dk gy	

104



6400

6500

6600

6700

6800

6900

6924
6934
6961First Rdg. Dresser Atlas
Total Depth Dresser Atlas
Total Depth Driller

← One Millisecond Travel Time

← Ten Milliseconds Travel Time

New Bit X55 R

New Bit X55 R

New Bit WD 7

CAMBRIAN

6400

6500

6600

6700

6800

6900

7000

Dol - m gy - sli grnsh ost, micx-vfs,dns, v arg & slty, shly,
sm anhy & gyp

Dol - gy micx-vfx,dns,arg,slty,sh stk,soat glauc,py/prt,soat bleb & thn inbd
of anhy

Dol - m - dk brnsh gy,vf-fx,stky sli inx por,arg,slty,sh stks,soat glauc & py

Dol - v lt gy - brnsh-grnsh-pnksh/prt,micx-vfx-chky/prt,stky sli inx por,sm
soat qtz xtls,py/prt,glauc/prt,sm bleb & thn stk/anhy,soat stk thn ch stk,
tr ool tex,sm stk/mar & grn sh;
Dol - lt gysh brn,micx-vfx,dns

Dol - v lt gy - lt gysh brn - sm rdsh stks & ptoch,micx-fx,stky sli inx por,
tr/ool tex soat inol/gyp xtls,soat py

Dol - aa; dol - m dk brnsh gy,micx-fx,dns,arg,stks/grnsh gy sh,slty,andy stks,
glauc,inol/gyp

Dol - gysh brn - sm soat rd spts & ptoch,micx - vfs,dns,sli py/prt,sm inol/gyp
& dol rhomb,sm bleb/anhy,slty & sdy, tr/ch

Dol - aa - inor/rd stk & ptoch

Dol - gysh brn w/rd stks & ptoch - aa

Dol - lt - m gysh brn - fw rdsh stks,micx-vfx,dns,slty,sli ch,sm dol
rhombs, sli stks,tr/salt csts, tr/rtz xtls

Dol - gysh br - pnk-rd ptoch-sm dk stk,micx-vfx,dns,slty,tr/rtz xtls,sm dol
rhomb lng & infig soat vug,stk grnsh gy & sm mar sh,tr/lt gy anhy,tr ool tex

Dol - aa less rd

Dol - lt brnsh gy - gysh brn - sm rd ptoch,micx-fx,dns,sli slty,sh - smky - lt
gysh brn,sm stk/m gy-brnsh w/glauc,sm dol rhombs,sm pel/m brnsh gy dol

Dol - lt brnsh gy-gysh brn-sm pnk & rd stks,micx-fx,dns,sli sli,rtz xtls,
sm dol rhomb, tr/lt brnsh gy anhy,sm inbd gysh grn sh,sm prtq/blk bit sh

Dol - v lt gy - gysh brn-pnk & rd stks & ptoch,micx-fx,dns,fw soat vug part
to complt infig w/sec dol,sm sh stk, tr/salt ost

Dol - v lt gy - lt & dk gysh brn-sm pnk & rd stks, micx-fx,dns,soat blind vug
part - compl infig w/sec dol,slty,arg stks,sh stks,tr/anhy,rtz salt csts,
tr/grn sltst

Dol - v lt - m gysh brn - pnk - rd stks & ptoch,micx-vfx,dns,slty,sm soat dol
infig vug, tr/anhy,rtz xtls,sli ch - gysh brn,sm stks/gysh grn sh & dull
gy sft sh, sm thn stks/gysh brn anhy,rtz salt csts,brec/prt (along frac), tr/
gyp, tr/int pel

Dol - aa - tr/grn sltst, sli inor/salt ost

Dol - v lt-m gysh brn - pnk-rd stk & ptoch,sm dk gysh brn arg stk,micx-fx,dns,
slty,sec dol,stk/anhy & gyp, tr qtz xtls.

Dol - v lt buff-brn pnk rd/prt,micx-fx,dns,sli slty,sec dol infig vug,stk/anhy
& gyp,stk/dull gy sft sh, soat salt ost

Dol - lt - m gysh brn - pnk - rd ptoch aa

Dol - aa gran/prt w/stky sli inx por

Dol - dns aa

Dol - v lt - m dk gysh brn - sm dk stks - pnk-rd stks & ptoch,micx-fx,dns,rtz/ool,
sm arg stk, wh mx sec dol rhomb infig vug,abun sh stk - dull gy, m dk gy
& sm gysh grn, sm sli csts,rtz/anhy & gyp,sm soat frac infig w/dol

F.T.D. 6961

Well name CanDel Mobil et al Iroquois I-II
Location I-II 67-50 129-30

2 of 2

K.B. elev. 416'
Geologist T.A.D. Haddow

Sheet No. 10



CORE LABORATORIES - CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS

File 933-2670 Page 1 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois I-11 K.B. 418 Grd. 400'
67° 40' 40.00 N.L.

Location 129° 32' 05.00 W.L. Field Iroquois River Area Province N. W. T.

Formation Ronning Interval 3280
3450' - 3614'

Sampled from (Top #1) 057 #3 by _____

Date sampled May 31/72 Date analysed June 6/72 Analyst ML

Recovery 2820' liquid.

_____ Mud type _____ Water cushion _____

Resistivity 0.048 Ohm-meters @ 69 °FSpecific gravity 1.1886 @ 60°FpH 11.4 H₂S AbsentRefractive Index 1.3772 @ 74°F

Total Solids:

Calculated 287,757 mg/literBy evaporation @ 110°C - mg/literBy evaporation @ 180°C - mg/literAt ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
111819	1104	25	Trace	-	-	-	171489	0	2915	58	347


PER CENT CALCULATED SOLIDS

38.9	.4	.0	Trace	-	-	-	59.6	.0	1.0	.0	.1
------	----	----	-------	---	---	---	------	----	-----	----	----

MEQ PER LITER

4861.7	55.1	2.1	Trace	-	-	-	4836.0	.0	60.6	1.9	20.4
--------	------	-----	-------	---	---	---	--------	----	------	-----	------

LOGARITHMIC PATTERN MEQ PER LITER



287673.111819.0



CORE LABORATORIES - CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS



File 933-2670 Page 2 of 2

Company CanDel Oil Ltd.Well CanDel Mobil et al Iroquois I-11 K.B. Grd.

67° 40' 40.00 N.L.

Location 129° 32' 05.00 W.L. Field Iroquois River Area Province N. W. T.Formation Ronning Interval 3200 - 3614Sampled from DST #3 (Bottomhole Sampler) by Date sampled May 31/72 Date analysed June 6/72 Analyst MLRecovery 2820' liquid.Mud type Water cushion

Total Solids:

Resistivity 0.059 Ohm-meters @ 69 ofCalculated 181,808 mg/literSpecific gravity 1.1226 @ 60°FBy evaporation @ 110°C - mg/literpH 11.1 H₂S AbsentBy evaporation @ 180°C - mg/literRefractive Index 1.3617At ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
70162	1063	25	Trace	Abs.	-	-	108193	0	2167	82	116


PER CENT CALCULATED SOLIDS

38.6	.6	.0	Trace	Abs.	-	-	59.5	.0	1.2	.0	.1
------	----	----	-------	------	---	---	------	----	-----	----	----

MEQ PER LITER

3050.5	53.0	2.1	Trace	Abs.	-	-	3051.0	.0	45.1	2.7	6.8
--------	------	-----	-------	------	---	---	--------	----	------	-----	-----

LOGARITHMIC PATTERN MEQ PER LITER



WATER ANALYSES

FOR

CANDEL OIL LTD.

**CANDEL MOBIL ET AL IROQUOIS I-11
IROQUOIS RIVER AREA
NORTHWEST TERRITORIES**

CORE LABORATORIES - CANADA LTD.

Petroleum Reservoir Engineering
CALGARY - EDMONTON - REGINA



CORE LABORATORIES - CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS



File 933-2581 Page 1 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois I-11 K.B. Grd. 400'
67° 40'20.00 N.L.

Location 129° 32'05.00 W.L. Field Iroquois River Area Province N.W.T.

Formation Interval 900' - 1010'

Sampled from DST #1 (BJ Tool #RS28) by BJ Testers

Date sampled Date analysed May 17/72 Analyst LK

Recovery Tool Recovery: 3000 cc's Water.

Mud type Water cushion

Resistivity 3.09 Ohm-meters @ 74 °F

Specific gravity 1.0027 @ 60°F

pH 9.3 H₂S Present

Refractive Index 1.3326 @ 73°F

Total Solids:

Calculated 1,858 mg/liter

By evaporation @ 110°C - mg/liter

By evaporation @ 180°C - mg/liter

At ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
695	3	1	Trace	-	-	-	832	210	31	86	Nil


PER CENT CALCULATED SOLIDS

37.4	.2	.1	Trace	-	-	-	44.8	11.3	1.7	4.6	.0
------	----	----	-------	---	---	---	------	------	-----	-----	----

MEQ PER LITER

30.2	.1	.1	Trace	-	-	-	23.5	3.4	.6	2.9	.0
------	----	----	-------	---	---	---	------	-----	----	-----	----

LOGARITHMIC PATTERN MEQ PER LITER



1713. 695.0



CORE LABORATORIES - CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS



File 933-2581 Page 2 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois 1-11 K.B. Grd. 400'
67° 40'20.00 N.L.

Location 129° 32'05.00 W.L. Field Iroquois River Area Province N.W.T.

Formation Interval 2121' - 2261'

Sampled from DST #2 (JB Tool #124) by

Date sampled Date analysed May 17/72 Analyst LK

Recovery Tool Recovery: 3000 cc's Water.

Mud type Water cushion

Total Solids:

Resistivity 1.21 Ohm-meters @ 75 °F
Specific gravity 1.0046 @ 60°F
pH 7.9 H₂S Present
Refractive Index 1.3334 @ 73°F

Calculated 4,969 mg/liter
By evaporation @ 110°C - mg/liter
By evaporation @ 180°C - mg/liter
At ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
1442	209	112	Trace	Abs.	-	-	2399	488	319	Nil	Nil


PER CENT CALCULATED SOLIDS

29.0	4.2	2.3	Trace	Abs.	-	-	48.3	9.8	6.4	.0	.0
------	-----	-----	-------	------	---	---	------	-----	-----	----	----

MEQ PER LITER

62.7	10.4	9.2	Trace	Abs.	-	-	67.7	8.0	6.6	.0	.0
------	------	-----	-------	------	---	---	------	-----	-----	----	----

LOGARITHMIC PATTERN MEQ PER LITER



4556. 1442.0

BJ

BORG X WARNER

DRILL STEM TEST REPORT

BJ SERVICE DIVISION
BORG-WARNER (CANADA) LIMITED

CANDEL MOBIL ET AL

IROQUOIS I-11

TEST NO. 1



DRILL-STEM TEST DATA

Well Name CANDEL MOBIL ET AL IROQUOIS I-11

Test No. 1

Well Number I-11

Zone Tested BEAR ROCK

Company CANDEL OIL CO.

Interval 900.0 TO 1010.0

Comp. Rep. H. MARTINOFF

Tester MEL MOSCRIPT

Date MAY 2, 1972

Type of Test DUAL BOTTOM HOLE

RFS Tool No. 28

Prewlow 5.0 mins. ISI 57.0 mins. Flow 84.0 mins. FSI 85.0 mins.

	IN REC. No. 5773		OUT REC. No. 5979		REC. No.	
	1150	RANGE 12 HR. CLOCK	1200	RANGE 24 HR. CLOCK	RANGE	HR. CLOCK
DEPTH		883.0		917.0		
Initial Hydro Mud Press		377.3		396.0		
Initial Shut-In Press		346.8		363.7		
Initial Flow Press		51.5		69.1		
Final Flow Press		311.2		329.6		
Final Shut-In Press		346.0		363.1		
Final Hydro Mud Press		377.3		396.0		

Mud Drop NIL

Viscosity 27.0

Top Packer Depth 894.0

Drill Pipe Size 3.5 IF

Surface Choke Size

Anchor Size 4.75

Cushion Amount

Fluid Loss

Temperature °F 80.0

Bottom Packer Depth

Wt. 13.0

Bottom Choke Size

Rat Hole Size

Type

Mud Weight 8.4

Net Pay Tested 30.0

Total Depth 1010.0

Fr. Run 443.61

Main Hole Size 8.750

Feet of Rat Hole

Rubber Size 7.5 X 2

Fluid Recovery Total Feet

Recovered 90 Feet of

Recovered 800 Feet of

Recovered Feet of

Recovered Feet of

Recovered Feet of

FRESH WATER

SULPHUROUS FRESH WATER

Gas Recovery

How Measured

Riser size:

mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day

Bleed Off Time for Drill Pipe

REMARKS: VERY WEAK INITIAL PUFF. WEAK AIR BLOW DYING IN 15 MIN.








TESTING REPORT

WEIGHT INDICATOR READING
PRIOR TO SETTING PACKERS
AFTER PULL PACKERS LOOSE

	ID	OD	LENGTH
45 LANDING SUB			
45 CHAMBER COS			1.00
45 TOOL OR P.O. SUB			6.00
CO SUB			
SHUT IN TOOL		4 3/4	5.20
R.F.S. No.	2 1/4	4 3/4	3.30
R.F.S. No.	2 1/4	4 3/4	
HYDRAULIC TOOL		4 3/4	7.20
JARS	1	4 3/4	6.00
RECORDER No. 5773	2 1/4	4 3/4	5.00
RECORDER No.	2 1/4	4 3/4	
SAFETY JOINT	2 11/16	4 3/4	1.75
BY PASS SUB	1 5/32	4 3/4	
PACKER	1 OR 3/4		6.00
PACKER	1 OR 3/4		5.00
ANCHOR-SPECIFY	2 1/4		1.00
PERF			15.00
BLANK OFF OR BY PASS SUB	1 5/32	4 3/4	
RECORDER No. 5979	2 1/4	4 3/4	5.00
PACKER	1 OR 3/4		
PACKER	1 OR 3/4		
ANCHOR-SPECIFY	2 1/4		
DR. COLLARS			86.72
RECORDER No.	2 1/4	4 3/4	
BULLNOSE	2 1/4	4 3/4	2.50
TOTAL DEPTH 1010			
TOTAL TAIL PIPE 110.22			
TOTAL TEST TOOL 69.95			

DST CHARTS FOR COMPARATIVE VISUAL ANALYSIS

HIGH PERMEABILITY
STRONG DAMAGE EFFECTHIGH PERMEABILITY
NO DAMAGE EFFECTMEDIUM PERMEABILITY
STRONG DAMAGE EFFECTMEDIUM PERMEABILITY
NO DAMAGE EFFECTLOW PERMEABILITY
STRONG DAMAGE EFFECTLOW PERMEABILITY
NO DAMAGE EFFECT



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DSY. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
RUN IN HOLE	1	0.0	0.0
	2	34.0	377.3
INITIAL HYDRO PRESSURE	3	84.0	377.3
INITIAL PREFLOW PRESSURE	4	84.0	16.4
FINAL PREFLOW PRESSURE	5	89.0	36.8
START INITIAL SHUT-IN	6	89.0	36.8
	7	90.0	341.4
	8	94.0	343.7
	9	99.0	345.1
	10	104.0	346.0
	11	109.0	346.3
	12	114.0	346.6
	13	119.0	346.6
	14	124.0	346.6
	15	129.0	346.6
INITIAL SHUT-IN PRESSURE	16	134.0	346.6
	17	139.0	346.8
	18	144.0	346.8
	19	146.0	346.8
START FLOW PERIOD	20	146.0	346.8
INITIAL FLOW PRESSURE	21	147.0	51.5
	22	151.0	66.4
	23	156.0	90.1
	24	161.0	111.7
	25	164.0	119.9
	26	165.0	379.3
	27	166.0	379.3
	28	167.0	228.2
	29	171.0	239.7
	30	176.0	249.1
	31	181.0	257.8
	32	186.0	265.8
	33	191.0	272.7
	34	196.0	279.3
	35	201.0	285.1



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
	36	206.0	290.5
	37	211.0	295.7
	38	216.0	300.3
	39	221.0	304.6
	40	226.0	308.3
FINAL FLOW PRESSURE	41	230.0	311.2
START FINAL SHUT-IN	42	230.0	311.2
	43	231.0	342.0
	44	235.0	343.4
	45	240.0	344.5
	46	245.0	344.8
	47	250.0	344.8
	48	255.0	345.1
	49	260.0	345.1
	50	265.0	345.1
	51	270.0	345.4
	52	275.0	345.4
	53	280.0	345.4
	54	285.0	345.4
	55	290.0	345.4
	56	295.0	345.4
	57	300.0	345.7
	58	305.0	345.7
	59	310.0	345.7
FINAL SHUT-IN PRESSURE	60	315.0	346.0
RUN OUT OF HOLE	61	315.0	346.0
FINAL HYDRO PRESSURE	62	316.0	377.3
	63	320.0	377.3
OUT OF HOLE	64	365.0	0.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

CALCULATIONS FOR LIQUID RECOVERY (FIRST SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE	347.3
NO. OF POINTS CONSIDERED IN BUILD-UP	13
NO. OF POINTS USED IN EXTRAPOLATION	12
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI)	0.11
EFFECTIVE PRODUCING TIME (MIN)	5.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

DATA FOR BUILD-UP PLOT (FIRST SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------

PORTION OF BUILD-UP CURVE NOT USED IN EXTRAPOLATION

7	1.0	341.4			6.00
---	-----	-------	--	--	------

POINTS USED IN EXTRAPOLATION

8	5.0	343.7	343.7	0.1	2.00
9	10.0	345.1	345.2	0.1	1.50
10	15.0	346.0	345.8	-0.2	1.33
11	20.0	346.3	346.1	-0.1	1.25
12	25.0	346.6	346.4	-0.2	1.20
13	30.0	346.6	346.5	-0.1	1.17
14	35.0	346.6	346.6	0.1	1.14
15	40.0	346.6	346.7	0.1	1.12
16	45.0	346.6	346.8	0.2	1.11
17	50.0	346.8	346.8	-0.0	1.10
18	55.0	346.8	346.8	0.0	1.09
19	57.0	346.8	346.9	0.0	1.09



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.

CALCULATIONS FOR LIQUID RECOVERY (SECOND SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE	346.5
NO. OF POINTS CONSIDERED IN BUILD-UP	18
NO. OF POINTS USED IN EXTRAPOLATION	18
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI).....	0.15
EFFECTIVE PRODUCING TIME (MIN)	89.0
(B) IN SITU CAPACITY (KH - MD FT)	6570.75
SLOPE OF BUILD-UP CURVE (PSI/CYCLE)	2.26
PRODUCING RATE (BBL/DAY)	106.34
FLUID VISCOSITY (CP)	0.860
FORMATION VOLUME FACTOR (RES BBL/ST BBL).....	1.000
(C) EFFECTIVE PERMEABILITY (MD)	219.02
FORMATION THICKNESS	30.00
(D) PRODUCTIVITY INDEX (BBL/DAY/PSI)	3.02
FLOWING PRESSURE (PSIG)	311.2
(E) APPROXIMATE DRAINAGE RADIUS (FT)	856.4
TOTAL FLOWING TIME (MIN)	89.0
(F) ESTIMATED DAMAGE RATIO	2.40
RESERVOIR POROSITY (PERCENT)	6.00
TOTAL COMPRESSIBILITY (VOL/VOL/PSI X 10-6)	9.00
WELL-BORE RADIUS (IN)	4.375
CALCULATED SKIN FACTOR	10.47
(G) PRODUCTION WITH DAMAGE REMOVED (BBL/DAY)	255.4



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 1

LOCATION I-11

REC. NO. 5773

DEPTH 883.


DATA FOR BUILD-UP PLOT (SECOND SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
POINTS USED IN EXTRAPOLATION					
43	1.0	342.0	342.1	0.1	90.00
44	5.0	343.4	343.6	0.2	18.80
45	10.0	344.5	344.2	-0.3	9.90
46	15.0	344.8	344.6	-0.3	6.93
47	20.0	344.8	344.8	-0.0	5.45
48	25.0	345.1	345.0	-0.1	4.56
49	30.0	345.1	345.1	0.0	3.97
50	35.0	345.1	345.2	0.1	3.54
51	40.0	345.4	345.3	-0.1	3.22
52	45.0	345.4	345.4	-0.0	2.98
53	50.0	345.4	345.5	0.1	2.78
54	55.0	345.4	345.5	0.1	2.62
55	60.0	345.4	345.6	0.2	2.48
56	65.0	345.4	345.6	0.2	2.37
57	70.0	345.7	345.7	-0.0	2.27
58	75.0	345.7	345.7	0.0	2.19
59	80.0	345.7	345.7	0.0	2.11
60	85.0	346.0	345.8	-0.2	2.05

ASSUMPTIONS AND LIMITATIONS

THE ENCLOSED DST INTERPRETATION CALCULATIONS REQUIRE SEVERAL NECESSARY ASSUMPTIONS TO PROVIDE A QUICK ESTIMATE OF MANY OF THE FACTORS INVOLVED. AS A RESULT THE INFORMATION GAINED SHOULD BE USED TO FORM AN OPINION OR ESTIMATE ONLY, UNTIL THE ASSUMPTIONS OF RESERVOIR AND FLUID PROPERTIES CAN BE WHOLLY OR PARTIALLY CLARIFIED BY MORE COMPLETE ANALYSIS AND TESTING.

PRESSURE VS. TIME
CANDEL MOBIL ET AL IAGQUOIS I-11
I-11
DST NO. 1 REC. NO. 5773




HORNER PRES. EXTRAPOLATION
 CANDEL MOBIL ET AL IROQUOIS I-11
 I-14
 DST NO. 1 $P_m = 346.5$


BOTTOM - HOLE PRESSURE (psig)

348.0
 347.0
 346.0
 345.0
 344.0
 343.0
 342.0
 341.0

10
 $(T + \Delta t) / \Delta t$




CANDEL MOBIL ET AL IROQUOIS I-11
 INTERVAL 900 - 1010
 DST NO. 1 REC. NO. 5773



DST RECORDER CHARTS

CANDEL MOBIL ET AL IROQUOIS I-11
 INTERVAL 900 - 1010
 DST NO. 1 REC. NO. 5979



BJ

BORG X WARNER

DRILL STEM TEST REPORT

BJ SERVICE DIVISION
BORG-WARNER (CANADA) LIMITED

CANDEL MOBIL ET AL

IROQUOIS I-11

TEST NO. 2



DRILL-STEM TEST DATA

Well Name	CANDEL MOBIL ET AL IROQUOIS 1-11	Test No.	2
Well Number	I-11	Zone Tested	RONNING
Company	CANDEL OIL LTD.	Interval	2121.0 TO 2261.0
Comp. Rep.	M. MILLER	Tester	MEL MOSCRIPT
		Date	MAY 5, 1972

Type of Test **DUAL BOTTOM HOLE** RFS Tool No. **124**Prewlow **5.0** mins. ISI **27.0** mins. Flow **60.0** mins. FSI **60.0** mins.

	IN REC. No. 5773		OUT REC. No. 5979		REC. No.	
	1150	RANGE 12	1200	RANGE 12	RANGE	HR. CLOCK
DEPTH						
Initial Hydro Mud Press		2104.0		2138.0		
Initial Shut-In Press		904.5		924.3		
Initial Flow Press		874.7		891.7		
Final Flow Press		162.0		181.7		
Final Shut-In Press		594.2		614.1		
Final Hydro Mud Press		875.5		892.3		
		904.5		924.3		

Mud Drop	10	Fluid Loss		Mud Weight	8.4
Viscosity	28.0	Temperature °F	84.0	Nat Pay Tested	90.0
Tap Packer Depth	2115.0	Bottom Packer Depth	2121.0	Total Depth	2261.0
Drill Pipe Size	3.5 IF	Wt. 13.0	Drill Collar I.D. 2.875	Ft. Run	447.00
Surface Choke Size	CLOSED	Bottom Choke Size	0.5	Main Hole Size	8.750
Anchor Size		Rat Hole Size		Feet of Rat Hole	
Cushion Amount		Type		Rubber Size	8.0

Fluid Recovery Total Feet	1300.0		
Recovered	90	Feet of	FRESH WATER
Recovered	1210	Feet of	SULPHUROUS FRESH WATER
Recovered		Feet of	
Recovered		Feet of	
Recovered		Feet of	

Gas Recovery	How Measured			Riser size:
mins.	Temp. °F	Press Rdg.	psi	Orifice Size
mins.	Temp. °F	Press Rdg.	psi	Orifice Size
mins.	Temp. °F	Press Rdg.	psi	Orifice Size
mins.	Temp. °F	Press Rdg.	psi	Orifice Size
mins.	Temp. °F	Press Rdg.	psi	Orifice Size
mins.	Temp. °F	Press Rdg.	psi	Orifice Size


Bleed Off Time for Drill Pipe

REMARKS: **WEAK INITIAL PUFF. WEAK AIR BLOW DECREASING THROUGHOUT TEST.**



TESTING REPORT

WEIGHT INDICATOR READING
PRIOR TO SETTING PACKERS
AFTER PULL PACKERS LOOSE



	ID	OD	LENGTH
4S LANDING SUB			
4S CHAMBER COS			1.00
4S TOOL OR P.O. SUB			5.00
CO SUB			
SHUT IN TOOL		4 3/4	5.20
R.F.S. No. 134	2 1/4	4 3/4	3.30
R.F.S. No.	2 1/4	4 3/4	
HYDRAULIC TOOL		4 3/4	7.20
JARS	1	4 3/4	6.00
RECORDER No. 5773	2 1/4	4 3/4	5.00
RECORDER No.	2 1/4	4 3/4	
SAFETY JOINT	2 11/16	4 3/4	1.75
BY PASS SUB	1 5/32	4 3/4	
PACKER	1 OR 7/8		6.00
PACKER	1 OR 7/8		5.00
ANCHOR—SPECIFY	2 1/2		1.00
PERF			15.00
BLANK OFF OR BY PASS SUB	1 5/32	4 3/4	
RECORDER No. 5979	2 1/4	4 3/4	5.00
PACKER	1 OR 7/8		
PACKER	1 OR 7/8		
ANCHOR—SPECIFY	2 1/2		
RECORDER No.	2 1/4	4 3/4	
DRILL COLLARS			116.50
BULLNOSE	2 1/4	4 3/4	2.50

DEPTH 2104

DEPTH

1. PACKER DEPTH 2115

2. PACKER DEPTH 2121

TOOL ABOVE INTERVAL 45.45

3. PACKER DEPTH

4. PACKER DEPTH







TOTAL INTERVAL

TOTAL DEPTH 2261

TOTAL TAIL PIPE 140.00

TOTAL TEST TOOL 68.95

DST CHARTS FOR COMPARATIVE VISUAL ANALYSIS

HIGH PERMEABILITY
STRONG DAMAGE EFFECTHIGH PERMEABILITY
NO DAMAGE EFFECTMEDIUM PERMEABILITY
STRONG DAMAGE EFFECTMEDIUM PERMEABILITY
NO DAMAGE EFFECTLOW PERMEABILITY
STRONG DAMAGE EFFECTLOW PERMEABILITY
NO DAMAGE EFFECT



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 5979

DEPTH 2138.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
RUN IN HOLE	1	0.0	0.0
	2	93.0	924.3
INITIAL HYDRO PRESSURE	3	124.0	924.3
INITIAL PREFLOW PRESSURE	4	124.0	94.6
FINAL PREFLOW PRESSURE	5	129.0	126.8
START INITIAL SHUT-IN	6	129.0	126.8
	7	134.0	822.5
	8	139.0	873.5
	9	144.0	886.5
	10	149.0	889.5
	11	154.0	891.4
INITIAL SHUT-IN PRESSURE	12	156.0	891.7
START FLOW PERIOD	13	156.0	891.7
INITIAL FLOW PRESSURE	14	157.0	181.7
	15	161.0	214.0
	16	166.0	265.2
	17	171.0	312.5
	18	176.0	355.2
	19	181.0	395.7
	20	186.0	433.6
	21	191.0	467.9
	22	196.0	501.2
	23	201.0	533.3
	24	206.0	563.0
	25	211.0	592.0
FINAL FLOW PRESSURE	26	216.0	614.1
START FINAL SHUT-IN	27	216.0	614.1
	28	221.0	837.5
	29	226.0	871.4
	30	231.0	882.8
	31	236.0	887.4
	32	241.0	889.5
	33	246.0	890.8



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 5979

DEPTH 2138.

MEASURED PRESSURES

	<u>POINT NUMBER</u>	<u>TIME MIN</u>	<u>PRESSURE PSIG</u>
	34	251.0	891.4
	35	256.0	891.7
	36	261.0	892.0
	37	266.0	892.3
	38	271.0	892.3
FINAL SHUT-IN PRESSURE	39	276.0	892.3
RUN OUT OF HOLE	40	276.0	892.3
FINAL HYDRO PRESSURE	41	277.0	924.3
	42	289.0	924.3
OUT OF HOLE	43	366.0	0.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 5979

DEPTH 2138.

CALCULATIONS FOR LIQUID RECOVERY (FIRST SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE	899.5
NO. OF POINTS CONSIDERED IN BUILD-UP	6
NO. OF POINTS USED IN EXTRAPOLATION	4
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI).....	0.21
EFFECTIVE PRODUCING TIME (MIN)	5.0



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 5979

DEPTH 2138.

DATA FOR BUILD-UP PLOT (FIRST SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------

PORTION OF BUILD-UP CURVE NOT USED IN EXTRAPOLATION

7	5.0	822.5			2.00
8	10.0	873.5			1.50

POINTS USED IN EXTRAPOLATION

9	15.0	886.5	886.6	0.2	1.33
10	20.0	889.8	889.5	-0.3	1.25
11	25.0	891.4	891.3	-0.0	1.20
12	27.0	891.7	891.9	0.2	1.19



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 5979

DEPTH 2138.

CALCULATIONS FOR LIQUID RECOVERY (SECOND SHUT-IN)

(A) EXTRAPOLATED RESERVOIR PRESSURE	895.3
NO. OF POINTS CONSIDERED IN BUILD-UP	12
NO. OF POINTS USED IN EXTRAPOLATION	7
ROOT MEAN SQUARE DEVIATION OF BEST-FIT LINE (PSI).....	0.13
EFFECTIVE PRODUCING TIME (MIN)	65.0
(B) IN SITU CAPACITY (KH - MD FT)	3341.91
SLOPE OF BUILD-UP CURVE (PSI/CYCLE)	8.76
PRODUCING RATE (BBL/DAY)	219.78
FLUID VISCOSITY (CP)	0.820
FORMATION VOLUME FACTOR (RES BBL/ST BBL).....	1.000
(C) EFFECTIVE PERMEABILITY (MD)	37.13
FORMATION THICKNESS	90.00
(D) PRODUCTIVITY INDEX (BBL/DAY/PSI)	0.78
FLOWING PRESSURE (PSIG)	614.1
(E) APPROXIMATE DRAINAGE RADIUS (FT)	267.3
TOTAL FLOWING TIME (MIN)	65.0
(F) ESTIMATED DAMAGE RATIO	5.86
RESERVOIR POROSITY (PERCENT)	9.00
TOTAL COMPRESSIBILITY (VOL/VOL/PSI X 10 ⁻⁶)	8.00
WELL-BORE RADIUS (IN)	4.375
CALCULATED SKIN FACTOR	30.63
(G) PRODUCTION WITH DAMAGE REMOVED (BBL/DAY)	1287.2



WELL NAME CANDEL MOBIL ET AL IROQUOIS I-11

DST. NO. 2

LOCATION I-11

REC. NO. 3979

DEPTH 2138.

DATA FOR BUILD-UP PLOT (SECOND SHUT-IN)

POINT NUMBER	TIME MIN	PRESSURE PSIG	PRESSURE CALC FROM BEST FIT LINE	PRESSURE DIFFERENCE CALC - OBSERVED	T+DELTA(T)/ DELTA(T)
-----------------	-------------	------------------	---	--	-------------------------

PORTION OF BUILD-UP CURVE NOT USED IN EXTRAPOLATION

28	5.0	837.5			14.00
29	10.0	871.4			7.50
30	15.0	882.8			5.33
31	20.0	887.4			4.25
32	25.0	889.5			3.60


POINTS USED IN EXTRAPOLATION

33	30.0	890.8	890.9	0.2	3.17
34	35.0	891.4	891.3	-0.1	2.86
35	40.0	891.7	891.6	-0.1	2.62
36	45.0	892.0	891.9	-0.1	2.44
37	50.0	892.3	892.1	-0.2	2.30
38	55.0	892.3	892.3	0.0	2.18
39	60.0	892.3	892.5	0.2	2.08

ASSUMPTIONS AND LIMITATIONS

THE ENCLOSED DST INTERPRETATION CALCULATIONS REQUIRE SEVERAL NECESSARY ASSUMPTIONS TO PROVIDE A QUICK ESTIMATE OF MANY OF THE FACTORS INVOLVED. AS A RESULT THE INFORMATION GAINED SHOULD BE USED TO FORM AN OPINION OR ESTIMATE ONLY, UNTIL THE ASSUMPTIONS OF RESERVOIR AND FLUID PROPERTIES CAN BE WHOLLY OR PARTIALLY CLARIFIED BY MORE COMPLETE ANALYSIS AND TESTING.

PRESSURE VS. TIME
CANDEL MOBIL ET AL IR000015 I-11
I-11
DST NO. 2 REC. NO.5979



915.0

HORNER PRES. EXTRAPOLATION
CANDEL MOBIL ET AL IADQUOIS I-11
I-11
DST NO. 2 $P_w = 895.3$

900.0

885.0

870.0

855.0

840.0

825.0

810.0

BOTTOM - HOLE PRESSURE (psig)

100

 $\frac{10}{(T + \Delta t) / \Delta t}$

1


FSI

ISI

▲


▲

CANDEL MOBIL ET AL IROQUOIS I-11
 INTERVAL 2121 - 2261
 DST NO. 2 REC. NO. 5773



DST RECORDER CHARTS

CANDEL MOBIL ET AL IROQUOIS I-11
 INTERVAL 2121 - 2261
 DST NO. 2 REC. NO. 5979



BJ

BORG X WARNER

DRILL STEM TEST REPORT

BJ SERVICE DIVISION
BORG-WARNER (CANADA) LIMITED

CANDEL MOBIL ET AL TROQUOIS

I-11

TEST NO. 3



DRILL-STEM TEST DATA

Well Name CANDEL ET AL IROQUOIS I-11	Test No. 3
Well Number I-11	Zone Tested RONNING
Company CANDEL OIL LTD.	Interval 3200.0 TO 3614.0
Comp. Rep. DOUG HADDOW	Tester LEO PENNER Date MAY 31, 1972

Type of Test **DUAL BOTTOM HOLE**RFS Tool No. **105**Preflow **5.0** mins. ISI **27.0** mins. Flow **114.0** mins. FSI **230.0** mins.

	OUT REC. No. 3852		OUT REC. No. 3689		REC. No.	
	5800	RANGE 12 HR. CLOCK	5700	RANGE 12 HR. CLOCK	RANGE	HR. CLOCK
DEPTH						
Initial Hydro Mud Press		3219.0		3225.0		
Initial Shut-In Press		1704.0		1707.0		
Initial Flow Press		1359.0		1361.9		
Final Flow Press		622.0		625.5		
Final Shut-In Press		1364.0		1367.6		
Final Hydro Mud Press		1368.0		1371.8		
		1704.0		1707.0		

Mud Drop YES	Fluid Loss	Mud Weight 10.3
Viscosity 29.0	Temperature °F 68.0	Net Pay Tested 130.0
Top Packer Depth 3200.0	Bottom Packer Depth	Total Depth 3614.0
Drill Pipe Size 3.5 IF	Wt. 13.5 Drill Collar I.D. 2.375	Ft. Run 450.00
Surface Choke Size CLOSED	Bottom Choke Size 0.5	Main Hole Size 8.750
Anchor Size 4.75	Rat Hole Size	Feet of Rat Hole
Cushion Amount	Type	Rubber Size 7.5

Fluid Recovery Total Feet **2820.0**
Recovered Feet of **RFS CONT. 2700 CC'S OF CLEAN SALT WATER**Recovered Feet of
Recovered Feet of
Recovered Feet of
Recovered Feet of
Recovered Feet of

Gas Recovery		How Measured		Riser size:	
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	= MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	= MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	= MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	= MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	= MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	= MCF/Day

Bleed Off Time for Drill Pipe

REMARKS: **PULL TEST UNTIL REACHED TOP OF FLUID RECOVERY. CAUGHT SAMPLE OF MUD THEN WHEN WE CONTINUED PULLING OUT OF THE HOLE THE PIPE WAS EMPTY. OUR TOOL HAS A PUMP-OFF FEATURE IN CASE IT IS NEEDED FOR FREEING THE PIPE WHEN STUCK THAT IS ACTIVATED BY APPLYING 500 PSI DIFFERENTIAL TO THE DRILL PIPE**



DRILL-STEM TEST DATA

Well Name CANDEL ET AL IROQUOIS I-11	Test No. 3
Well Number I-11	Zone Tested RONNING
Company CANDEL OIL LTD	Interval 3200.0 TO 3614.0
Comp. Rep. DOUG HADDOW	Tester LEO PENNER Date MAY 31, 1972

Type of Test

RFS Tool No.

Preflow

mins. ISI

mins. Flow

mins. FSI

mins.

DEPTH	REC. No.	HR. CLOCK	REC. No.	HR. CLOCK	REC. No.	HR. CLOCK
	RANGE		RANGE		RANGE	
Initial Hydro Mud Press						
Initial Shut-In Press						
Initial Flow Press						
Final Flow Press						
Final Shut-In Press						
Final Hydro Mud Press						

Mud Drop

Fluid Loss

Mud Weight

Viscosity

Temperature °F

Net Pay Tested

Top Packer Depth

Bottom Packer Depth

Total Depth

Drill Pipe Size

Wt.

Drill Collar I.D.

Ft. Run

Surface Choke Size

Bottom Choke Size

Main Hole Size

Anchor Size

Rat Hole Size

Feet of Rat Hole

Cushion Amount

Type

Rubber Size

Fluid Recovery Total Feet

Recovered

Feet of

Recovered

Feet of

Recovered

Feet of

Recovered

Feet of

Recovered

Feet of

Gas Recovery

How Measured

Riser size:

mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day
mins.	Temp. °F	Press Rdg.	psi	Orifice Size	=	MCF/Day

Bleed Off Time for Drill Pipe

REMARKS: **ALLOWING YOU TO CIRCULATE OR PRESSURE UP UNDER THE PACKERS. THE SAME RESULTS OCCUR IF THE HOLE IS NOT KEPT FULL WHILE PULLING TEST - THE RECOVERY OVERBALANCES THE ANNULUS PRESSURE BY 500 PSI.**



TESTING REPORT

WEIGHT INDICATOR READING
PRIOR TO SETTING PACKERS
AFTER PULL PACKERS LOOSE



	ID	OD	LENGTH
4S LANDING SUB			
4S CHAMBER			
4S TOOL OR P.O. SUB			1.00
CO SUB			1.00
SHUT IN TOOL		4 3/4	5.00
R.F.S. No. 105	2 1/4	4 3/4	3.25
R.F.S. No.	2 1/4	4 3/4	
HYDRAULIC TOOL		4 3/4	7.00
JARS	1	4 3/4	5.30
RECORDER No.	2 1/4	4 3/4	DEPTH
RECORDER No.	2 1/4	4 3/4	DEPTH
SAFETY JOINT	2 11/16	4 3/4	1.75
BY PASS SUB	1 5/32	4 3/4	
PACKER	1 OR 3/8	7 1/2	6.00
PACKER	1 OR 3/8	7 1/2	5.00
ANCHOR—SPECIFY	2 1/2		1.00
PERES			17.00
BLANK OFF OR BY PASS SUB	1 5/32	4 3/4	
RECORDER No. 3852	2 1/4	4 3/4	6.00
PACKER	1 OR 3/8		
PACKER	1 OR 3/8		
ANCHOR—SPECIFY	2 1/2		
DRILL PIPE		3 1/2 IF	377.00
RECORDER No. 3689	2 1/4	4 3/4	5.00
PERFS			5.00
BULLNOSE	2 3/4	4 3/4	2.50

DEPTH
DEPTH







TOOL ABOVE INTERVAL 35.30
DEPTH 3219

TOTAL INTERVAL 413.50

DEPTH 3225

TOTAL TAIL PIPE
TOTAL TEST TOOL 71.80

DST CHARTS FOR COMPARATIVE VISUAL ANALYSIS





WELL NAME CANDEL ET AL IROQUOIS I-11

DST. NO. 3

LOCATION I-11

REC. NO. 3689

DEPTH 3225.

MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
RUN IN HOLE	1	0.0	0.0
	2	81.0	1707.0
INITIAL HYDRO PRESSURE	3	107.0	1707.0
INITIAL PREFLOW PRESSURE	4	107.0	525.7
FINAL PREFLOW PRESSURE	5	112.0	575.7
START INITIAL SHUT-IN	6	112.0	575.7
	7	113.0	1332.4
	8	117.0	1357.7
	9	122.0	1359.1
	10	127.0	1360.5
	11	132.0	1360.5
	12	137.0	1361.9
INITIAL SHUT-IN PRESSURE	13	139.0	1361.9
START FLOW PERIOD	14	139.0	1361.9
INITIAL FLOW PRESSURE	15	140.0	625.5
	16	144.0	729.4
	17	149.0	846.1
	18	154.0	941.5
	19	159.0	1025.5
	20	164.0	1096.7
	21	169.0	1160.5
	22	174.0	1204.2
	23	179.0	1239.4
	24	184.0	1269.0
	25	189.0	1294.3
	26	194.0	1314.0
	27	199.0	1329.5
	28	204.0	1340.8
	29	209.0	1350.7
	30	214.0	1356.3
	31	219.0	1360.5
	32	224.0	1361.9
	33	229.0	1363.3
	34	234.0	1364.8
	35	239.0	1366.2



WELL NAME CANDEL ET AL IROQUOIS I-11

DST. NO. 3

LOCATION I-11


REC. NO. 3689

DEPTH 3225.


MEASURED PRESSURES

	POINT NUMBER	TIME MIN	PRESSURE PSIG
	36	244.0	1366.2
	37	249.0	1366.2
FINAL FLOW PRESSURE	38	253.0	1367.6
START FINAL SHUT-IN	39	253.0	1367.6
	40	258.0	1367.6
	41	263.0	1367.6
	42	273.0	1367.6
	43	283.0	1367.6
	44	293.0	1367.6
	45	303.0	1367.6
	46	313.0	1369.0
	47	323.0	1369.0
	48	333.0	1369.0
	49	343.0	1369.0
	50	353.0	1369.0
	51	363.0	1369.0
	52	373.0	1369.0
	53	383.0	1370.4
	54	393.0	1370.4
	55	403.0	1370.4
	56	413.0	1370.4
	57	423.0	1370.4
	58	433.0	1370.4
	59	443.0	1371.8
	60	453.0	1371.8
	61	463.0	1371.8
	62	473.0	1371.8
FINAL SHUT IN PRESSURE	63	483.0	1371.8
RUN OUT OF HOLE	64	483.0	1371.8
FINAL HYDRO PRESSURE	65	484.0	1707.0
	66	497.0	1707.0
OUT OF HOLE	67	572.0	0.0

PRESSURE VS. TIME
 CANDEL ET AL IROQUOIS I-11
 I-11
 OST NO. 3 REC. NO. 3689




CANDEL MOBIL ET AL IROQUOIS I-11
INTERVAL 3200 - 3614
DST NO. 3 REC. NO. 3852



DST RECORDER CHARTS

CANDEL MOBIL ET AL IROQUOIS I-11
INTERVAL 3200 - 3614
DST NO. 3 REC. NO. 3689



2 DATE JUNE 3 19 72

Rig No. 8 Page No. HO LOCATION CANDEL MOBILE ILLINOIS 7-11

Time		
Start	Stop	Interval

Rig No. 8 Report No. 40

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
										No.	O.D.	I.D.	Wgt.	Gals.		Bbls.		Gal.		Singles	
																		Bbls.			
B I T S	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars					
																Other Ft.					
																C.B. Ft.					
MUD		12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives					At Surveys Degree		MOTOR HOURS		Oil Added		Subs. Ft.				
WEIGHT																					
VISCOSITY																					
GEL																Ft. Down On Kelly					
P U M P S	No. 1	Pressure											Light				TOTAL				
	Model	S.P.M.											BOILER HRS.								
		Liner Size						Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	Next Slip				
	No. 2	Pressure																			
P S	Model	S.F.M.						Casing Record	Surface Prod.												
		Liner Size																			
W.L.		F.C.		pH.		Solids		Cement													

[illegible]

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller L BATEMAN	12.
Derrick GARRY BARNES	12.
Motor TOM MCALEX	12
Floor MERV GREFF	12
Floor KEN LEGUERIER	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

	From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER		CRUDE	Stands		
						No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	Singles			
													Bbls.			
B I T S	No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft.Reamed	Hrs.	COND.	D. Collars	
															Other Ft.	
															C.B. Ft.	
MUD		8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives				At Surveys Degree		MOTOR HOURS		Oil Added	Subs. Ft.	
WEIGHT												1				
VISCOSITY												2				
GEL												3			Ft. Down on Kelly	
P U M P S	No. 1	Pressure											Light Plant	P.	TOTAL	
	Model	S.P.M.											BOILER HRS.			
	Liner Size					Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	Next Slip	
	No. 2	Pressure														
	Model	S.P.M.					Casing Record	Surface Prod.								
	Liner Size															
W.L.		F.C.	pH.	Solids	Cement											

[illegible]

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor <i>Frank Devene.</i>	<i>16</i>
Floor	

Accidents

Outside Temp.

Weather Conditions

Road Conditions

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands
										No.	O.D.	I.D.	Wgt.	Gals.		Bbls.		Gal.		
																		Bbls.		
B I T S	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars				
																Other Ft.				
																	C.B. Ft.			
																	Subs. Ft.			
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives					At Surveys Degree		MOTOR HOURS		Oil Added		Ft. Down on Kelly			
WEIGHT													1							
VISCOSITY													2							
GEL													3				TOTAL			
P U M P S	No. 1 Model	Pressure											Light Plant							
	No. 2 Model	Pressure											BOILER HRS.							
S	Liner Size					Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	Next Slip					
	S.P.M.					Water Truck Hours:														
						Desilter Hours:														
W.L.		F.C.		pH.		Solids.		Desander Hours												

[illegible]

Tour — 4 p.m. to Midnight	
Specify actual hours worked,	Hrs.
Driller GARY HEWITT	12
Derrick HOWARD MACKIN	12
Motor GENE PLATO	12
Floor MEL GUNSON	12
Floor DON DOUGLAS	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher *[Signature]* Toolpusher *[Signature]*
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by Approved by

B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by Approved by

DATE June. 2. 1972.

NABORS DRILLING LIMITED

WORK RECORD

JUN 6 1972

DATE June 2 1972

Rig No. 8 Page No. 39 LOCATION Candel Mobil Inokhai I-11

NOTE: Do Not Record Payroll Information Here

REMARKS

Time		
Start	Stop	Interval

Rig No. 8 Report No. 34

B I T S	From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands				
											No.		O.D.		I.D.		Wgt.		Gals.			Bbls.		Gol.	
	No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft.Reamed	Hrs.	COND.											D. Collars
																									Other Ft.
																									C.B. Ft.
	MUD		12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives				At Surveys Degree				MOTOR HOURS		Oil Added								Subs. Ft.
	WEIGHT														1		8								Ft. Down On Kelly
	VISCOSITY														2		8								TOTAL
	GEL														3										
	No. 1	Pressure													Light Plant		8								
	Model	S.P.M.															BOILER HRS. 8								
	No. 2	Pressure													Slip		Feet or		Cut		Feet Left on Spool		Next Slip		
	Model	S.P.M.																							
	Liner Size																								
	Casing Record																								
	Surface Prod.																								
	W.L.	F.C.	pH.	Solids	Cement																				

B I T S	From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands													
											No.		O.D.		I.D.		Wgt.		Gals.			Bbls.		Gol.										
	No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft.Reamed	Hrs.	COND.											D. Collars									
																									Other Ft.									
																									C.B. Ft.									
	MUD		8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives				At Surveys Degree				MOTOR HOURS		Oil Added								Subs. Ft.									
	WEIGHT														1										Ft. Down On Kelly									
	VISCOSITY														2										TOTAL									
	GEL														3																			
	No. 1	Pressure													Light Plant																			
	Model	S.P.M.															BOILER HRS.																	
	Liner Size														Size		TRIPS		No. Lines		TON MILES		TOTAL MILES		Slip		Feet or		Cut		Feet Left on Spool		Next Slip	
	No. 2	Pressure																																
	Model	S.P.M.																																
	Liner Size				</																													

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	L Bateman	12
Derrick	G Baranov	12
Motor	T. McCarley	12
Floor	M Graft	12
Floor	K Legowski	12
Accidents Nil		
Outside Temp. 64		
Weather Conditions clear		
Road Conditions Poor		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller		
Derrick		
Motor	5 Jack Demare	16
Floor		
Floor		
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	G Hewitt	12
Derrick	H Macdon	12
Motor	G Pluta	12
Floor	M Benson	12
Floor	D Dauglon	12
Accidents Nil		
Outside Temp. 60		
Weather Conditions clear		
Road Conditions Poor		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher Jan. S. Keweenaw Toolpusher Jan. S. Keweenaw

B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

NABORS DRILLING LIMITED

WORK RECORD

JUN 6 1972 DATE June 1 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Page No. 38 LOCATION CANDEL MOBIL. IROQUOIS. I-11

Rig No. 8 Report No. 38.

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands							
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.		Singles			
																						Bbls.		D. Collars			
B		No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.		Other Ft.	
I																										C.B. Ft.	
T																										Subs. Ft.	
S																										Ft. Down On Kelly	
																										TOTAL	
																										Next Slip	

REMARKS	Time		
	Start	Stop	Interval
O.S.T No 3.	12 ⁰⁰	4 ⁰⁰	4.
Trip Out w/ Test 1.	4 ⁰⁰	7 ⁰⁰	2.
LAY DOWN TEST TOOL	7 ⁰⁰	8 ⁰⁰	1
With Pipe Without Pipe Standby			
LAY DOWN DRILL COLLARS.	8 ⁰⁰	10 ⁰⁰	2.
Trip in Run Plug No 3.	10 ⁰⁰	11 ⁰⁰	1
Run Plug No 3. @ 2150 To 2000	11 ⁰⁰	11 ³⁰	½.
W.O.C. TRIP OUT	11 ³⁰	4 ⁰⁰	4½.
Run Plug No 3. 100 SX 4 3/8" cal. cdy Felt Plug @ 2050.			
With Pipe Without Pipe Standby			
W.O.C.	4 ⁰⁰	7 ⁰⁰	3.
Trip in Felt Plug @ 2050.	7 ⁰⁰	8 ⁰⁰	½
Trip up to FOOT 30	8 ⁰⁰	8 ³⁰	½.
Run Plug No 4. 630 to 780	8 ³⁰	9 ⁰⁰	½.
W.O.C.	9 ⁰⁰	12 ⁰⁰	3.
FELT TOP OF PLUG NO 4 @ 623			
Run Plug No. 4. 100 SX 3 9/16" cal. cdy			
With Pipe Without Pipe Standby			

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller <u>L BATEMAN</u>	<u>12</u>
Derrick <u>GARRY BARNES</u>	<u>12</u>
Motor <u>TOM MCCOULEY</u>	<u>12</u>
Floor <u>MEAU GRIFF</u>	<u>12</u>
Floor <u>KEN LECUERRIER</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp. <u>65</u>	
Weather Conditions <u>clear</u>	
Road Conditions <u>poor</u>	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
<u>MECH. FRANK DENENE</u>	<u>12</u>
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller <u>GARY HEWITT</u>	<u>12</u>
Derrick <u>HOWARD JACKSON</u>	<u>12</u>
Motor <u>GENE FLATO</u>	<u>12</u>
Floor <u>WELK GUNSON</u>	<u>12</u>
Floor <u>DON DOUGLAS</u>	<u>12</u>
<u>BURKE MORIARTY</u>	<u>6</u>
Accidents <u>GENE FLATO - INJURED</u>	
Outside Temp. <u>64</u>	
Weather Conditions <u>clear</u>	
Road Conditions <u>fair</u>	

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher In Wessberg Toolpusher In Wessberg
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE MAY 30 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 30 1972

Rig No. 8 Page No. 36 LOCATION CANDEL MOBILE IROLOUIS I-11

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6961					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	
B I T S No. 21 Size 8 1/2 Type W07 OPEN Serial No. 38284 Wt. 112 R.P.M. 6 From To Ftg. Hrs. Ft. Reamed Hrs. COND. 62601 MUD 12 a.m. 2 p.m. 4 a.m. 6 a.m. Additives At Surveys Degree MOTOR HOURS Oil Added WEIGHT 10-3 SALT 280 VISCOSITY 30 FIBER SEAL 55K. GEL P U M No. 1 Pres- 800-700 Model S.P.M. 40-45 No. 2 Pres- 512 X 15 Model S.P.M. 112 12 6 85 1585 No. 3 Pres- Model S.P.M. W.L. F.C. pH 10.3 Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	
B I T S No. 21 Size 8 1/2 Type W07 OPEN Serial No. 38284 Wt. 112 R.P.M. 6 From To Ftg. Hrs. Ft. Reamed Hrs. COND. 62601 MUD 8 a.m. 10 a.m. 12 p.m. 2 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added WEIGHT VISCOSITY GEL P U M No. 1 Pres- Model S.P.M. No. 2 Pres- Model S.P.M. W.L. F.C. pH Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	
B I T S No. 21 Size 8 1/2 Type W07 OPEN Serial No. 38284 Wt. 112 R.P.M. 6 From To Ftg. Hrs. Ft. Reamed Hrs. COND. 62601 MUD 4 p.m. 6 p.m. 8 p.m. 10 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added WEIGHT VISCOSITY GEL P U M No. 1 Pres- 300-150 Model S.P.M. 45-150 No. 2 Pres- 512 X 15 Model S.P.M. 112 12 6 245 1743 No. 3 Pres- Model S.P.M. W.L. F.C. pH Solids Cement												

REMARKS	Start	Time	Interval
CIRC W.O.O.	1200	800	8
X Mud Loss 5 BBL Per Hr. 5 MIN SAFETY HOW TO OPERATE & STARING VALVE			

REMARKS	Start	Time	Interval
CIRC W.O.O.	800	400	8
Mud Loss 5 BBL Per Hr.			

REMARKS	Start	Time	Interval
CIRC W.O.O.	400	715	314
TRIP OUT	715	930	214
LAY DOWN 16 COLLARS	930	1100	112
TRIP IN OPEN ENDED	1100	1210	110
HELD 5 MIN SAFETY MEETING - PAPER WAY TO LIFT -			

Rig No. 8 Report No. 36

Tour	Midnight - 8 a.m.	Hrs.
Specify actual hours worked.		
Driller	L BATEMAN	12
Derrick	GARY BARNES	12
Motor	TOM MCCAULEY	12
Floor	MERV GRIFF	12
Floor	KEN LEGUERRIER	12
Accidents NIL		
Outside Temp.		
Weather Conditions CLOUDY		
Road Conditions NIL		

Tour	8 a.m. to 4 p.m.	Hrs.
Specify actual hours worked.		
Driller		
Derrick		
Motor		
Floor		
Floor	May 29	
MECH FRANK DERRICK 12		
May 30		
FRANK DERRICK 12		
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		

Tour	4 p.m. to Midnight	Hrs.
Specify actual hours worked.		
Driller	GARY HEWITT	12
Derrick	HOWARD MERRILL	12
Motor	GARY HEWITT	12
Floor	MERV GRIFF	12
Floor	DAN DOUGLAS	12
Accidents NIL		
Outside Temp. 25		
Weather Conditions Cloudy		
Road Conditions NIL		

Totco Ring on Bit No. _____ D.P. Caliper Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____
 B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____

Toolpusher _____ Approved by _____

DATE MAY 29 1972

REMARKS

[illegible]

Tour — Midnight - 8 a.m.		
Specify actual hours worked.	Hrs.	
Driller	L BATEMAN 12	
Derrick	GARRY BARSNESS 12	
Motor	TOM MCCAULEY 12	
Floor	MERV GREFF 12	
Floor	KEN LEGUERRIER 12	
Accidents		
Outside Temp.		
Weather Conditions CLOUDY		
Road Conditions NIL		
Tour — 8 a.m. to 4 p.m.		
Specify actual hours worked.	Hrs.	
Driller		
Derrick		
Motor		
Floor		
Floor		
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
Specify actual hours worked.	Hrs.	
Driller	GARY HEWITT 12	
Derrick	HOWARD MCKINLEY 12	
Motor	GEORGE FLATO 12	
Floor	MEL GUANSON 12	
Floor	DON DOUGLAS 12	
Accidents NIL		
Outside Temp. 95		
Weather Conditions Overcast		
Road Conditions NIL		

Toolpusher James A. [Signature]
Approved by _____

DATE MAY 28 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 28 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Page No. 34 LOCATION CANDEL MORIA TROCUDIS I-11

REMARKS

Time
Start Stop Interval

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS			FUEL	WATER	CRUDE	Stands			
6959	2	6961	1/4	11400	No. 5	O.D. 4 1/2	I.D. 2 3/8	Wgt.	Gals.	Bbls.	Gal.			
											Singles			
											Bbls.			
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars
20	8 3/4	WD 7	OPFN	38284	45	50	6923	6961	38	4 1/2				12601
											Other Ft.			
											C.B. Ft.			
											Subs. Ft.			
											Ft. Down on Kelly			
											TOTAL			
											6961			
											BOILER HRS.			
											2			
											Next Slip			
											HO90 THIS			
											5 MIN SAFETY OIL - GREASE OFF FLOOR OR ANYTHING SLIPPERY.			
											With Pipe			
											Without Pipe			
											Standby			

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS			FUEL	WATER	CRUDE	Stands			
6961					No. 5	O.D. 4 1/2	I.D. 2 3/8	Wgt.	Gals.	Bbls.	Gal.			
											Singles			
											Bbls.			
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars
0														62601
											Other Ft.			
											C.B. Ft.			
											Subs. Ft.			
											Ft. Down on Kelly			
											TOTAL			
											4H8			
											BOILER HRS.			
											Next Slip			
											With Pipe			
											Without Pipe			
											Standby			

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS			FUEL	WATER	CRUDE	Stands			
					No. 5	O.D. 4 1/2	I.D. 2 3/8	Wgt.	Gals.	Bbls.	Gal.			
											Singles			
											Bbls.			
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars
											Other Ft.			
											C.B. Ft.			
											Subs. Ft.			
											Ft. Down on Kelly			
											TOTAL			
											BOILER HRS.			
											Next Slip			
											With Pipe			
											Without Pipe			
											Standby			

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rock _____ Total Contractor Time _____ Hrs. Toolpusher _____
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____Rig No. 8 Report No. 34

Tour - Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller	L BATEMAN 12
Derrick	GARY BARNES 12
Motor	TOM McCAULEY 12
Floor	MEAN GREEFF 12
Floor	KEN LEGIER 12
Accidents	
Outside Temp. 25	
Weather Conditions CLEAR	
Road Conditions	

Tour - 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
Accidents	
Outside Temp. 50	
Weather Conditions CLEAR + SUNNY	
Road Conditions	

Tour - 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller	GARY HEWITT 12
Derrick	HOWARD MCKINLEY 12
Motor	GENE FLATC 12
Floor	MEAN GREEFF 12
Floor	DAN DOUGLAS 12
Accidents	
Outside Temp. 48	
Weather Conditions OVERCAST - RAIN	
Road Conditions	

DATE MAY 27 19 72

HABORS DRILLING LIMITED

WORK RECORD

DATE MAY 27 19 72Rig No. 8 Page No. 33 LOCATION CANDEL MOBIL IRGUCOIG-I-II

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6812	74	6886	7 3/4	112000	No. 5	O.D. 6 1/2	I.D. 3 3/8	Wgt. 116	Gals.	Bbls.	Gal.	Singles
B 19 8 3/4 X 55R OPEN 26663 45 4 1/2 6742 6886 144 16 3/4												
MUD 12 a.m. 2 a.m. 4 a.m. 6 a.m. Additives 150# Carbox Soda												
WEIGHT 9.3 9.3 9.3 9.3												
VISCOSITY 30 30 30 30												
GEL												
P No. 1 Pressure 900 900 900 900												
Model S.P.M. 48 48 48 48												
Liner Size 5 1/2 X 15												
M No. 2 Pressure 14 3 1/2 6 512 1271												
Model S.P.M.												
Liner Size 5 1/2 X 14												
W.L. F.C. pH. 11.5 Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6886	37	6923	5 1/4	112	No. 5	O.D. 6 1/2	I.D. 3 3/8	Wgt. 116	Gals.	Bbls.	Gal.	Singles
B 19 8 3/4 X 55R OPEN 26663 45 4 1/2 6742 6923 181 22												
MUD 8 a.m. 10 a.m. 12 p.m. 2 p.m. Additives												
WEIGHT 9.3 9.3												
VISCOSITY 27 27												
GEL												
P No. 1 Pressure 900												
Model S.P.M. 48												
Liner Size												
M No. 2 Pressure												
Model S.P.M.												
Liner Size												
W.L. F.C. pH. 11.5 Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6923	36	6959	4 1/2	112	No. 5	O.D. 6 1/2	I.D. 3 3/8	Wgt. 116	Gals.	Bbls.	Gal.	Singles
B 20 8 3/4 WD7 OPEN 38384 45 50 6923 6959 36 4 1/2												
MUD 4 p.m. 6 p.m. 8 p.m. 10 p.m. Additives												
WEIGHT 9.3 9.3												
VISCOSITY 26 26												
GEL												
P No. 1 Pressure 900												
Model S.P.M. 48												
Liner Size												
M No. 2 Pressure												
Model S.P.M.												
Liner Size												
W.L. F.C. pH. 11.5 Solids Cement												

REMARKS

Time
Start Stop Interval

621237 DRILL 8 3/4 HOLE
RIG SERV + KEY COCK
62601 DRILL 8 3/4 HOLE
5 GAL INHIBITER
CLEAN RIG IS @ SAFE RIG 5 MIN.
4 1/2 BBL. FROM DAEMIX TO SYSTEM
PUMP FUEL

With Pipe Without Pipe Standby

RIG SERV
DRILL 8 3/4 HOLE
TRIP
8 00 8 15 1/4
8 15 1 30 5 1/4
1 30 4 00 2 1/2

With Pipe Without Pipe Standby

TRIP - RIG SERV - BLIND PANS
BREAK CIRC + CLEAN TO BTM
DRILL 8 3/4 HOLE
4 00 7 00 3
7 00 7 30 1/2
7 30 12 00 4 1/2

HELD SMIL SAFETY MEETING
- BRIDGER 1 WAY TO USE SPINNING CHAIN -

With Pipe Without Pipe Standby

Rig No. 8 Report No. 33

Tour — Midnight - 8 a.m.
Specify actual hours worked. Hrs.
Driller L BATEMAN 12
Derrick GARY BARNES 12
Motor TOM MCCAULEY 12
Floor MERY GREEFF 12
Floor KEN LEGUERRIER 12

Accidents NIL
Outside Temp. 30
Weather Conditions CLEAR
Road Conditions NO

Tour — 8 a.m. to 4 p.m.
Specify actual hours worked. Hrs.

Driller
Derrick
Motor
Floor
Floor
MECH FRANK DELERIE 12

Accidents NIL
Outside Temp. 45
Weather Conditions CLEAR + SUNNY
Road Conditions NIL

Tour — 4 p.m. to Midnight
Specify actual hours worked. Hrs.

Driller GARY HEWITT 12
Derrick HOWARD MACKOW 12
Motor GENE ELATO 12
Floor MEL GUNSDAL 12
Floor DEAN DOUGLAS 12

Accidents NIL
Outside Temp. 30
Weather Conditions CLEAR + SUNNY
Road Conditions NIL

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____
Toolpusher _____
Approved by _____

DATE May 26 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 32

REMARKS	Time		
	Start	Stop	Interval
DRILG 8 3/4 HOLE	12 ⁰⁰	130	1 1/2
PIC SERV ✓ HYDRIL	130	145	1/4
DRILG 8 3/4 HOLE	145	8 ⁰⁰	6 1/4
8			
— HELD 5 MIN SAFETY MEETING — — WORKING AROUND THE SAFE CONDITIONS —			
With Pipe	Without Pipe	Standby	
DRILG	8 ⁰⁰	9 ⁰⁰	1
DROP SURVEY 2 1/2°	9 ⁰⁰	9 ¹⁵	1/4
TRIP	9 ¹⁵	12 ⁰⁰	2 3/4
PIC SERV & BLIND RIGS, HYDRIL RIGS	12 ⁰⁰		
CONTROLLED MOTOR KILLS & CROWD SAYS		12 ¹⁵	1/4
TRIP IN SLOW	12 ¹⁵	2 ³⁰	2 1/4
BREAK CIRC & CLEAN TO BOTTOM	2 ³⁰	2 ⁴⁵	1/4
DRILG	2 ⁴⁵	4 ⁰⁰	1 1/4
With Pipe	Without Pipe	Standby	
DRILG 8 3/4 HOLE	4 ⁰⁰	4 ⁴⁵	3/4
PIC SERV - CONSERVATION BOARD	4 ⁴⁵		
CHECKED PIPE RANGS HYDRIL - M. H. P. SMITH		5 ⁰⁰	1/4
DRILG 8 3/4 HOLE (ALL O.K.)	5 ⁰⁰	12 ¹⁰	7
Set Up M.O.			
CONSERVATION BOARD CHECK ROP DRILL			
With Pipe	Without Pipe	Standby	

Tour — Midnight - 8 a.m.		
Specify actual hours worked.	Hrs.	
Driller	CARY HEWITT	17
Derrick	DALE BEN	12
Motor	CARL COLLINS	12
Floor	CHARLES HENNING	12
Floor	DAVE HADLICKA	12
Accidents Nil		
Outside Temp. 20		
Weather Conditions OVERCAST		
Road Conditions Nil		
Tour — 8 a.m. to 4 p.m.		
Specify actual hours worked.	Hrs.	
Driller	BRIAN KIDALE	12
Derrick		
Motor	TOM MCCAULEY	12
Floor	MERV GAFFE	12
Floor	KEN LEGUERRIER	12
	FRANK PERONE	12
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
Specify actual hours worked.	Hrs.	
Driller	LORNE BATEMAN	12
Derrick	HOWARD MACDON	12
Motor	GERRY BARNES	12
Floor	MEI GUNSAULT	12
Floor	GEOFF ELATO	12
Floor	DON DINGLAS	12
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher Don Weisberg Toolpusher Don Weisberg
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6505	65	6570	7 1/4	110	No. 5	O.D. 6 1/2	I.D. 5 1/2	Wgt. 16 1/2	Gals.	Bbls.	Gal.	904 3/4
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Fr. Reamed	Hrs.
18	8 3/4	R-SSR	OPEN	38288	45	45	6500	6570	70	9 1/2		
MUD 12 a.m. 2 a.m. 4 a.m. 6 a.m. Additives At Surveys Degree MOTOR HOURS Oil Added												
WEIGHT 10.3 10.3 10.3												
VISCOSITY 30 30 30 40 BBLS FROM PREMIX												
GEL												
P U M S												
No. 1	Pres. 900	—	700									
Model C	S.P.M. 48	—	48									
Liner Size 5 1/2 X 13												
No. 2	Pres. —	—	—	Size 1 1/8	TRIPS 2 1/2	No. Lines 6	TON MILES 359	TOTAL MILES 1118	Slip —	Feet Left on Spool —	Cut —	Next Slip 4090 @ 700
Model 214	S.P.M. —											
Liner Size 5 1/2 X 14												
W.L. 1,000 F.C. pH. Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6570	60	6630	7 1/2	111 M	No. 5	O.D. 6 1/2	I.D. 5 1/2	Wgt. 16 1/2	Gals.	Bbls.	Gal.	626
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Fr. Reamed	Hrs.
18	8 3/4	R-SSR	PUT	38288	45	45	6500	6630	130	17 1/2		
MUD 8 a.m. 10 a.m. 12 p.m. 2 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added												
WEIGHT 10.2 10.2 10.2 SALT 40 SXS												
VISCOSITY 30 30												
GEL												
P U M S												
No. 1	Pres. 900	✓	900									
Model C	S.P.M. 48	✓	48									
Liner Size 5 1/2 X 13												
No. 2	Pres. —	—	—	Size 1 1/8	TRIPS 2 1/2	No. Lines 6	TON MILES 359	TOTAL MILES 1118	Slip —	Feet Left on Spool —	Cut —	Next Slip 4090 700
Model 214	S.P.M. —											
Liner Size 5 1/2 X 14												
W.L. F.C. pH. Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6630	59	6689	7 1/2	112 M	No. 5	O.D. 6 1/2	I.D. 5 1/2	Wgt. 16 1/2	Gals.	Bbls.	Gal.	6183
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Fr. Reamed	Hrs.
18	8 3/4	R-SSR	OPEN	38288	45	45	6500	6689	189	25		
MUD 4 p.m. 6 p.m. 8 p.m. 10 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added												
WEIGHT 10.2 10.2 10.2 10.2 SALT 60 SXS												
VISCOSITY 31 30 30 30												
GEL												
P U M S												
No. 1	Pres. 900	✓	900									
Model C	S.P.M. 48	✓	48									
Liner Size 5 1/2 X 15												
No. 2	Pres. —	—	—	Size 1 1/8	TRIPS 2 1/2	No. Lines 6	TON MILES 359	TOTAL MILES 1118	Slip —	Feet Left on Spool —	Cut —	Next Slip 4090 @ 700
Model 214	S.P.M. —											
Liner Size 5 1/2 X 14												
W.L. F.C. pH. Solids Cement												

REMARKS	Time		
	Start	Stop	Interval
DRAG 8 3/4 HOLE	12 00	12 45	3/4
RIG SERV V HYDRA	12 45	1 00	1/4
DRAG 8 3/4 HOLE	1 00	8 00	7
- HELD 5 MIN SAFETY MEETING -			
- OPERATION OF EQUIPMENT OUT AROUND RIG -			
With Pipe	Without Pipe	Standby	
DRAG 8 3/4 HOLE	8 00	8 30	1/2
RIG SERV V 3 1/2 RAMPS	8 30	8 45	1/4
DRAG 8 3/4 HOLE	8 45	4 00	7 1/4
With Pipe	Without Pipe	Standby	
DRAG	4 00	5 00	1
RIG SERV V KELLY COCK	5 00	5 15	1/4
DRAG	5 15	17 00	6 3/4
With Pipe	Without Pipe	Standby	

Tour — Midnight - 8 a.m.	
Specify actual hours worked. Hrs.	
Driller GARY HEWITT	12
Derrick DALE BELL	12
Motor CARL COLLINS	12
Floor CHARLES HEWITT	12
Floor DAVE HODLUKA	12
Accidents Nil	
Outside Temp. 15	
Weather Conditions OVERCAST	
Road Conditions Nil	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked. Hrs.	
Driller	
Derrick	
Motor	
Floor	
Floor	
MECH FRANK DEWENE	12
Accidents Nil	
Outside Temp. + 45	
Weather Conditions SUNNY	
Road Conditions Nil	
Tour — 4 p.m. to Midnight	
Specify actual hours worked. Hrs.	
Driller BRIAN RIDDLE	12
Derrick HOWARD MACKIN	12
Motor GARRY BARNES	12
Floor MEL GUNSON	12
Floor GENE FLATO	12
Accidents Nil	
Outside Temp. + 45	
Weather Conditions SUNNY	
Road Conditions Nil	

DATE May 24 1972

NABORS DRILLING LIMITED

I-11

WORK RECORD

DATE May 24 1972

Rig No. 8 Page No. 30

LOCATION CANDEL MOBILE ILLINOIS

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 30

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS		FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
17		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
18		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
19		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
20		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
21		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
22		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
23		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
24		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
25		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
26		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
27		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
28		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
29		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
30		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
31		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
32		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
33		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
34		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
35		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
36		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
37		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
38		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
39		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
40		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
41		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
42		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
43		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
44		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
45		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
46		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
47		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
48		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
49		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
50		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
51		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
52		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
53		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
54		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
55		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
56		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
57		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
58		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
59		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
60		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
61		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
62		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
63		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
64		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
65		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
66		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
67		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
68		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
69		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
70		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
71		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
72		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
73		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
74		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
75		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
76		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
77		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
78		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
79		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
80		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
81		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
82		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
83		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
84		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
85		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
86		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
87		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
88		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
89		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
90		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
91		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
92		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
93		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
94		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
95		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
96		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
97		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
98		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
99		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
100		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
101		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
102		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
103		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
104		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
105		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
106		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
107		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
108		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
109		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
110		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
111		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
112		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
113		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
114		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
115		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
116		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
117		8 3/4		X53R		DUT		31208		45		45		6350		6429		79	
118		8 3/4		X53R		DUT		31208		45		45							

DATE May 23 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE May 23 1972Rig No. 8 Page No. 29LOCATION CANDEL MOBIL IROQUOIS 11-1

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS	FUEL	WATER	CRUDE	Stands				
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.
6326	24	6350	500	103	10 1/4	10 1/4	2 1/2						
MUD 12 a.m. 2 a.m. 4 a.m. 6 a.m. Additives SALT 100SX At Surveys Degree MOTOR HOURS Oil Added													
WEIGHT 103 10.3 VISCOSITY 30 30 GEL													
P. No. 1 Pres. 925 S.P.M. 49													
U. Model 220 Liner 5 1/2 X 15 Size TRIPS No. Lines TON MILES TOTAL MILES Slip Feet or Cut Feet Left on Spool Next Slip													
M. No. 2 Pres. 925 S.P.M. 49													
S. Model 214 Liner 5 1/2 X 14 Casing Record Surface Prod.													
W.L. F.C. pH. Solids Cement													
6350	20	6370	4 1/2	105	10 1/4	10 1/4	2 1/2						
MUD 8 a.m. 10 a.m. 12 p.m. 2 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added													
WEIGHT 103 10.2 VISCOSITY 30 31 GEL													
P. No. 1 Pres. 925 S.P.M. 49													
U. Model 220 Liner 5 1/2 X 15 Size TRIPS No. Lines TON MILES TOTAL MILES Slip Feet or Cut Feet Left on Spool Next Slip													
M. No. 2 Pres. 925 S.P.M. 49													
S. Model 214 Liner 5 1/2 X 14 Casing Record Surface Prod.													
W.L. F.C. pH. Solids Cement													
6370	25	6395	7 1/2	105	10 1/4	10 1/4	2 1/2						
MUD 4 p.m. 6 p.m. 8 p.m. 10 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added													
WEIGHT 10.2 10.2 VISCOSITY 31 30 31 31 GEL													
P. No. 1 Pres. 925 S.P.M. 49													
U. Model 220 Liner 5 1/2 X 15 Size TRIPS No. Lines TON MILES TOTAL MILES Slip Feet or Cut Feet Left on Spool Next Slip													
M. No. 2 Pres. 925 S.P.M. 49													
S. Model 214 Liner 5 1/2 X 14 Casing Record Surface Prod.													
W.L. F.C. pH. Solids Cement													

REMARKS	Start	Stop	Interval
DRLG 8 3/4 HOLE	12 00	5 00	5 00
TRIP - STRAP PIPE	5 00	8 00	3 00
RIG SERV BLIND RAMS	8 00	8 15	1/4
BREAK CIRC - DEAL 5' to BTM	11 00	11 15	1/4
DRLG 8 3/4 HOLE	11 15	4 00	4 3/4
DRLG.	4 00	7 00	3 00
RIG SERV BLIND RAMS	7 00	7 15	1/4
DRLG.	7 15	12 00	4 45

Rig No. 8 Report No. 29

Tour - Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller GARY HEWITT	12
Derrick DALE BELL	12
Motor CARL COLLINS	12
Floor CHARLES HENNING	12
Floor DALE HRODICKA	12
Accidents NIL	
Outside Temp. 5	
Weather Conditions SNOWING	
Road Conditions NIL	
Tour - 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
FRANK DENNE	12
Accidents NIL	
Outside Temp.	
Weather Conditions OVERCAST	
Road Conditions NIL	
Tour - 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller BOB ROGERS	12
Derrick HOWARD MCKAY	12
Motor GERRY BARNES	12
Floor MEL GUNSON	12
Floor GENE FLETO	12
Accidents NIL	
Outside Temp.	
Weather Conditions OVERCAST WINDY SUNSET	
Road Conditions NIL	

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher Don Wootley

B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____

Toolpusher Don Wootley

Approved by _____

DATE May 22 19 72

NABORS DRILLING LIMITED

WORK RECORD

DATE May 22 19 72Rig No. 8 Page No. 28 LOCATION CANDEL MOBIL IROQUOIS 11-1

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 28

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
6231		49		6280		7 1/2		108		50		6119		6280		161		27 1/2		5610 19	
15		8 1/2		XSSR		OUT		38291		40		50		6119		6280		161		27 1/2	
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		10.3		10.4		10.4		10.4		CAUSTIC 35XS										11 80	
VISCOSITY		30		30		31		30												Ft. Down On Kelly	
GEL																				TOTAL	
P		No. 1		Pres-ure		850		-		850										Light Plant	
U		Model		S.P.M.		48		-		48										BOILER HRS.	
M		250		Liner Size		5 1/2 X 15				Size		TRIPS		No. Lines		TON MILES		TOTAL MILES		Slip	
P		No. 2		Pres-ure		118		6 1/2		6		687		687		-		-		Feet Left on Spool	
S		Model		S.P.M.						Casing Record		Surface		Prod.						Next Slip	
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
6280		17		6287		1 1/2		102		50		6119		6285		166		26		6-8-1	
15		8 1/2		XSSR		OUT		38291		45		45		6119		6285		166		26	
16		8 1/2		WD7		OPEN		40025		40		45		6285		6287		2		1/4	
MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		10.3		10.3		10.3		10.3												9.48	
VISCOSITY		30		30		30		30												Ft. Down On Kelly	
GEL																				TOTAL	
P		No. 1		Pres-ure		850		-		850										Light Plant	
U		Model		S.P.M.		48		-		48										BOILER HRS.	
M		250		Liner Size		5 1/2 X 15				Size		TRIPS		No. Lines		TON MILES		TOTAL MILES		Slip	
P		No. 2		Pres-ure		118		7		6		759		882		60		60		Feet Left on Spool	
S		Model		S.P.M.						Casing Record		Surface		Prod.						Next Slip	
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
6287		39		6326		7 1/2		102		50		6119		6326		41		8		626.01	
15		8 1/2		WD7		OPEN		40025		40		45		6285		6326		41		8	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		10.2		10.2		10.2		10.2		SALT - 180 SXS										9.48	
VISCOSITY		31		30		31		31		SALT - 180 SXS										Ft. Down On Kelly	
GEL																				TOTAL	
P		No. 1		Pres-ure		900		-		900										Light Plant	
U		Model		S.P.M.		48		-		48										BOILER HRS.	
M		250		Liner Size		5 1/2 X 15				Size		TRIPS		No. Lines		TON MILES		TOTAL MILES		Slip	
P		No. 2		Pres-ure		118		5		6		73		832		-		-		Feet Left on Spool	
S		Model		S.P.M.						Casing Record		Surface		Prod.						Next Slip	
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
6287		39		6326		7 1/2		102		50		6119		6326		41		8		626.01	
15		8 1/2		WD7		OPEN		40025		40		45		6285		6326		41		8	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		10.2		10.2		10.2		10.2		SALT - 180 SXS										9.48	
VISCOSITY		31		30		31		31		SALT - 180 SXS										Ft. Down On Kelly	
GEL																				TOTAL	
P		No. 1		Pres-ure		900		-		900										Light Plant	
U		Model		S.P.M.		48		-		48										BOILER HRS.	
M		250		Liner Size		5 1/2 X 15				Size		TRIPS		No. Lines		TON MILES		TOTAL MILES		Slip	
P		No. 2		Pres-ure		118		5		6		73		832		-		-		Feet Left on Spool	
S		Model		S.P.M.						Casing Record		Surface		Prod.						Next Slip	
W.L.		F.C.		pH.		Solids		Cement													

REMARKS	Time		
	Start	Stop	Interval
DRUG 7 3/4 HOLE	12:00	4:00	4
RIG SERV ✓ HYDRIL	4:15	4:15	1/4
DRUG 7 3/4 HOLE	4:15	8:00	3 3/4
CANDEL MOBIL etal IROQUOIS 1 - 11 67° 50' N 129° 30' W			
HELD 5 MIN SAFETY MEETING - BLIND OUT - OUTSIDE			
DRUG 7 3/4 HOLE	7:00	9:15	1 1/4
TRIP - SURVEY @ 6285	9:15	12:00	2 3/4
RIG SERV BLIND RAMP MARK			
LAY DOWN JUNK SUB		12:30	1/2
SLIP & CUT 60' DRUG LINE	12:30	1:30	1
TRIP IN	1:30	2:20	2
BREAK CIRC. CLEAN TO BOTTOM	3:30	3:45	1/4
DRUG	3:45	4:00	1/4
DRUG	4:00	4:15	1/4
DRUG	4:15	4:30	1/4
DRUG	4:30	4:45	1/4
DRUG	4:45	5:00	1/4
DRUG	5:00	5:15	1/4
DRUG	5:15	5:30	1/4
DRUG	5:30	5:45	1/4
DRUG	5:45	6:00	1/4
DRUG	6:00	6:15	1/4
DRUG	6:15	6:30	1/4
DRUG	6:30	6:45	1/4
DRUG	6:45	7:00	1/4
DRUG	7:00	7:15	1/4
DRUG	7:15	7:30	1/4
DRUG	7:30	7:45	1/4
DRUG	7:45	8:00	1/4
DRUG	8:00	8:15	1/4
DRUG	8:15	8:30	1/4
DRUG	8:30	8:45	1/4
DRUG	8:45	9:00	1/4
DRUG	9:00	9:15	1/4
DRUG	9:15	9:30	1/4
DRUG	9:30	9:45	1/4
DRUG	9:45	10:00	1/4
DRUG	10:00	10:15	1/4
DRUG	10:15	10:30	1/4
DRUG	10:30	10:45	1/4
DRUG	10:45	11:00	1/4
DRUG	11:00	11:15	1/4
DRUG	11:15	11:30	1/4
DRUG	11:30	11:45	1/4
DRUG	11:45	12:00	1/4
DRUG	12:00	12:15	1/4
DRUG	12:15	12:30	1/4
DRUG	12:30	12:45	1/4
DRUG	12:45	1:00	1/4
DRUG	1:00	1:15	1/4
DRUG	1:15	1:30	1/4
DRUG	1:30	1:45	1/4
DRUG	1:45	2:00	1/4
DRUG	2:00	2:15	1/4
DRUG	2:15	2:30	1/4
DRUG	2:30	2:45	1/4
DRUG	2:45	3:00	1/4
DRUG	3:00	3:15	1/4
DRUG	3:15	3:30	1/4
DRUG	3:30	3:45	1/4
DRUG	3:45	4:00	1/4
DRUG	4:00	4:15	1/4
DRUG	4:15	4:30	1/4
DRUG	4:30	4:45	1/4
DRUG	4:45	5:00	1/4
DRUG	5:00	5:15	1/4
DRUG	5:15	5:30	1/4
DRUG	5:30	5:45	1/4
DRUG	5:45	6:00	1/4
DRUG	6:00	6:15	1/4
DRUG	6:15	6:30	1/4
DRUG	6:30	6:45	1/4
DRUG	6:45	7:00	1/4
DRUG	7:00	7:15	1/4
DRUG	7:15	7:30	1/4
DRUG	7:30	7:45	1/4
DRUG	7:45	8:00	1/4
DRUG	8:00	8:15	1/4
DRUG	8:15	8:30	1/4
DRUG	8:30	8:45	1/4
DRUG	8:45	9:00	1/4
DRUG	9:00	9:15	1/4
DRUG	9:15	9:30	1/4
DRUG	9:30	9:45	1/4
DRUG	9:45	10:00	1/4
DRUG	10:00	10:15	1/4
DRUG	10:15	10:30	1/4
DRUG	10:30	10:45	1/4
DRUG	10:45	11:00	1/4
DRUG	11:00	11:15	1/4
DRUG	11:15	11:30	1/4
DRUG	11:30	11:45	1/4
DRUG	11:45	12:00	1/4
DRUG	12:00	12:15	1/4
DRUG	12:15	12:30	1/4
DRUG	12:30	12:45	1/4
DRUG	12:45	1:00	1/4
DRUG	1:00	1:15	1/4
DRUG	1:15	1:30	1/4
DRUG	1:30	1:45	1/4
DRUG	1:45	2:00	1/4
DRUG	2:00	2:15	1/4
DRUG	2:15	2:30	1/4
DRUG	2:30	2:45	1/4
DRUG	2:45	3:00	1/4
DRUG	3:00	3:15	1/4
DRUG	3:15	3:30	1/4
DRUG	3:30	3:45	1/4
DRUG	3:45	4:00	1/4
DRUG	4:00	4:15	1/4
DRUG	4:15	4:30	1/4
DRUG	4:30	4:45	1/4
DRUG	4:45	5:00	1/4
DRUG	5:00	5:15	1/4
DRUG	5:15	5:30	1/4
DRUG	5:30	5:45	1/4
DRUG	5:45	6:00	1/4
DRUG	6:00	6:15	1/4
DRUG	6:15	6:30	1/4
DRUG	6:30	6:45	1/4
DRUG	6:45	7:00	1/4
DRUG	7:00	7:15	1/4
DRUG	7:15	7:30	1/4
DRUG	7:30	7:45	1/4
DRUG	7:45	8:00	1/4
DRUG	8:00	8:15	1/4
DRUG	8:15	8:30	1/4
DRUG	8:30	8:45	1/4
DRUG	8:45	9:00	1/4
DRUG	9:00	9:15	1/4
DRUG	9:15	9:30	1/4
DRUG	9:30	9:45	1/4
DRUG	9:45	10:00	1/4
DRUG	10:00	10:15	1/4
DRUG	10:15	10:30	1/4
DRUG	10:30	10:45	1/4
DRUG	10:45	11:00	1/4
DRUG	11:00	11:15	1/4
DRUG	11:15	11:30	1/4
DRUG	11:30	11:45	1/4
DRUG	11:45	12:00	1/4
DRUG	12:00	12:15	1/4
DRUG	12:15	12:30	1/4
DRUG	12:30	12:45	1/4
DRUG	12:45	1:00	1/4
DRUG	1:00	1:15	1/4
DRUG	1:15	1:30	1/4
DRUG	1:30	1:45	1/4
DRUG	1:45	2:00	1/4
DRUG	2:00	2:15	1/4
DRUG	2:15	2:30	1/4
DRUG	2:30	2:45	1/4
DRUG	2:45	3:00	1/4
DRUG	3:00	3:15	1/4
DRUG	3:15	3:30	1/4
DRUG	3:30	3:45	

DATE MAY 21 19 72

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 21 19 72Rig No. 8 Page No. 27LOCATION CANDEL MOBILE ILLINOIS 11-1

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 27

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands							
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.	
6119		9		6128		1 1/2		106		5 1/2		6 1/2		2 1/2						5453.64		Singles					
15		8 3/4		X53R		OPEN		38291		35		45		6119		6128		9		1 1/2						626.0'	

DATE MAY 20 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 20 1972Rig No. 8 Page No. 26 LOCATION CANDEL MOBIL IRADIS 11-1

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5800	82	5882	7 3/4	105	No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	5232
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
14	8 3/4	X55R	OUT	37892	45	45	5620	5882	254	27 1/2		
MUD												
WEIGHT												
VISCOSITY												
GEL												
Additives												
At Surveys Degree												
MOTOR HOURS												
Oil Added												
COND.												
D. Collars												
Other Ft.												
C.B. Ft.												
Subs. Ft.												
Ft. Down on Kelly												
TOTAL												
Next Slip												
BOILER HRS.												
Light Plant												
Feet Left on Spool												
Casing Record												
Surface Prod.												
W.L.												
F.C.												
pH.												
Solids												
Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5882	145	6027	7 3/4	106	No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	5296
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
14	8 3/4	X55R	OUT	37892	45	45	5620	6027	399	37 1/2		
MUD												
WEIGHT												
VISCOSITY												
GEL												
Additives												
At Surveys Degree												
MOTOR HOURS												
Oil Added												
COND.												
D. Collars												
Other Ft.												
C.B. Ft.												
Subs. Ft.												
Ft. Down on Kelly												
TOTAL												
Next Slip												
BOILER HRS.												
Light Plant												
Feet Left on Spool												
Casing Record												
Surface Prod.												
W.L.												
F.C.												
pH.												
Solids												
Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
6027	92	6119	7 3/4	106	No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	5390
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
14	8 3/4	X55R	OPEN	37892	45	45	5620	6119	495	45		
MUD												
WEIGHT												
VISCOSITY												
GEL												
Additives												
At Surveys Degree												
MOTOR HOURS												
Oil Added												
COND.												
D. Collars												
Other Ft.												
C.B. Ft.												
Subs. Ft.												
Ft. Down on Kelly												
TOTAL												
Next Slip												
BOILER HRS.												
Light Plant												
Feet Left on Spool												
Casing Record												
Surface Prod.												
W.L.												
F.C.												
pH.												
Solids												
Cement												

REMARKS	Start	Time	Stop	Interval
RIG SERV	12:00	12:15		1/4
DRUG 8 3/4 HOLE	12:15	8:00		7 3/4
CANDEL MOBIL IRADIS				
67° 50' N 129° 30' W				
CHANGE HEAD - LINER OFF				
SLY WHEEL SIDE C250				
TRAVEL FROM ROCKY MOUNTAIN HOUSE				
HELD 5 MINUTE SAFETY MEETING				
- WORKING ON MUD PUMPS -				

With Pipe	Without Pipe	Standby
DRUG 8 3/4 HOLE	8:00	9:00
RIG SERV V3 1/2 RAMS	9:00	9:15
DRUG 8 3/4 HOLE	9:15	4:00
TRAVEL FROM EDMONTON		
WORK ON R.G.		

With Pipe	Without Pipe	Standby
DRUG	4:00	4:15
RIG SERV - KEN & COCK	4:15	4:30
DRUG	4:30	12:00
LOSS OF FLUID TO FORMATION & PULS HA.		
HELD 5 MIN SAFETY MEETING		
- PROPER USE OF KEN & COCK -		

Rig No.	8	Report No.	26
Tour - Midnight - 8 a.m.			
Specify actual hours worked.			
Driller	GARY HEWITT	12	
Derrick	DAVE BELL	12	
Motor	CARL COLLINS	12	
Floor	CHARLES HEWITT	12	
Floor	DAVE HRODICKA	12	
MAY 19/72			
GARY HEWITT 12			
Accidents Nil			
Outside Temp. 50			
Weather Conditions OVERCAST			
Road Conditions Nil			

Tour - 8 a.m. to 4 p.m.			
Specify actual hours worked.			
Driller			
Derrick			
Motor			
Floor			
Floor			
MAY 19/72			
E. DENEVE 12			
MAY 20/72			
E. DENEVE 12			
Accidents Nil			
Outside Temp. 10			
Weather Conditions Snow			
Road Conditions Nil			

Tour - 4 p.m. to Midnight			
Specify actual hours worked.			
Driller	BRIAN RIDDLE	12	
Derrick	HOWARD MACKAY	12	
Motor	GERRY BARRETT	12	
Floor	MAI CAUNSON	12	
Floor	GENE FLATO	12	
Accidents Nil			
Outside Temp. 10			
Weather Conditions Snow			
Road Conditions Nil			

Totco Ring on Bit No. _____ D.P. Caliper Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____
Approved by _____

DATE MAY 19 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 19 1972

Rig No. 8 Page No. 25

LOCATION CANDEL MORIL IROQUOIS 11-1

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands			
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.		
5628	40	5668	6 1/4	104M	3	6 1/4	2 1/8	48M				5011.91			
14	8 3/4	XSSR	OUT	37892	80	95	5628	5668	40	6 1/4		626.01			
MUD 12 a.m. 2 a.m. 4 a.m. 6 a.m. Additives												At Surveys Degree	MOTOR HOURS	Oil Added	
WEIGHT 17 4.7 4.7 4.7 SALT 110 SKS												1	8	✓	
VISCOSITY 32 32 31 CILLO-SIAL 2 SKS												2	8	✓	
GEL CAUSTIC 4 SKS												3			
No. 1	Pressure	650	650	650	650								Light Plant	8	✓
No. 2	S.P.M.	50	50	50	50								BOILER HRS.	8	
No. 1	Size	5 1/2	X 1 1/2			Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or Cut	Feet Left on Spool	Next Slip	
No. 2	Pressure	1 1/2	5 1/2	6	552	552			9150	700					
No. 1	Size	5 1/2	X 1 1/2			Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or Cut	Feet Left on Spool	Next Slip	
No. 2	Pressure	1 1/2	5 1/2	6	552	552			9150	700					
W.L. F.C. pH. 10.5 Solids												Cement			

REMARKS	Start	Stop	Interval
RUN IN SLOW	1700	130	1 1/2
RIGSERV MOTOR KILLS	130	145	1/4
DRUG	145	800	6 3/4
HOLD BLOWOUT DRILL			
HOLD 5 MIN SAFETY MEETING			
CANDEL MORIL et al			
IROQUOIS 1 - 11			
67° 50' N 129° 30' W			
With Pipe	Without Pipe	Standby	
DRUG	8 00	10 00	2 00
Rig Serv. & Hydril	10 00	11 00	1 00
DRUG	11 00	4 00	5 00
3 men worked 4 hrs on rig & then			
Traveled out			
CHLORIDE PPM x 1000 - 252			
With Pipe	Without Pipe	Standby	
DRUG	4 00	6 15	2 15
Rig Serv.	6 15	1 30	1 15
DRUG	6 30	12 00	5 30
HOLD 5 MIN SAFETY MEETING			
WORK WITH FORK LIFT			
PUMP & CLEAN SHAKER & DESILTER			
SUCKER TANKS			
With Pipe	Without Pipe	Standby	

Rig No. 8 Report No. 25

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller J. WEST	12
Derrick D. BELL	12
Motor C. COLLINS	12
Floor C. HENNIG	12
Floor D. HEDLICKA	12
Accidents Nil	
Outside Temp. + 5	
Weather Conditions CLEAR	
Road Conditions —	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick KELLY COCHRAN	12
Motor JOHN COCHRAN	12
Floor BEN STACHNIE	12
Floor DAVID HEDLICKA	6
STAMP OVER FOR CREW CHANGE	
Accidents Nil	
Outside Temp. + 30	
Weather Conditions CLEAR	
Road Conditions Nil	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller BRIAN RIDDLE	12
Derrick HOWARD MACKIN	12
Motor GERRY BRADSHAW	12
Floor MEL GUNSON	12
Floor GENE FLATO	12
Accidents Nil	
Outside Temp. + 35	
Weather Conditions CLEAR	
Road Conditions Nil	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller

B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by John Miller

DATE MAY 18 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 18 1972

Rig No. 8 Page No. 24

LOCATION CANDEL MOBIL IROQUOIS 11-1

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5574	47	5571	7 3/4	100M	No. 5	O.D. 6 1/4	I.D. 2 3/8	Wgt. 45				4917.03
Singles												
D. Collars												
Other Ft.												
C.B. Ft.												
Subs. Ft.												
Ft. Down On Kelly												
TOTAL												
5571												
700												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5571	38	5609	7 3/4	100M	No. 5	O.D. 6 1/4	I.D. 2 3/8	Wgt. 45				4917.03
Singles												
D. Collars												
Other Ft.												
C.B. Ft.												
Subs. Ft.												
Ft. Down On Kelly												
TOTAL												
5609												
700												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5609	19	5628	4 1/2	100M	No. 5	O.D. 6 1/4	I.D. 2 3/8	Wgt. 45				4917.03
Singles												
D. Collars												
Other Ft.												
C.B. Ft.												
Subs. Ft.												
Ft. Down On Kelly												
TOTAL												
5628												
700												

REMARKS	Start	Time	Interval
RIG SERV PIPE RAMP	12:00	12:15	1/4
DRIG	12:15	8:00	7 3/4
HIELD 5 MIN SAFETY MEETING			
CANDEL MOBIL etal IROQUOIS 11 67° 50' N 129° 30' W			

With Pipe	Without Pipe	Standby
RIG SERV HYDRIL (REMOTE)	8:00	8:15
DRIG	8:15	4 1/2

With Pipe	Without Pipe	Standby
DRIG	4:00	6:45
RIG SERV - KELLY LOCK	6:45	7:00
DRIG	7:00	8:45
DROP SURVEY @ 5628, 0%	8:45	9:00
TRIP OUT	9:00	
CLOSE BLIND RAMPS		2 1/2
TRIP IN	11:30	12:00

With Pipe	Without Pipe	Standby
-----------	--------------	---------

Rig No. 8 Report No. 24

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller J. WIESE	12
Derrick D. BIELL	12
Motor C. COLLINS	12
Floor C. HEARNIG	12
Floor D. HEDLICKA	12
Accidents Nil	
Outside Temp. +10°	
Weather Conditions CLEAR	
Road Conditions	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
B. STACHNIK	12
Accidents Nil	
Outside Temp. +30	
Weather Conditions SUNNY	
Road Conditions	

Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller B. RIDDLE	12
Derrick K. CALHANE	12
Motor H. MACKAY	12
Floor G. BARNES	12
Floor J. COULSON	12
Accidents Nil	
Outside Temp. +28	
Weather Conditions CLEAR	
Road Conditions	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by

DATE MAY 17 1972

NAPORS DRILLING LIMITED

WORK RECORD

DATE MAY 17 1972

Rig No. 8 Page No. 23 LOCATION CANDEL MOBIL IROQUOIS 11-1

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5398	70	5468	7 3/4	102M	No. 5	O.D. 6 1/4	I.D. 2 1/8	Wgt. 16	Gals.	Bbls.	Gal.	Singles
B I T S												
No. 12	Size 8 3/4	Type J-88	Size Jets OUT	Serial No. HH391	Wt. 45	R.P.M. 45	From 4946	To 5468	Ftg. 522	Hrs. 41 1/2	COND. RUN	D. Collars 126.01
MUD 12 a.m. 2 a.m. 4 a.m. 6 a.m. Additives At Surveys Degree MOTOR HOURS Oil Added												
WEIGHT 8.4 8.5 8.5 8.5 COT HULLS - 50 SKS												
VISCOSITY 33 32 32 32 KUDICK SEAL - 25 SKS												
GEL GEL - 35 SKS												
P U M S												
No. 1	Pres. 650	Model S.P.M. 50	Liner Size 5 1/2 X 15	Size 1 1/2	TRIPS 3 1/2	No. Lines 6	TON MILES 314	TOTAL MILES 314	Slip	Feet or Cut	Feet Left on Spool	Next Slip
Casing Record Surface Prod. 9 1/2 @ 704												
W.L. F.C. pH. 10.5 Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5468	16	5484	2 1/2	104M	No. 5	O.D. 6 1/4	I.D. 2 1/8	Wgt. 48	Gals.	Bbls.	Gal.	Singles
B I T S												
No. 12	Size 8 3/4	Type J-88	Size Jets OUT	Serial No. HH391	Wt. 45	R.P.M. 45	From 4946	To 5484	Ftg. 522	Hrs. 44	COND. RUN	D. Collars 126.01
MUD 8 a.m. 10 a.m. 12 p.m. 2 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added												
WEIGHT 8.5 8.5 8.5 8.5 COT HULLS 15 SKS												
VISCOSITY 32 32 32 32 C-110 SEAL 25 SKS												
GEL												
P U M S												
No. 1	Pres. 650	Model S.P.M. 50	Liner Size 5 1/2 X 15	Size 1 1/2	TRIPS 6	No. Lines 6	TON MILES	TOTAL MILES	Slip	Feet or Cut	Feet Left on Spool	Next Slip
Casing Record Surface Prod.												
W.L. F.C. pH. Solids Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
5484	40	5524	8 3/4	104M	No. 5	O.D. 6 1/4	I.D. 2 1/8	Wgt. 48	Gals.	Bbls.	Gal.	Singles
B I T S												
No. 13	Size 9 1/4	Type RRG-1	Size Jets OPEN	Serial No. DP950	Wt. 20	R.P.M. 45	From 5484	To 5524	Ftg. 410	Hrs. 6 3/4	COND. RUN	D. Collars 126.01
MUD 4 p.m. 6 p.m. 8 p.m. 10 p.m. Additives At Surveys Degree MOTOR HOURS Oil Added												
WEIGHT 8.5 8.5 8.5 8.5 GEL - 4 SKS												
VISCOSITY 32 32 34 34 SALT - 800 SKS												
GEL SANDUST - 50 SKS												
P U M S												
No. 1	Pres. 700	Model S.P.M. 50	Liner Size 5 1/2 X 15	Size 1 1/2	TRIPS 6	No. Lines 6	TON MILES 433	TOTAL MILES 433	Slip	Feet or Cut	Feet Left on Spool	Next Slip
Casing Record Surface Prod.												
W.L. F.C. pH. Solids Cement												

REMARKS	Start	Stop	Interval
RIG SERV ✓ 3 1/2" RAMS	12:00	12:15	1/4
DRUG FLUID LOSS 12 BBL'S PER HR	12:15	8:00	7 3/4
6:00 AM LOSS OF 10 BBL'S PER HR			
CANDEL MOBIL IROQUOIS 1 - 11 67° 50' N 129° 30' W			
✓ ESCAPE BUGGY ✓ DRUMS BRAKES			
✓ SCOTT AIR PACKS ✓ DRILLING LINE			
✓ FIRE EXTINGUISHERS			
ALL OK			

With Pipe	Without Pipe	Standby
RIG SERV ✓ MOTOR KILLS	8:00	8:15 1/4
DRUG	8:15	10:05 2 1/2
HOIST	10:45	12:45 2
LAY DOWN CONNOR + STAR	12:45	1:15 1/2
TRIP IN SLOW	1:15	3:45 2 3/4
BREAK CIRC + CEMENT TO BOTTOM	3:45	4:00 1/4
✓ BLIND RAMS		
LAY DOWN DRILCO STUB		
MAY 17-1972 - John Miller		

With Pipe	Without Pipe	Standby
DRUG	4:00	5:45 1 45
RIG SERV ✓ 14 APRIL	5:45	6:00 1/4
DRUG M.V. SALT SANDUST	6:00	
GEL + COTTON HULLS		10:00 4
LEAN OUT PUMPS	10:00	11:00 1
DRUG	11:00	12:00 1 1/4

Rig No. 8 Report No. 23

Tour — Midnight - 8 a.m.	
Specify actual hours worked. Hrs.	
Driller J. WEST	12
Derrick D. BELL	12
Motor C. COLLINS	12
Floor D. HIRDLICKA	12
Floor C. HIENNIG	12
Accidents NIL	
Outside Temp. +5°	
Weather Conditions CLEAR	
Road Conditions	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked. Hrs.	
Driller	
Derrick	
Motor	
Floor	
Floor	
Accidents NIL	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 4 p.m. to Midnight	
Specify actual hours worked. Hrs.	
Driller E. KIDDE	12
Derrick H. COCHRANE	12
Motor H. MACHON	12
Floor E. BARNHART	12
Floor J. COLLESON	12
Accidents NIL	
Outside Temp.	
Weather Conditions	
Road Conditions	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by

DATE MAY 16 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 16 1972

Rig No. 8 Page No. 22 LOCATION CANDEL MOBILE ILLINOIS 11-1

NOTE: Do Not Record Payroll Information Here

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
5117		97		5214		7 3/4		100M		No. 5		O.D. 6 1/4		I.D. 2 1/8		Wgt. 45				4538.33	
12		8 3/4		J-88		OUT		HH-341		45		45		4946		5214		268		20 3/4	
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT		8.4		8.4		8.4		8.4		FIRERSAL 4SKS								1		8	
VISCOSITY		28		28		28		28		QUICK SEAL 4SKS								2		8	
GEL										SAND DUST 6SKS								3		8	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.																	
P		No. 1		Pres-ure		650		650		650		650									
U		Model		S.P.M.		50		50		50		50									
M		No. 2		Pres-ure		5 1/2		X 15													
S		Model		S.P.M.				</													

DATE MAY 15 1972

Rig No. 8 Report No. 21

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	T. WEST	12
Derrick	D. BELL	12
Motor	C. COLLINS	12
Floor	C. HENNIG	12
Floor	D. HIRSHICKA	12
Accidents		
Outside Temp. - 10°		
Weather Conditions OVERCAST		
Road Conditions		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller		
Derrick		
Motor		
Floor		
Floor		
	B. STACHNIK	12
Accidents		
Outside Temp. + 30		
Weather Conditions WINDY		
Road Conditions		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	B. RIDGE	12
Derrick	K. COCHRANE	12
Motor	H. MACDONALD	12
Floor	G. BARNES	12
Floor	J. COLESON	12
Accidents		
Outside Temp. + 15°		
Weather Conditions CLEAR		
Road Conditions		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller Toolpusher John Miller
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE MAY 14 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 20

[illegible]

REMARKS	Time		
	Start	Stop	Interval
RIG SERV MOTOR KILLS	12 ⁰⁰	12 ¹⁵	1/4
DRLG (FLUID LOSS 10 BBL'S PER HR)	12 ¹⁵		
@ 400 AM (FLUID LOSS 10 BBL'S PER HR)			
@ 8:00AM (FLUID LOSS 10 BBL'S PER HR)		8 ⁰⁰	7 3/4
Held 5 min SAFETY MEETING			
With Pipe	Without Pipe	Standby	
DRLG	8 ⁰⁰	8 ³⁰	1/2
Rig Serv on B.O.P.	8 ³⁰	8 ⁴⁵	1/2
DRLG	8 ⁴⁵	11 ⁰⁰	7 1/2
Fluid Loss, 10 BBL'S PER HR.			
Ran 15 SPS OF SANDWICH TO HELP SEAL OFF FORM - 10-1.			
With Pipe	Without Pipe	Standby	
Rig Serv on 30 1/2 Rpm's	11 ⁰⁰	11 ¹⁵	1/4
DRLG	11 ¹⁵	6 ⁴⁵	2 1/2
SURVEY @ 4820, 1 1/2"	6 ⁴⁵	7 ¹⁵	1/2
DRLG	7 ¹⁵	12 ⁰⁰	4 3/4
Held 5 min SAFETY MEETING.			
With Pipe	Without Pipe	Standby	

Tour — Midnight - 8 a.m.		
Specify actual hours worked.	Hrs.	
Driller	J. WEST 12	
Derrick	D. BELL 12	
Motor	C. COLLINS 12	
Floor	D. HIRDLICKA 12	
Floor	C. HENNIG 12	
Accidents NIL		
Outside Temp. 0°		
Weather Conditions OVERCAST		
Road Conditions		
Tour — 8 a.m. to 4 p.m.		
Specify actual hours worked.	Hrs.	
Driller		
Derrick		
Motor		
Floor		
Floor		
	HOWARD MACKOW 16	
Accidents B. STACHNIK INJURE		
Outside Temp. 92°		
Weather Conditions CLOUDY		
Road Conditions NIL		
Tour — 4 p.m. to Midnight		
Specify actual hours worked.	Hrs.	
Driller	BRIAN RIDDLE 12	
Derrick	MELLY COCHRANE 12	
Motor	B. STACHNIK 12	
Floor	GERRY BARSNESS 12	
Floor	JUNO COULSON 12	
Accidents NIL		
Outside Temp. +15°		
Weather Conditions Light Snow/Wind		
Road Conditions NIL		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller Toolpusher John Miller
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE MAY 13 1972

Rig No. 8 Page No. 19 LOCATION CANDLER MOBIL 11-1

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 19

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
4312		108		4420		7 1/4		88M		No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	Bbls.	3750.87			
										5	6 1/4	2 1/4						Singles			
																		Bbls.			
B I T S	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars					
	10	8 3/4	R61xJ	3-11		NR121	45	45	3815	4420	605	35 1/2			RUN	626.01					
																Other Ft.					
																12.37					
																		C.B. Ft.			
MUD		12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives					At Surveys Degree			MOTOR HOURS		Oil Added		6.30			
WEIGHT		84	84	84	84						104330 1 3/4°			1	8	✓		Subs. Ft.			
VISCOSITY		28	28	28	28									2	8	✓		948			
GEL													3		x		Ft. Down On Kelly				
P U C M P S	No. 1	Pressure	1000	1000	1000	1000									Light	8	✓		TOTAL		
	Model	S.P.M.	56	56	56	56									BOILER HRS.		8			4420	
	230	Liner Size	5 1/2 x 15				Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	Next Slip					
	No. 2	Pressure					1 1/2	1 1/2	6	111	111	-	-		4150	700					
P S	Model	S.P.M.					Casing Record		Surface												
	214	Liner Size	5 1/2 x 19				Record		Prod.												
W.L.		F.C.		p.H.		Solids		Cement													

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
1420		554475		3 1/4		90M		No. 5 16		O.D. 6 1/4 6 1/8		I.D. 2 7/8		Wgt.		Gals.		Bbls.		Gal. 3781 41	
																				Singles	
																				Bbls.	
B I T S	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars					
	10	8 3/4	RG1XJ	3-11	NR121	45	45	3815	4445	630	2 1/2			2-8-1	626 01	Other Ft.					
	11	8 7/8	RRG1XJ	3-12	RT987	40-45	45	4445	4445	30	2			5 RLG.	12 37	C.B. Ft.					
MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives				At Surveys Degree		MOTOR HOURS		Oil Added		630	
WEIGHT						8.4										1		8		Subs. Ft.	
VISCOSITY						28										2		8		943	
GEL																3				Ft. Down on Kelly 410.38	
P U M P S	No. 1	Pressure	1000			1100								Light Plant		8 8		TOTAL			
	Model C	S.P.M.	56			54								BOILER HRS.				14175.9			
	250	Liner Size	5 1/2 x 1 1/2					Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet of	Cut	Feet Left on Spool	Next Slip				
	No. 2	Pressure						1 1/2	1 1/2	6	111	111	-	-		4150	700				
S	Model 214	S.P.M.						Casing Record	Surface												
	14	Liner Size	5 1/2 x 1 1/4					Prod.													
F.C.		pH.		Solids		Cement															

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER		CRUDE	Stand			
					No.	O.D.	I.D.	Wgt.		Gals.	Bbls.			Gal.	Bbls.	
4475	101	4576	7 3/4	91	5	6 1/2	2 1/4						3876.2			
					16	6 1/2	2 1/4						Singles 31.60			
B I T S	No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	
	11	8 1/2	RRG-1X	3-12	RT487	100	40	4445	4576	131	9 1/2			17.30	626.0	
							40								Other Ft. 17.30	
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree		MOTOR HOURS		Oil Added		
WEIGHT		8.4	8.4	8.4	8.4	SPARCUST 15 SCS						1		8		
VISCOSITY		28	28	28	28							2		8		
GEL												3				
P U M S	No. 1	Pressure	1100	-	1100	✓					Light Plant		8 8		TOTAL	
	Model	S.P.M.	32	-	32	✓					BOILER HRS.		8			
	No. 2	Liner Size	5 1/2	X	15		Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	Next Slip
P S	No. 2	Pressure				18	25	6	9	206	-	-	-	-	4150	400
	Model	S.P.M.				Water Truck Hours:				206						
	No. 2	Liner Size	5 1/2	X	14	Desilter Hours:										
W.L.		F.C.	pH.	Solids.		Desander Hours:										

REMARKS	Time		
	Start	Stop	Interval
RIG SERU - HYDRIL	1200	12 ^{'s}	1 ^{/₄}
DRLG	12 ^{'s}	300	2 ^{'s}
SURVEY @ 4330	300	330	1 ^{/₂}
DRLG	330	800	4 ^{'s}
			8 hr
FIELD 5 MIN SAFETY MEETING			
With Pipe	Without Pipe	Standby	

	With Pipe	Without Pipe	Standby
RIG SERU + KILLY COCK	800	8 ¹⁵	1/4
DRLG	815	930	1/4
HOIST CLOSE BLIND RAMS	930	11 ¹⁵	1 3/4
RUN IN	11 ¹⁵	1 ¹⁵	2
BREAK CIRCLE CHASE 30' TO BOTTOM	1 ¹⁵		
15' FILL		2 ⁰⁰	1 1/2
DRLG 8 3/4" HOLE	2 ⁰⁰	4 ⁰⁰	2
			8
HELD 5 MIN SAFETY MEETING			

	With Pipe	Without Pipe	Standby
Fund Ser.: x # $\frac{1}{2}$ " PIPE RINGS	4 ⁰⁰	4 ¹⁵	7 ¹⁵
DRLG.	4 ¹⁵	17 ⁰⁰	7 ³⁰
FUND LOSS OF 30 BARS HR,			8
RAN SAWDUST FUND LOSS OF			
10 BARS HR. NOW.			
Held 5 min SAFETY MEET. - W			

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller J. WEST	12
Derrick D. BELL	12
Motor C. COLLINS	12
Floor D. HRDLICKA	12
Floor C. HEINIG	12
Accidents NIL	
Outside Temp. +5°	
Weather Conditions SNOW	
Road Conditions —	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
<i>H. MACKOW</i>	<i>12</i>
Accidents <i>NIL</i>	
Outside Temp. — <i>10°</i>	
Weather Conditions <i>OVERCAST</i>	
Road Conditions —	

Tour — 4 p.m. to Midnight		Hrs.
Specify actual hours worked.		
Driller	B. RIGGLE	12
Derrick	K. COCHRANE	12
Motor	B. STACHNIK	12
Floor	J. COULSON	12
Floor	G. BARNES	12
Accidents		NIL
Outside Temp.		+15°
Weather Conditions		LIGHT SNOW
Road Conditions		NIL

Totco Ring on Bir No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John G. J. J.

B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____

Toolpusher John Miller
Approved by _____

DATE MAY 12 1972

Rig No. 8 Report No. 18

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	J. WEST	12
Derrick	D. BELL	12
Motor	C. COLLINS	12
Floor	C. HENNIG	12
Floor	D. HRDLICKA	12
Accidents <i>NIL</i>		
Outside Temp. <i>0°</i>		
Weather Conditions <i>CLEAR</i>		
Road Conditions <i>—</i>		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller	J. WEST	6
Derrick	<i>Larry Pederson</i>	12
Motor	<i>K. SUMMER</i>	8
Floor	C. HENNIG	6
Floor	<i>Gordon Kesler</i>	12
<i>STAYED OVER</i>		
<i>F/CREW CHANGE</i>		
Accidents <i>NIL</i>		
Outside Temp. <i>+25°</i>		
Weather Conditions <i>CLEAR</i>		
Road Conditions <i>—</i>		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	<i>Brian Riddie</i>	12
Derrick	<i>K. COCHRANE</i>	12
Motor	<i>B. STACHNIT</i>	12
Floor	<i>J. COULSON</i>	12
Floor	<i>G. BARNESS</i>	12
	<i>H. MACKOW</i>	12
	<i>B. SIMPSON</i>	8
	<i>F. DENEVE</i>	12
Accidents <i>NIL</i>		
Outside Temp. <i>+25°</i>		
Weather Conditions <i>CLEAR</i>		
Road Conditions <i>NIL</i>		

Totco Ring on Bit No. _____ D.P. Caliper'd Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller Toolpusher John Miller
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE MAY 11 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 11 1972

Rig No. 8 Page No. 17

LOCATION CANOE MOBILE IRVING 11-1

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
3602	161	3863	7 3/4	78M	No. 5	O.D. 6 1/4	I.D. 2 3/8	Wgt. 16	Gals.	Bbls.	Gal.	3099.27
B I T S												Singles
No. 9	Size 8 3/4	Type RRG28X	Size Jets 3-11	Serial No. WF001	Wt. 45	R.P.M. 45	From 3903	To 3763	Ftg. 360	Hrs. 21	COND. RUN	D. Collars 626.01
MUD												Other Ft. 12.37
WEIGHT 8.4												C.B. Ft. 6.30
VISCOSITY 28												Subs. Ft. 9.48
GEL												Ft. Down on Kelly 20
P No. 1 Pres- 1000												TOTAL 3763
Model S.P.M. 50												Stands 3120.39
Liner Size 5 1/2 X 15												Singles 31.19
No. 2 Pres- 1000												D. Collars 626.01
Model S.P.M. 58												Other Ft. 12.37
Liner Size 5 1/2 X 15												C.B. Ft. 6.30
W.L. F.C. pH. Solids Cement												Subs. Ft. 9.48
												Ft. Down on Kelly 11
												TOTAL 3815

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
3763	52	3815	3 1/4	80M	No. 5	O.D. 6 1/4	I.D. 2 3/8	Wgt. 16	Gals.	Bbls.	Gal.	3120.39
B I T S												Singles 31.19
No. 9	Size 8 3/4	Type RRG28X	Size Jets 3-11	Serial No. WF001	Wt. 45	R.P.M. 45	From 3903	To 3815	Ftg. 412	Hrs. 24 3/4	COND. 1 1/1	D. Collars 626.01
MUD												Other Ft. 12.37
WEIGHT 8.4												C.B. Ft. 6.30
VISCOSITY 28												Subs. Ft. 9.48
GEL												Ft. Down on Kelly 11
P No. 1 Pres- 1000												TOTAL 3815
Model S.P.M. 50												Stands 3120.39
Liner Size 5 1/2 X 15												Singles 31.19
No. 2 Pres- 1000												D. Collars 626.01
Model S.P.M. 58												Other Ft. 12.37
Liner Size 5 1/2 X 15												C.B. Ft. 6.30
W.L. F.C. pH. Solids Cement												Subs. Ft. 9.48
												Ft. Down on Kelly 11
												TOTAL 3815

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
3815	129	3944	6 3/4	80M	No. 5	O.D. 6 1/4	I.D. 2 3/8	Wgt. 16	Gals.	Bbls.	Gal.	3215.14
B I T S												Singles 629.6
No. 10	Size 8 3/4	Type RRG1	Size Jets 3-11	Serial No. NB121	Wt. 45	R.P.M. 45	From 3815	To 3944	Ftg. 129	Hrs. 5 1/4	COND. DRILL	D. Collars 626.01
MUD												Other Ft. 12.37
WEIGHT 8.4												C.B. Ft. 6.30
VISCOSITY 28												Subs. Ft. 9.48
GEL												Ft. Down on Kelly 12
P No. 1 Pres- 1000												TOTAL 3944
Model S.P.M. 56												Stands 3215.14
Liner Size 5 1/2 X 15												Singles 629.6
No. 2 Pres- 1000												D. Collars 626.01
Model S.P.M. 58												Other Ft. 12.37
Liner Size 5 1/2 X 15												C.B. Ft. 6.30
W.L. F.C. pH. Solids Cement												Subs. Ft. 9.48
												Ft. Down on Kelly 12
												TOTAL 3944

REMARKS	Start	Stop	Interval
RIG SERV ✓ HYDRIL	1200	1215	1/4
DRLG	1215	800	7 3/4
HELD 5 MIN SAFETY MEETING			
✓ DRILLING LINE			
✓ DRUMS BRAKES			
✓ ESCAPE BUGGY			
✓ ALL BREATHING APPARATUS			
ALL OK			

With Pipe	Without Pipe	Standby	
RIG SERV + ✓ MOTOR KILLS	800	815	1/4
DRLG	815	1130	3 1/4
TRIP OUT FOR PLUGGED	1130		
JETS + CLOSE BLIND RAMS		1:30	2
DUMP & CLEAN TANKS	1:30	3:15	1 3/4
TRIP IN WITH BIT # 10	3:15	400	3/4

With Pipe	Without Pipe	Standby	
TRIP IN WITH BIT # 10	400	4:45	3/4
CLEAN TO BOTTOM	4:45	5:00	1/4
DRILL 8 3/4" HOLE	5:00	6:30	1 1/2
CON A BIG SERVICE	6:30	6:45	1/4
DRILL 8 3/4" HOLE	6:45	1200	5 1/4

With Pipe	Without Pipe	Standby
HELD 5 MIN SAFETY MEET		
✓ CROWN SAVER ON TRIP OK		

Rig No. 8	Report No. 17
Tour — Midnight - 8 a.m.	
Specify actual hours worked. Hrs.	
Driller J. WEST	12
Derrick D. BILL	12
Motor C. COLLINS	12
Floor C. HENNIG	12
Floor D. HRDLICKA	12

Accidents NIL
Outside Temp. 0°
Weather Conditions CLEAR
Road Conditions

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked. Hrs.	
Driller	
Derrick	
Motor	
Floor	
Floor	
LEASE K. SOMMER	12
INHEAD B. SIMPSON	12
MECH F. DENEVE	12
Accidents	
Outside Temp. +20°	
Weather Conditions CLEAR	
Road Conditions	

Tour — 4 p.m. to Midnight	
Specify actual hours worked. Hrs.	
Driller L. PEDERSEN	12
Derrick K. COCHRANE	12
Motor B. STACHNIK	12
Floor G. KESLER	12
Floor J. COULSON	12
Accidents NIL	
Outside Temp. +30°	
Weather Conditions CLEAR	
Road Conditions	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by John Miller

DATE MAY 10 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 10 1972

Rig No. 8 Page No. 16

LOCATION CANOE L MOBIL IRQUOIS 11-1

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 16

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands		
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	
3403	0			76M	16	6 1/4	27 1/8							
B	9	8 3/4	RRG2BX	3-11	WF001	45	40	3403						
I														
T														
S														
MUD				12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives	At Surveys Degree				MOTOR HOURS	Oil Added
WEIGHT													1	8
VISCOSITY													2	8
GEL													3	8
P	No. 1	Pressure												
U	Model	S.P.M.												
M	250	Liner Size	5 1/2 x 15		Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	
P	No. 2	Pressure												
S	Model	S.P.M.												
	250	Liner Size	5 1/2 x 14											
W.L.				F.C.	pH.	Solids	Cement							

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands		
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	
3403	89	3492	5 1/2	76M	16	6 1/4	27 1/8	48						
B	9	8 3/4	RRG2BX	3-11	WF001	45	40	3403	3492	89	5 1/2			
I														
T														
S														
MUD				8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives	At Surveys Degree				MOTOR HOURS	Oil Added
WEIGHT													1	8
VISCOSITY													2	8
GEL													3	8
P	No. 1	Pressure												
U	Model	S.P.M.												
M	250	Liner Size	5 1/2 x 15		Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	
P	No. 2	Pressure												
S	Model	S.P.M.												
	250	Liner Size	5 1/2 x 14											
W.L.				F.C.	pH.	Solids	Cement							

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands		
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	
3492	110	3602	7 3/4	76M	16	6 1/4	27 1/8	48						
B	9	8 3/4	RRG2BX	3-11	WF001	45	40	3403	3602	199	13 1/4			
I														
T														
S														
MUD				4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives	At Surveys Degree				MOTOR HOURS	Oil Added
WEIGHT													1	8
VISCOSITY													2	8
GEL													3	8
P	No. 1	Pressure												
U	Model	S.P.M.												
M	250	Liner Size	5 1/2 x 15		Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	
P	No. 2	Pressure												
S	Model	S.P.M.												
	250	Liner Size	5 1/2 x 14											
W.L.				F.C.	pH.	Solids	Cement							

REMARKS	Start	Stop	Interval
SLIP LINE FOR NEW SPOOL	1200	300	3
RIG SERV - P.P. RAMS	300	315	1/4
INSTALL NEW BRAKE PADS	315		
+ NEW LINKAGE ARMS + P.W.S		700	3 3/4
RUN IN BLOCKS WINDING UP	700		
TRY TO GET CIRC NO RETURNS	830	930	1
MIX LOSS CIRC MAT	930	1030	1
DRUG			

With Pipe	Without Pipe	Standby
NO RETURNS ON BTM		800
CIRC + MIX LOSS CIRC MAT		1030 2 1/2
DRUG		1030 400 5 1/2

With Pipe	Without Pipe	Standby
RIG SERVICE & KELLY COCK		400 415 1/4
DRILL 8 3/4" HOLE		415 1200 7 3/4

With Pipe	Without Pipe	Standby
HELD 5 MIN SAFETY MEET		
CHECKED ALL FIRE EXTINGUISHERS		

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller J. WEST	12
Derrick D. BELL	12
Motor C. COLLINS	12
Floor D. HRDLICKA	12
Floor C. HEINIG	12

Accidents N/A

Outside Temp. -10°

Weather Conditions OVERCAST

Road Conditions

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
LEASE K. SOMMER	12
WELD B. SIMPSON	12
MECH F. DENEVE	12

Accidents

Outside Temp.

Weather Conditions

Road Conditions

Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller L. PEDERSEN	12
Derrick K. COCHRANE	12
Motor B. STACHNIK	12
Floor C. KESLER	12
Floor J. COULSON	12

Accidents N/A

Outside Temp. 0°

Weather Conditions CLOUDY + LIGHT SNOW

Road Conditions

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller

B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____

Toolpusher John Miller

Approved by _____

DATE MAY 9TH 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 9 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Page No. 15 LOCATION CANDEL MOBILE, LOUISIANA 11-1

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS			FUEL	WATER	CRUDE	Stands																	
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars														
3089	116	3205	7 1/4	74M	16	6 1/4	2 1/8				2520.89																	
8	8 3/4	RRG28X	3-11	2L-998	45	40	2671	3205	534	39			RUN	626.01														
MUD												12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added	6.30								
WEIGHT												8.48	8.4	8.4	8.4					3100	1 1/2	1	8		4.48			
VISCOSITY												28	28	28	28							2	8					
GEL																						3						
P												No. 1	Pressure	1000														
U												Model	S.P.M.	58														
M												250	Liner Size	5 1/2 X 15														
S												No. 2	Pressure															
P												Model	S.P.M.															
S												2 1/2	Liner Size	5 1/2 X 14														
W.L.												F.C.	pH.	Solids	Cement													

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS			FUEL	WATER	CRUDE	Stands																
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars													
3205	111	3316	6 3/4	75M	16	6 1/4	2 1/8				2650.76																
8	8 3/4	RRG28X	3-11	2L-998	45	40	2671	3316	645	5 3/4			DRILL	626.01													
MUD												8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added	6.30							
WEIGHT												8.4	8.4	8.4	8.4							1	8		4.48		
VISCOSITY												28	28	28	28							2	8				
GEL																						3					
P												No. 1	Pressure	1000													
U												Model	S.P.M.	58													
M												250	Liner Size	5 1/2 X 15													
S												No. 2	Pressure														
P												Model	S.P.M.														
S												2 1/2	Liner Size	5 1/2 X 14													
W.L.												F.C.	pH.	Solids	Cement												

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS			FUEL	WATER	CRUDE	Stands																
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars													
3316	87	3403	5	76M	16	6 1/4	2 1/8				2650.76																
8	8 3/4	RRG28X	3-11	2L-998	45	40	2671	3403	732	5 3/4			761	626.01													
MUD												4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added	6.30							
WEIGHT												8.4	8.4	8.4	8.4							1	8		4.48		
VISCOSITY												28	28	28	28							2	8				
GEL																						3					
P												No. 1	Pressure	1000													
U												Model	S.P.M.	56													
M												250	Liner Size	5 1/2 X 15													
S												No. 2	Pressure														
P												Model	S.P.M.														
S												2 1/2	Liner Size	5 1/2 X 14													
W.L.												F.C.	pH.	Solids	Cement												

REMARKS

Time

Start Stop Interval

RIG SERV MOTOR KILLS 1200 1215 1/4
DRLG 1215 145 1 1/2
SURVEY @ 3100 1 1/2° 145 215 1/2
DRLG 215 800 5 3/4
HELD 5 MIN SAFETY MEET

With Pipe Without Pipe Standby

RIG SERV + KELLY COCK 800 815 1/4
DRLG 815 1030 2 1/4
CLEAN UP SLOUGHING HOLE 1030
@ 3230 1100 1/2
DRLG 1100 100 2
SURVEY AT 3220 1° 100 130 1/2
DRILL 8 3/4" HOLE 130 400 2 1/2
LEAK WILD MECH

With Pipe Without Pipe Standby

RIG SERVICE + PIPE RAMS 100 415 3/4
DRILL 8 3/4" HOLE 415 915 5
DROP SURVEY AT 3400 915 945 1/2
TRIP OUT OF HOLE 945 1100 1 1/4
CLOSED BLIND RAMS.
RAN COLLARS + 1 SID OF P.A. IN HOLE 1100 1115 3/4
PREPARE TO SKIP DRILL LAMP 1100 1130 1/4
CANDEL MOBILE
HELD 5 MIN SAFETY MEET
CHECKED BRAKE BLOCKS NEED REPAIRED ON DRILLING SIDE

With Pipe Without Pipe Standby

Rig No. 8 Report No. 15

Tour — Midnight - 8 a.m.

Specify actual hours worked. Hrs.

Driller J. WIEST 12
Derrick D. BELL 12
Motor C. COLLINGS 12
Floor C. HENNIG 12
Floor D. HRDLICKA 12

Accidents NIL

Outside Temp. +10°

Weather Conditions OVERCAST

Road Conditions —

Tour — 8 a.m. to 4 p.m.

Specify actual hours worked. Hrs.

Driller
Derrick
Motor
Floor
Floor
K. SOMMER 12
B. SIMPSON 12
F. DENFUE 12

Accidents

Outside Temp.

Weather Conditions

Road Conditions

Tour — 4 p.m. to Midnight

Specify actual hours worked. Hrs.

Driller L. PEDERSEN 12
Derrick K. COCHRANE 16
Motor B. STACHNIK 12
Floor G. KESLER 12
Floor J. COULSON 12
(NOTE) K. COCHRANE
HELP DIG OUT ICE BRIDGES
ON MAY 8/72

Accidents NIL

Outside Temp. +10°

Weather Conditions OVERCAST

Road Conditions —

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller

B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by

Toolpusher John Miller
Approved by

DATE MAY 8 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 8 1972

Rig No. 8 Page No. 14

LOCATION CANDEL MOBILE 169015 11-1

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 14

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2772		100		2872		7 3/4		70M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		2204.89	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 2872		Ftg. 192	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. RUN		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 13		TOTAL 2872	
S		MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4		RAPID DRILL 4 SKS				1		8		✓	
		VISCOSITY		28		28		28		28						2		8		✓	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 8					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2872		96		2968		7 1/4		70M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		226.756	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 2968		Ftg. 297	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. DRILL		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 15		TOTAL 2968	
S		MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4						1		8		✓	
		VISCOSITY		28		28		28		28						2		8		✓	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 8					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2968		121		3089		7 3/4		74M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		236.272	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 3089		Ftg. 418	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. DRILL		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 10		TOTAL 3089	
S		MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4						1		8		3.25	
		VISCOSITY		28		28		28		28						2		8		2.45	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 3					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2968		121		3089		7 3/4		74M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		236.272	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 3089		Ftg. 418	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. DRILL		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 10		TOTAL 3089	
S		MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4						1		8		3.25	
		VISCOSITY		28		28		28		28						2		8		2.45	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 3					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2968		121		3089		7 3/4		74M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		236.272	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 3089		Ftg. 418	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. DRILL		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 10		TOTAL 3089	
S		MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4						1		8		3.25	
		VISCOSITY		28		28		28		28						2		8		2.45	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 3					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2968		121		3089		7 3/4		74M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		236.272	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 3089		Ftg. 418	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. DRILL		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 10		TOTAL 3089	
S		MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4						1		8		3.25	
		VISCOSITY		28		28		28		28						2		8		2.45	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 3					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2968		121		3089		7 3/4		74M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		236.272	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 3089		Ftg. 418	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2		Hrs. 16 1/2		COND. DRILL		D. Collars 6 7/8		Other Ft. 12.37		C.B. Ft. 6.30		Subs. Ft. 9.48		Ft. Down on Kelly 10		TOTAL 3089	
S		MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added			
		WEIGHT		8.4		8.4		8.4		8.4						1		8		3.25	
		VISCOSITY		28		28		28		28						2		8		2.45	
		GEL														3				✓	
P		No. 1		Pres. 1000		1000		1000		1000						Light Plant 8		✓			
U		Model C		S.P.M. 55		55		55		55						BOILER HRS. 3					
M		No. 2		Liner Size 5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		5 1/2 x 1 1/4		Size		TRIPS		No. Lines		TON MILES		TOTAL MILES	
S		Model 71A		S.P.M. 71A		71A		71A		71A		Casing Record		Surface Prod.							
		W.L.		F.C.		pH.		Solids		Cement											

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
2968		121		3089		7 3/4		74M		No. 5 16		O.D. 6 1/8 I.D. 2 7/8		Wgt. 48		Gals. Bbls.		Gal. Bbls.		236.272	
B		No. 8		Size 8 3/4		Type RRG 2BX		Size Jets 3-11		Serial No. 21-998		Wt. 40		R.P.M. 48		From 2671		To 3089		Ftg. 418	
I		Hrs. 16 1/2		Ft. Reamed 16 1/2																	

DATE MAY 7 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 7 1972

Rig No. 8 Page No. 13

LOCATION CANDLER MOBIL ILLINOIS 11-1

NOTE: Do Not Record Payroll Information Here

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.	
2542		88		2630		7 1/4		68M		No. 5		O.D. 6 1/2		I.D. 2 1/8		Wgt. 16						1951.21	
B		No. 7		Size 8 3/4		Type RRG2BX		Size Jets 3-11		Serial No. WI-216		Wt. 40		R.P.M. 48		From 2261		To 2630		Ftg. 369		Hrs. 2 1/4	
T																						COND. RUN	
S																						D. Collars 126.01	
																						Other Ft. 12.37	
																						C.B. Ft. 1.30	
																						Subs. Ft. 9.48	
																						Ft. Down on Kelly 25	
																						TOTAL 2630	
																						Next Slip	
								</															

DATE MAY 6 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 6 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Page No. 12 LOCATION CANDLE MOBILE ALABAMA 11-1

Rig No. 8 Report No. 12

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	Singles
2261	112	2373	7 1/2	67M	5	6 1/4	2 3/8					1678.63
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
7	8 3/4	RRG2BX	3-11	WF216	40	45	2261	2373	112	7 1/2		RUN
MUD												
				Additives				At Surveys Degree		MOTOR HOURS		Oil Added
				4" RAPIDRIL				2300 2°		1 8		✓
										2 8		✓
										3 8		✓
										Light Plant		8
										BOILER HRS.		8
										Feet Left on Spool		Next Slip
W.L. F.C. pH. Solids Cement												
From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	Singles
2373	83	2456	7 1/4	68M	5	6 1/4	2 3/8					179.41
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
7	8 3/4	RRG2BX	3-11	WF216	40	48	2261	2456	195	14 3/4		DRILL
MUD												
				Additives				At Surveys Degree		MOTOR HOURS		Oil Added
								2450 2°		1 8		✓
										2 8		✓
										3 8		✓
										Light Plant		8
										BOILER HRS.		8
										Feet Left on Spool		Next Slip
W.L. F.C. pH. Solids Cement												
From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	Singles
2456	86	2542	7 3/4	68	5	6 1/4	2 3/8	48				179.34
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
7	8 3/4	RRG2BX	3-11	WF216	40	48	2261	2542	281	22 3/4		DRILL
MUD												
				Additives				At Surveys Degree		MOTOR HOURS		Oil Added
				4" RAPIDRIL						1 8		✓
										2 8		✓
										3 8		✓
										Light Plant		8
										BOILER HRS.		8
										Feet Left on Spool		Next Slip
W.L. F.C. pH. Solids Cement												
From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands
					No.	O.D.	I.D.	Wgt.	Gals.	Bbls.	Gal.	Singles
2542	86	2628	7 3/4	68	5	6 1/4	2 3/8	48				179.34
B I T S												
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.
7	8 3/4	RRG2BX	3-11	WF216	40	48	2261	2628	281	22 3/4		DRILL
MUD												
				Additives				At Surveys Degree		MOTOR HOURS		Oil Added
				4" RAPIDRIL						1 8		✓
										2 8		✓
										3 8		✓
										Light Plant		8
										BOILER HRS.		8
										Feet Left on Spool		Next Slip
W.L. F.C. pH. Solids Cement												

REMARKS	Time		
	Start	Stop	Interval
RIG SERVICE ✓ KELLY CORK	1200	1215	1/4
DRLG	1215	1240	3 3/4
SURVEY @ 2300 2°	1240	1245	1/4
DRLG	1245		
Held 5 min safety meeting			
With Pipe Without Pipe Standby			
RIG SERVICE ✓ PIPE RAMS	800	815	1/4
DRLG	815	835	7
SURVEY AT 2450 2°	835	845	1/2
DRILL 8 3/4" HOLE	845	900	1/4
Held 5 min safety meeting			
With Pipe Without Pipe Standby			
RIG SERVICE ✓ HYDRIL	400	415	1/4
DRILL 8 3/4" HOLE	415	1200	7 1/4
Held 5 min safety meeting			
With Pipe Without Pipe Standby			

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller J. WEST	12
Derrick DALE BELL	12
Motor C. COLLINS	12
Floor D. HEDLICKA	12
Floor CHAS HENNIG	12
Accidents NIL	
Outside Temp. +10°	
Weather Conditions CLEAR	
Road Conditions	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
L.H.S. K. SOMMER	12
WELD B. SIMPSON	12
MICH F. DENEVE	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller L. PEDERSEN	12
Derrick K. COCHRAN	12
Motor R. STACHNIK	12
Floor G. KESLER	12
Floor J. COULSON	12
Accidents NIL	
Outside Temp. 30°	
Weather Conditions CLEAR	
Road Conditions	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by John Miller

DATE MAY 5 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE MAY 5 1972

Rig No. 8 Page No. 11 LOCATION CANDEL MORIA IRAQI 11-1

NOTE: Do Not Record Payroll Information Here

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Bbls.	
2141		81		2222		7 3/4		66M		16		6 1/8		2 1/8						1539.76	
B		6		8 3/4		RRG2B		3-11		WF 216		40		48		2141		2222		81	
T																					
S																					
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		8.4		→														6.30		11.83	
VISCOSITY		28		→														12.37		26	
GEL																					
P		No. 1		Pressure		1000		→													
U		Model		S.P.M.		58		→													
M		No. 2		Pressure		5 1/2 X 15															
S		Model		S.P.M.																	
W.L.		F.C.		pH.		Solids		Cement													

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Bbls.	
222		39		2261		3 1/4		67M		16		6 1/8		2 1/8						1571.57	
B		6		8 3/4		RRG2B		3-11		WF 216		40		48		2141		2261		120	
T																					
S																					
MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		8.4		8.4														6.30		11.83	
VISCOSITY		28		28														12.37		34	
GEL																					
P		No. 1		Pressure		1000		1000													
U		Model		S.P.M.		58		58													
M		No. 2		Pressure		5 1/2 X 15															
S		Model		S.P.M.																	
W.L.		F.C.		pH.		Solids		Cement													

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Bbls.	
222		39		2261		3 1/4		67M		16		6 1/8		2 1/8						1571.57	
B		6		8 3/4		RRG2B		3-11		WF 216		40		48		2141		2261		120	
T																					
S																					
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		8.4		8.4														6.30		11.83	
VISCOSITY		28		28														12.37		34	
GEL																					
P		No. 1		Pressure		1000		1000													
U		Model		S.P.M.		58		58													
M		No. 2		Pressure		5 1/2 X 15															
S		Model		S.P.M.																	
W.L.		F.C.		pH.		Solids		Cement													

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Bbls.	
222		39		2261		3 1/4		67M		16		6 1/8		2 1/8						1571.57	
B		6		8 3/4		RRG2B		3-11		WF 216		40		48		2141		2261		120	
T																					
S																					
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added		C.B. Ft.		Subs. Ft.	
WEIGHT		8.4		8.4														6.30		11.83	
VISCOSITY		28		28														12.37		34	
GEL																					
P		No. 1		Pressure		1000		1000													
U		Model		S.P.M.		58		58													
M		No. 2		Pressure		5 1/2 X 15															
S		Model		S.P.M.																	
W.L.		F.C.		pH.		Solids		Cement													

REMARKS		Time	
		Start	Stop
DRLG		1200	330
RIG SERV CROWN SAVER MOTOR		330	345
KILLS + BOP'S OK / KELLY COCK			
DRLG		345	800
CHANGED FUEL FILTERS IN #2 RIG ENGINE			
HELD 5 MIN SAFETY MEETING			
With Pipe		Without Pipe	
DRUNKS BRAKES + DRIVING			
LINE + ESCAPE RUGGY + LINE			
ALL SATISFACTORY			
ALL BREATHING APPARATUS			
DRLG		800	830
RIG SERV + PIPE RAM'S		830	845
DRLG		845	1030
CIRC + COND HOLE TO TEST		1030	1130
HOIST (SLM)		1130	100
MAKE UP TESTING TOOLS		100	215
TRIP IN WITH TEST #2		215	400
With Pipe		Without Pipe	
TESTING		400	645
TRIP OUT TEST		645	830
BREAK DOWN TESTING TOOLS		830	
LAY DOWN TAIL PIPE			945
TRIP IN WITH BIT #2		945	1130
BREAK CIRCULATION + CONNECTION		1130	1200
DST #2 2121-2261			
Preflow 5 min / 30 V.O 60 mFSI 60 min			
Recovered 1300 fluid			
BHT 84°F			
With Pipe		Without Pipe	

Rig No. 8 Report No. 11

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller J. WEST	12
Derrick J. TOKAR	12
Motor G. FLATO	12
Floor D. HROLIKA	12
Floor K. LEQUIERRE	12
Accidents NIL	
Outside Temp. +5°	
Weather Conditions CLEAR	
Road Conditions	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
K. SOMMER	12
B. SIMPSON	12
E. DIENEVE	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller L. PEDERSEN	12
Derrick K. COCHRANE	16
Motor B. STACHNIK	16
Floor G. KESLER	12
Floor J. COULSON	12
Accidents NIL	
Outside Temp. 25°	
Weather Conditions CLEAR	
Road Conditions	

Totco Ring on Bit No. D.P. Caliper Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller

B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by

DATE MAY 4 1972

NABORS DRILLING LIMITED

WORK RECORD

Rig No. 8 Page No. 10

LOCATION CANDEL MOBILE LAUDS 11-1

NOTE: Do Not Record Payroll Information Here

DATE MAY 4 1972

Rig No. 8 Report No. 10

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands																																																						
1737	193	1930	7 1/2	58m	No. 5	O.D. 6 1/4	I.D. 2 1/8	Wgt. 16 1/2	Gals.	Bbls.	Gal.	1256.23																																																						
<table border="1"> <tr> <th>No.</th> <th>Size</th> <th>Type</th> <th>Size Jets</th> <th>Serial No.</th> <th>Wt.</th> <th>R.P.M.</th> <th>From</th> <th>To</th> <th>Ftg.</th> <th>Hrs.</th> <th>Ft. Reamed</th> <th>Hrs.</th> <th>COND.</th> </tr> <tr> <td>5</td> <td>8 1/4</td> <td>XSSR</td> <td>3-11</td> <td>38833</td> <td>40</td> <td>48</td> <td>1010</td> <td>1930</td> <td>920</td> <td>39</td> <td></td> <td></td> <td>RVN</td> </tr> </table>													No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	5	8 1/4	XSSR	3-11	38833	40	48	1010	1930	920	39			RVN																										
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.																																																					
5	8 1/4	XSSR	3-11	38833	40	48	1010	1930	920	39			RVN																																																					
<table border="1"> <tr> <th>MUD</th> <th>12 a.m.</th> <th>2 a.m.</th> <th>4 a.m.</th> <th>6 a.m.</th> <th>Additives</th> <th>At Surveys Degree</th> <th>MOTOR HOURS</th> <th>Oil Added</th> </tr> <tr> <td>WEIGHT</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> <td></td> <td>1800</td> <td>1 1/4</td> <td>1</td> </tr> <tr> <td>VISCOSITY</td> <td>28</td> <td>28</td> <td>28</td> <td>28</td> <td></td> <td></td> <td></td> <td>2</td> </tr> <tr> <td>GEL</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>3</td> </tr> </table>													MUD	12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added	WEIGHT	8.4	8.4	8.4	8.4		1800	1 1/4	1	VISCOSITY	28	28	28	28				2	GEL								3																		
MUD	12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added																																																										
WEIGHT	8.4	8.4	8.4	8.4		1800	1 1/4	1																																																										
VISCOSITY	28	28	28	28				2																																																										
GEL								3																																																										
<table border="1"> <tr> <th>No. 1</th> <th>Pres-sure</th> <th>1000</th> <th>✓</th> <th>✓</th> <th>✓</th> <th>✓</th> <th>✓</th> <th>✓</th> </tr> <tr> <th>Model</th> <th>S.P.M.</th> <td>58</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> <td>✓</td> </tr> <tr> <th>U</th> <th>Liner Size</th> <td>5 1/2 X 15</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>No. 2</th> <th>Pres-sure</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>Model</th> <th>S.P.M.</th> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> <tr> <th>S</th> <th>Liner Size</th> <td>5 1/2 X 14</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>													No. 1	Pres-sure	1000	✓	✓	✓	✓	✓	✓	Model	S.P.M.	58	✓	✓	✓	✓	✓	✓	U	Liner Size	5 1/2 X 15							No. 2	Pres-sure								Model	S.P.M.								S	Liner Size	5 1/2 X 14						
No. 1	Pres-sure	1000	✓	✓	✓	✓	✓	✓																																																										
Model	S.P.M.	58	✓	✓	✓	✓	✓	✓																																																										
U	Liner Size	5 1/2 X 15																																																																
No. 2	Pres-sure																																																																	
Model	S.P.M.																																																																	
S	Liner Size	5 1/2 X 14																																																																
<table border="1"> <tr> <th>W.L.</th> <th>F.C.</th> <th>pH.</th> <th>Solids</th> <th>Cement</th> </tr> <tr> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>													W.L.	F.C.	pH.	Solids	Cement																																																	
W.L.	F.C.	pH.	Solids	Cement																																																														

REMARKS	Start	Time	Interval
RIG SERU + HYDRIL	1700	12 1/2	1/4
DRILG	12 1/2	330	3 1/4
SURVEY @ 1800 1 1/4	330	345	1/4
DRILG	345	800	4 1/4
			8
FIELD BLOWOUT DRILL			

Tour — Midnight - 8 a.m.		
Specify actual hours worked.		
Driller	J. WEST	12
Derrick	J. TOKAR	12
Motor	G. FLATO	12
Floor	D. HRDLICA	12
Floor	K. LEGUIERRE	12

Accidents NIL
 Outside Temp. +10°
 Weather Conditions CLEAR
 Road Conditions

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands																																				
1930	163	2093	7 3/4	65m	No. 5	O.D. 6 1/4	I.D. 2 1/8	Wgt. 16 1/2	Gals.	Bbls.	Gal.	1414.85																																				
<table border="1"> <tr> <th>No.</th> <th>Size</th> <th>Type</th> <th>Size Jets</th> <th>Serial No.</th> <th>Wt.</th> <th>R.P.M.</th> <th>From</th> <th>To</th> <th>Ftg.</th> <th>Hrs.</th> <th>Ft. Reamed</th> <th>Hrs.</th> <th>COND.</th> </tr> <tr> <td>5</td> <td>8 1/4</td> <td>XSSR</td> <td>3-11</td> <td>38833</td> <td>40</td> <td>48</td> <td>1010</td> <td>2093</td> <td>1083</td> <td>46 3/4</td> <td></td> <td></td> <td>DRILL</td> </tr> </table>													No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	5	8 1/4	XSSR	3-11	38833	40	48	1010	2093	1083	46 3/4			DRILL								
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.																																			
5	8 1/4	XSSR	3-11	38833	40	48	1010	2093	1083	46 3/4			DRILL																																			
<table border="1"> <tr> <th>MUD</th> <th>8 a.m.</th> <th>10 a.m.</th> <th>12 p.m.</th> <th>2 p.m.</th> <th>Additives</th> <th>At Surveys Degree</th> <th>MOTOR HOURS</th> <th>Oil Added</th> </tr> <tr> <td>WEIGHT</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> <td>6</td> <td>545</td> <td>RAPIDRILL</td> <td>1</td> </tr> <tr> <td>VISCOSITY</td> <td>28</td> <td>28</td> <td>28</td> <td>28</td> <td></td> <td></td> <td></td> <td>2</td> </tr> <tr> <td>GEL</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>3</td> </tr> </table>													MUD	8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added	WEIGHT	8.4	8.4	8.4	8.4	6	545	RAPIDRILL	1	VISCOSITY	28	28	28	28				2	GEL								3
MUD	8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added																																								
WEIGHT	8.4	8.4	8.4	8.4	6	545	RAPIDRILL	1																																								
VISCOSITY	28	28	28	28				2																																								
GEL								3																																								
<table border="1"> <tr> <th>No. 1</th> <th>Pres-sure</th> <th>1000</th></tr></table>													No. 1	Pres-sure	1000	1000 <th>1000 <th>1000 <th>✓</th> <th>✓</th> <th>✓</th> </th></th>	1000 <th>1000 <th>✓</th> <th>✓</th> <th>✓</th> </th>	1000 <th>✓</th> <th>✓</th> <th>✓</th>	✓	✓	✓																											
No. 1	Pres-sure	1000																																														
Model	S.P.M.	58	58	58	58	✓	✓	✓																																								
U	Liner Size	5 1/2 X 15																																														
No. 2	Pres-sure																																															
Model	S.P.M.																																															
S	Liner Size	5 1/2 X 14																																														

| | W.L. | F.C. | pH. | Solids | Cement | |------|------|-----|--------|--------| | | | | | | | | | | | | | | | | | | |

REMARKS	Start	Time	Interval
RIG SERU + KELLY COCK	800	8 1/2	1/4
DRILG	8 1/2	400	7 3/4
			8
Pick up Roller Reamer on May 4			

Tour — 8 a.m. to 4 p.m.		
Specify actual hours worked.		
Driller		
Derrick		
Motor		
Floor	B. STACHANIK	12
Floor	A. SOMMER	12
Floor	B. SIMPSON	12
Floor	F. DENEVE	12

Accidents
 Outside Temp.
 Weather Conditions
 Road Conditions

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands																																										
2093	48	2141	4	66m	No. 5	O.D. 6 1/4	I.D. 2 1/8	Wgt. 16 1/2	Gals.	Bbls.	Gal.	1414.85																																										
<table border="1"> <tr> <th>No.</th> <th>Size</th> <th>Type</th> <th>Size Jets</th> <th>Serial No.</th> <th>Wt.</th> <th>R.P.M.</th> <th>From</th> <th>To</th> <th>Ftg.</th> <th>Hrs.</th> <th>Ft. Reamed</th> <th>Hrs.</th> <th>COND.</th> </tr> <tr> <td>5</td> <td>8 1/4</td> <td>XSSR</td> <td>3-11</td> <td>38833</td> <td>40</td> <td>48</td> <td>1010</td> <td>2141</td> <td>1131</td> <td>50 1/4</td> <td></td> <td></td> <td>871</td> </tr> <tr> <td>6</td> <td>8 1/4</td> <td>RPG 2 B</td> <td>3-11</td> <td>WF-216</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </table>													No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	5	8 1/4	XSSR	3-11	38833	40	48	1010	2141	1131	50 1/4			871	6	8 1/4	RPG 2 B	3-11	WF-216									
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.																																									
5	8 1/4	XSSR	3-11	38833	40	48	1010	2141	1131	50 1/4			871																																									
6	8 1/4	RPG 2 B	3-11	WF-216																																																		
<table border="1"> <tr> <th>MUD</th> <th>4 p.m.</th> <th>6 p.m.</th> <th>8 p.m.</th> <th>10 p.m.</th> <th>Additives</th> <th>At Surveys Degree</th> <th>MOTOR HOURS</th> <th>Oil Added</th> </tr> <tr> <td>WEIGHT</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> <td>8.4</td> <td>0</td> <td>RAPIDRILL - 8 LBS</td> <td>2130</td> <td>2 3/4</td> </tr> <tr> <td>VISCOSITY</td> <td>28</td> <td>28</td> <td>28</td> <td>28</td> <td></td> <td></td> <td></td> <td>1</td> </tr> <tr> <td>GEL</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td>2</td> </tr> </table>													MUD	4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added	WEIGHT	8.4	8.4	8.4	8.4	0	RAPIDRILL - 8 LBS	2130	2 3/4	VISCOSITY	28	28	28	28				1	GEL								2						
MUD	4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives	At Surveys Degree	MOTOR HOURS	Oil Added																																														
WEIGHT	8.4	8.4	8.4	8.4	0	RAPIDRILL - 8 LBS	2130	2 3/4																																														
VISCOSITY	28	28	28	28				1																																														
GEL								2																																														
<table border="1"> <tr> <th>No. 1</th> <th>Pres-sure</th> <th>1000</th></tr></table>													No. 1	Pres-sure	1000	1000 <th>1000 <th>✓</th> <th>✓</th> <th>✓</th> <th>✓</th> </th>	1000 <th>✓</th> <th>✓</th> <th>✓</th> <th>✓</th>	✓	✓	✓	✓																																	
No. 1	Pres-sure	1000																																																				
Model	S.P.M.	58	58	58	✓	✓	✓	✓																																														
U	Liner Size	5 1/2 X 15																																																				
No. 2	Pres-sure																																																					
Model	S.P.M.																																																					
S	Liner Size	5 1/2 X 14																																																				

| | W.L. | F.C. | pH. | Solids | Cement | |------|------|-----|--------|--------| | | | | | | | | | | | | | | | | | | |

REMARKS	Start	Time	Interval
RIG SERV & CLOSE HYDRIL	400		
BY REMOTE WORKING O.K.		415	1/4
DRILL 8 1/4" HOLE	415	815	4
DROP SURVEY & TRIP OUT	815	1000	1 3/4
MAKE UP BIT #1 & CHANGE	1000		
STABILIZERS AROUND 160' FROM			
BOTTOM & STABILIZER 30'		1030	1/2
TRIP IN WITH BIT #1	1030	1130	1
WORKING JUNK SUB.	1130	1200	1/2
HELD 5 MIN SAFETY MEET			8
CHECKED ALL FIRE EXTINGUISHERS O.K.			

Tour — 4 p.m. to Midnight		
Specify actual hours worked.		
Driller	L. PEDERSEN	12
Derrick	H. MACHOW	12
Motor	H. COCHRANE	12
Floor	H. TOKAR	12
Floor	G. KESLER	12

Accidents NIL
 Outside Temp. 20°
 Weather Conditions CLOUDY
 Road Conditions

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher John Miller
 B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by John Miller

DATE MAY 3 1972

Rig No. 8 Report No. 9

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	J. WEST	12
Derrick	J. TOKAR	12
Motor	G. FLATO	12
Floor	K. LEQUERRER	12
Floor	D. HERDLICA	12
Accidents NIL		
Outside Temp. +15		
Weather Conditions CLEAR		
Road Conditions —		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller		
Derrick		
Motor		
Floor	B. STACHNIK	12
Floor	K. SAMMER	12
	B. SIMPSON	12
	E. DENIEVE	12
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	L. PEDERSEN	12
Derrick	H. MACKOW	12
Motor	K. COCHRANE	12
Floor	V. TOKAR	12
Floor	G. KESLER	12
Accidents NIL		
Outside Temp. 30°		
Weather Conditions CLEAR		
Road Conditions —		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller Toolpusher John Miller
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE MAY 2ND 19 72

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 8

[illegible]

REMARKS	Time		
	Start	Stop	Interval
RIG SERV + ✓ BOP EQUIP	12 ⁰⁰	12 ¹⁵	1/4
CIRC + CONDITION HOLE F/TST	12 ¹⁵	1 ⁰⁰	3/4
DUMM V TRIP (HOLE GOOD)	1 ⁰⁰	1 ³⁰	1/2
CIRC	1 ³⁰	2 ⁰⁰	1/2
TRIP OUT TO TEST (SLM)	2 ⁰⁰	3 ³⁰	1 1/2
PICK UP 4 3/4" DC F / TAIL PIPE +	3 ³⁰	-	-
MAKE UP PACKER + RIG UP TO RUN DST	-	5 ⁴⁵	2 1/4
RUN IN HOLE	5 ⁴⁵	6 ⁴⁵	1
HEAD UP + RUN DST #1	6 ⁴⁵	8 ⁰⁰	1 1/4
With Pipe	Without Pipe	Standby	
DRILL STEM TEST #1	8 ⁰⁰	11 ⁴⁵	3 3/4
PULL OUT	11 ⁴⁵	1 ⁰⁰	1 1/4
BREAK DOWN TEST TOOL.	1 ⁰⁰	2 ¹⁵	1 1/4
TRIP IN WITH BIT "5"	2 ¹⁵	3 ¹⁵	1
DRILL 8 3/4" HOLE	3 ¹⁵	4 ⁰⁰	3/4
			B
DST#1 900'-1010'			
Times Perflow 5min ISI / hr NO 90min PSI 90min			
Recovered 890' fluid			
Temp 80°F			
With Pipe	Without Pipe	Standby	
DRILL 8 3/4" HOLE	4 ⁰⁰	4 ¹⁵	1/4
RIG SERVICE & CONNECTION	4 ¹⁵	4 ³⁰	1/4
DRILL 8 3/4" HOLE	4 ³⁰	12 ⁰⁰	7 1/2
			B
HOLD 5 MIN SAFETY MEET.			
With Pipe	Without Pipe	Standby	

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	J. WEST	12
Derrick	J. TOKAR	12
Motor	G. FLATO	12
Floor	K. LEGUERRIER	12
Floor	D. HRDLICA	12
Accidents NIL		
Outside Temp. +15°		
Weather Conditions CLEAR		
Road Conditions —		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller		
Derrick		
Motor		
Floor	B. STACHNIAK	12
Floor	K. SOMMER	12
Floor	R. SIMPSON	12
Floor	NEVE	12
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	L. PEDERSEN	12
Derrick	H. MACKOW	12
Motor	K. COCHRANE	12
Floor	H. TOKAR	12
Floor	G. KESLER	12
Accidents NIL		
Outside Temp. 35°		
Weather Conditions CLEAR		
Road Conditions —		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller Toolpusher John Miller
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE MAY 1ST 1972

Rig No. 8 Report No. 437

[illegible]

Rig No. 8 Report No. 187

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller <u>TERRY WEST</u>	<u>12</u>
Derrick <u>JOHN TOKAR</u>	<u>12</u>
Motor <u>GENE FLATO</u>	<u>12</u>
Floor <u>KEN LEVEQUE</u>	<u>12</u>
Floor <u>DAVE HRODICA</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp. <u>0°</u>	
Weather Conditions <u>OVERCAST</u>	
Road Conditions <u>GOOD</u>	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor <u>B STACHNIK</u>	<u>12</u>
Floor <u>K SOMMER</u>	<u>12</u>
<u>B SIMPSON</u>	<u>13</u>
<u>F DENEVIE</u>	<u>12</u>
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller <u>L PEDERSEN</u>	<u>12</u>
Derrick <u>H. MACDONALD</u>	<u>12</u>
Motor <u>K COCHRANE</u>	<u>12</u>
Floor <u>V. TOKAR</u>	<u>12</u>
Floor <u>G KESLER</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp. <u>25°</u>	
Weather Conditions <u>CLEAR</u>	
Road Conditions	

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher John Miller Toolpusher John Miller
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE April 30 1972

Rig No. 8 Report No. 12

Tour — Midnight - 8 a.m.		
Specify actual hours worked.	Hrs.	
Driller <u>J. CHABOT</u>	12	
Derrick <u>J. TOKAR</u>	12	
Motor <u>G. FLEED</u>	12	
Floor <u>H. LECHERRING</u>	12	
Floor <u>E. APR 129-72</u>		
Driller, <u>JERRY WEST</u>	8	
Floor <u>DAVE HRDLICKA</u>	8	
Unable to get to Rig Floor		
Accidents	No Ann Wells. d.c.	
Outside Temp.	To bad weather	
Weather Conditions	H. 2	
Road Conditions		
Tour — 8 a.m. to 4 p.m.		
Specify actual hours worked.	Hrs.	
Driller <u>TERRY WEST</u>	8	
Derrick <u>S</u>		
Motor		
Floor <u>DAVE HRDLICKA</u>	8	
Floor <u>TRAVEL TO RIG 8</u>		
<u>B. SIMPSON</u>	15	
<u>F. DENEVE</u>	12	
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
Specify actual hours worked.	Hrs.	
Driller <u>L. PEDERSEN</u>	15	
Derrick <u>H. MACKIN</u>	12	
Motor <u>K. COCHRANE</u>	12	
Floor <u>V. TOKAR</u>	12	
Floor <u>G. KESLER</u>	12	
<u>B. STACHNIK</u>	12	
<u>K. SOMMER</u>	12	
Accidents	NIL	
Outside Temp.	15°	
Weather Conditions	CLEAR	
Road Conditions	—	

DATE April 28 1972

Rig No. 8 Report No. 11

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
										No.	O.D.	I.D.	Wgt.	Gals.		Bbls.		Gal.			
																				Singles	
																				Bbls.	
B I T S	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars					
																Other Ft.					
																C.B. Ft.					
																Subs. Ft.					
MUD				4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS		Oil Added			
WEIGHT																1		8			
VISCOSITY																2		2			
GEL																3					
P U M P S	No. 1	Pressure													Light		8				
	Model	S.P.M.													BOILER HRS.		8		TOTAL		
		Liner Size					Size	TRIPS	No. Lines	TON MILES	TOTAL MILES	Slip	Feet or	Cut	Feet Left on Spool	Next Slip					
	No. 2	Pressure																			
	Model	S.P.M.					Water Truck Hours:														
		Liner Size					Desilter Hours:														
W.L.		F.C.	p.H.	Solids.		Desander Hours:															

Collar 1 3rd joint + one collar in 9' ft. Cemented w/ 350 Sacs of Findex Cement. displaced Plug w/ water. Got 16 barrels Cement Returns. Plug down @ 12:04 P.M. on April 29-1972.				
W.O.C. + DUMPED + CLEANED 4:00 TANKS + FILLED WITH WATER PRIMED PUMPS, RIG UP TO PICK UP B.O.P.S				DERRICK
			1200 8	
With Pipe	Without Pipe	Standby		

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor B STACHNIK	12
Floor K SOMMER	12
B. SIMPSON	14
F. DENEVE	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	L. PEDERSEN	12
Derrick	W. L. LINDSEY	
Motor	R. G. LINDSEY	
Floor	V. TOKAR	12
Floor	G. KIESLER	12
	H. MACKOW	12

Accidents *NIL*

Outside Temp. *10°*

Weather Conditions *CLOUDY + SNOWING*

Road Conditions *—*

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____ Toolpusher _____
 S.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE APRIL 28 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE APRIL 28 1972Rig No. 8 Page No. 9 LOCATION CANDEL MUD OIL TROUGH 1-11

NOTE: Do Not Record Payroll Information Here

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.		D. Collars	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.		D. Collars	
78		207		285		54		30		30		90		78		285		207		54						244			
5		12 1/4		REAMER		-		845-P		30		90		78		285		207		54						244			
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added													
WEIGHT																													
VISCOSITY		62		64		64																							
GEL																													
No. 1		Pres- sure		250		350		350																					
Model		S.P.M.		68		68		68																					
No. 2		Pres- sure		55		15																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14																							
Model		S.P.M.																											
No. 2		Pres- sure		5 1/2		14</																							

DATE APRIL 27 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE APRIL 27 1972Rig No. 8 Page No. 9LOCATION CANDEL MOBILE OIL IRQUOIS 1-11

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 9

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands	
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.
561	101	662	74	48	No. 14	O.D. 6 1/2	I.D. 2 3/4	Wgt. 45				30.84	
B	3	8 3/4	ODV	2-12-1-13	14702	30	90	424	662	238	18		
I													
T													
S													
MUD 12 a.m. 2 a.m. 4 a.m. 6 a.m. Additives													
WEIGHT 51 52 50 53													
VISCOSITY													
GEL													
P	No. 1	Pres-ure	1200	"	1200	"							
U	Model	S.P.M.	68	"	68	"							
M	No. 2	Pres-ure	55	"	15								
P	Model	S.P.M.											
S	No. 2	Pres-ure	55	"	14								
W.L. F.C. pH. Solids Cement													
From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands	
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.
662	85	747	74	48	No. 14	O.D. 6 1/2	I.D. 2 3/4	Wgt. 45				9353	
B	3	8 3/4	ODV	2-3-1-15	14702	30	90	424	747	323	254		
I													
T													
S													
MUD 8 a.m. 10 a.m. 12 p.m. 2 p.m. Additives													
WEIGHT													
VISCOSITY													
GEL													
P	No. 1	Pres-ure	1200	"	1200	"							
U	Model	S.P.M.	68	"	68	"							
M	No. 2	Pres-ure	55	"	15								
P	Model	S.P.M.											
S	No. 2	Pres-ure	55	"	14								
W.L. F.C. pH. Solids Cement													
From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands	
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.
747	72	819	5 1/2	50	No. 14	O.D. 6 1/2	I.D. 2 3/4	Wgt. 45				18696	
B	3	8 3/4	ODV	2-3-1-15	14702	30	90	424	750	326	254		
I													
T													
S													
MUD 4 p.m. 6 p.m. 8 p.m. 10 p.m. Additives													
WEIGHT 92 GEL - 10 SKS													
VISCOSITY 58 65													
GEL													
P	No. 1	Pres-ure	1200	"	1000	"							
U	Model	S.P.M.	68	"	68	"							
M	No. 2	Pres-ure	55	"	15								
P	Model	S.P.M.											
S	No. 2	Pres-ure	55	"	14								
W.L. F.C. pH. Solids Cement													

REMARKS	Time		
	Start	Stop	Interval
DRILL 8 3/4" HOLE	12 00	12 45	3/4
RIG SERVICE + CONNECTION	12 45	1 00	1/4
DRILL 8 3/4" HOLE	1 00	5 30	4 1/2
SURVEY AT 620 FT. 3/4"	5 30	6 00	1/2
DRILL 8 3/4" HOLE	6 00	8 00	2
8			
HELD 5 MIN SAFETY MEETING			
With Pipe	Without Pipe	Standby	
DRILL 8 3/4" HOLE	8 00	8 15	1/4
SURVEY AT 650 FT. 3/4"	8 15	8 30	1/4
DRILL 8 3/4" HOLE	8 30	1 15	5 1/4
SURVEY AT 710 1/4" & RIG SERVICE	2 15	2 15	1/2
DRILL 8 3/4" HOLE	2 15	4 00	1 3/4
8			
With Pipe	Without Pipe	Standby	
DRILL 8 3/4" HOLE	4 00	4 15	1/4
TRIP OUT BIT #3 ODV.	4 15	5 00	3/4
RIG SERVICE	5 00	5 15	1/4
TRIP IN BIT #4 DT2.	5 15	6 15	1
DRILL 8 3/4" HOLE	6 15	11 30	5 1/4
SURVEY AT 800. 1/2"	11 30	11 45	1/4
LAY DOWN 5 SINGLES	11 45	12 00	1/4
8			
HELD 5 MIN SAFETY MEET			
With Pipe	Without Pipe	Standby	

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller C STAROBA	12
Derrick J TOKAR	12
Motor G. FLATO	12
Floor H. MACKOW	12
Floor K. LE GUERRIER	12
Accidents NIL	
Outside Temp. 5°	
Weather Conditions Clear	
Road Conditions —	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor K. SIMPSON	12
Floor B. SIMPSON	12
Floor F. DIENEVE	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller L. PEDERSEN	12
Derrick S. CHABOT	12
Motor P. GAIMANO	12
Floor I. TOKAR	12
Floor G. KESLER	12
Accidents NIL	
Outside Temp. 20°	
Weather Conditions CLEAR	
Road Conditions —	

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____
 B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____
 Toolpusher _____ Approved by _____

DATE APRIL 26 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE APRIL 26 1972Rig No. 8 Page No. 8 LOCATION CANDEL MOBILE OIL TANKS 1-11

NOTE: Do Not Record Payroll Information Here

From	Footage	To	Hrs. on Bottom	Wt. Drill String (1000 lbs.)	DRILL COLLARS				FUEL	WATER	CRUDE	Stands	
No.	Size	Type	Size Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Fr. Reamed	Hrs.	COND.
272	119	391	6 1/4	38	No. 5	O.D. 6 1/8	I.D. 2 3/8	Wgt. 30					
2	8 3/4	DT-2	-	37621	20	110	127	391	214	14 1/2			
MUD				12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives		At Surveys Degree		MOTOR HOURS	
WEIGHT										300		1 8	
VISCOSITY				65		68		66		67		3	
GEL												3	
P	No. 1	Pressure	50	50	50	100							
U	Model	S.P.M.	56	56	56	56							
M	No. 2	Pressure	55	55	55	55							
P	Model	S.P.M.											
S	Liner Size												
W.L.				F.C.	pH	Solids	Cement						

REMARKS	Start	Stop	Interval
DRILL 8 3/4" HOLE	12:00	1:15	1 1/4
RIG SERVICE + SURVEY 390-5'	1:15	1:45	30
DRILL 8 3/4" HOLE	1:45	2:45	1
PUT ON + TIGHTEN BELTS ON	2:45		
AIR COMPRESSOR + WATER PUMP		3:00	1/4
DRILL 8 3/4" HOLE	3:00	5:15	2 1/4
CONNECTION + SURVEY 350-4'	5:15	5:45	30
CIRC + REAM BACK TO BOTTOM	5:45	6:15	30
DRILL 8 3/4" HOLE	6:15	8:00	1 3/4
HELD 5 MIN SAFETY MEETING			
With Pipe	Without Pipe	Standby	
DRILL 8 3/4" HOLE	8:00	9:45	1 3/4
WORK TIGHT HOLE	9:45	10:15	30
PULL OUT DRILL COLLAR +	10:15		
RUN IN WITH BIT #3		11:45	1 1/2
REAM TO BOTTOM	11:45	12:15	30
DRILL 8 3/4" HOLE	12:15	2:00	1 3/4
SURVEY AT 4:40 EE 1/2"	2:00		
+ RIG SERVICE		2:30	1/2
DRILL 8 3/4" HOLE	2:30	4:00	1 1/2
With Pipe			
Without Pipe	Standby		
DRILL 8 3/4" HOLE	4:00	9:30	5 1/2
CONNECTION + RIG SERVICE	9:30		
SURVEY AT 5:30 1/8"		10:00	1/2
DRILL 8 3/4" HOLE	10:00	12:00	2 1/4
HELD 5 MIN SAFETY MEET			
CHECKED ALL FIRE EXTINGUISHERS			
With Pipe	Without Pipe	Standby	

Rig No.	Report No.
8	8
Tour — Midnight - 8 a.m.	
Specify actual hours worked.	
Driller	C. STAROBA 12
Derrick	J. TOKAR 12
Motor	G. FLATO 12
Floor	H. MACKOW 12
Floor	K. LEGUERRIER 12
Accidents NIL	
Outside Temp. 10°	
Weather Conditions SNOW	
Road Conditions -	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	
Driller	
Derrick	
Motor	
Floor	B. STACHNIN 12
Floor	H. SCHMIDT 12
Floor	B. SIMPSON 12
Floor	F. DENRUE
Accidents NIL	
Outside Temp.	
Weather Conditions	
Road Conditions	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	
Driller	L. PEDERSEN 12
Derrick	S. CHAROT 12
Motor	P. GAUMAND 12
Floor	V. TOKAR 12
Floor	G. KESLER 12
Floor	B. SIMPSON 12
Accidents NIL	
Outside Temp. 20°	
Weather Conditions CLOUDY	
Road Conditions -	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher
 B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by
 Approved by

DATE APRIL 25 1972

Rig No. 8 Report No. 7

REMARKS	Time		
	Start	Stop	Interval
PICK UP BOTTOM HOLE COLLAR 120"			
+ A COLLAR + INSTALL KELLY		1 ⁰⁰	1
CIRC + MIX MUD TO RAISE VIS	1 ⁰⁰	2 ³⁰	1 1/2
DRILL 8 3/4" SURFACE HOLE	2 ³⁰	3 ⁰⁰	1/2
RIG SERVICE + MAKE CONNECTION	3 ⁰⁰	3 ¹⁵	1/4
DRILL 8 3/4" HOLE	3 ¹⁵	6 ⁴⁵	3 1/2
PULL COLLAR + UNPUMP BIT	6 ⁴⁵		
PICK UP 1 DRILL COLLAR + 1 REAMER		7 ¹⁵	1/2
DRILL 8 3/4" HOLE	7 ¹⁵	8 ⁰⁰	3/4
			8
HELD 5 MIN SAFETY MEETING			
	With Pipe	Without Pipe	Standby
DRILL 8 3/4" HOLE	8 ⁰⁰	8 ⁴⁵	1 1/4
RUN SURVEY 120' 3/4"	8 ⁴⁵	9 ⁰⁰	1 1/2
DRILL	9 ⁰⁰	10 ⁰⁰	1"
PULL OUT COLLARS +	10 ⁰⁰		
CHECK BIT BUCKET TOOTH STUCK			
IN BIT CONES RUN IN WITH			
SAME BIT		11 ¹⁵	1 1/5
DRILL 8 3/4" HOLE	11 ¹⁵	12 ¹⁵	1
TRIP FOR PLUGGED JETS	12 ¹⁵	1 ¹⁵	1
DRILL 8 3/4" HOLE	1 ¹⁵	3 ¹⁵	2
SURVEY AT 150' 1/2"	3 ¹⁵	3 ⁴⁵	1/2
DRILL 8 3/4" HOLE	3 ⁴⁵	4 ⁰⁰	1/4
	With Pipe	Without Pipe	Standby
DRILL 8 3/4" HOLE	4 ⁰⁰	6 ¹⁵	2 1/4
TRIP OUT BIT # 2	6 ¹⁵	6 ³⁰	1/4
TRIP IN WITH BIT # 2. PRICE	6 ³⁰		
OF BUCKET TOOTH STUCK IN			
CONES		7 ⁰⁰	3 1/2
DRILL 8 3/4" HOLE	7 ⁰⁰	7 ¹⁵	1/4
CONNECTION + RIG SERVICE	7 ¹⁵	7 ⁴⁵	1/2
DRILL 8 3/4" HOLE	7 ⁴⁵	10 ¹⁵	2 1/2
SURVEY AT 240' - 1/2"	10 ¹⁵	11 ⁰⁰	3/4
DRILL 8 3/4" HOLE	11 ⁰⁰	12 ⁰⁰	1
HELD 5 MIN SAFETY MEET			8
	With Pipe	Without Pipe	Standby

Tour — Midnight - 8 a.m.		
Specify actual hours worked.	Hrs.	
Driller C. STAROBA	12	
Derrick J. TOKAR	12	
Motor G. FLATO	12	
Floor H. MACKOW	12	
Floor K. LEGUERRIER	12	
Accidents NIL		
Outside Temp. 70		
Weather Conditions SNOW		
Road Conditions SLIPPERY		
Tour — 8 a.m. to 4 p.m.		
Specify actual hours worked.	Hrs.	
Driller V		
Derrick		
Motor		
Floor		
Floor		
B. SIMPSON	14	
E. DENIÈVE	12	
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
Specify actual hours worked.	Hrs.	
Driller J. PEDERSEN	12	
Derrick S. CHAROT	12	
Motor P. GAUMOND	12	
Floor V. TOKAR	12	
Floor G. KESLER	12	
B. STANLEY	12	
H. SCHMIDT	12	
Accidents NIL		
Outside Temp. 10+		
Weather Conditions CLOUDY		
Road Conditions CLOSED		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____
 B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE APRIL 24 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 6

[illegible]

Driller	C. STAROBA	12
Derrick	J. TOKAR	12
Motor	G. FLATO	12
Floor	H. MACKOW	12
Floor	K. LEGUERRIER	12

Accidents *NIL*
Outside Temp. *5^T*
Weather Conditions *MILD*
Road Conditions *Rough*

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.

Driller	
Derrick	
Motor	
Floor	
Floor	
B. SIMPSON	
H. F. DENEVE	

Accidents
Outside Temp.
Weather Conditions
Road Conditions

Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.

Driller	L PEDERSEN	12
Derrick	S. CHABOT	12
Motor	P. GAUMOND	12
Floor	V. THAR	12
Floor	G. KESLER	12

Accidents *NIL*
Outside Temp. *15°*
Weather Conditions *CLOUDY*
Road Conditions *FAIR*

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher 
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____

Toolpusher

Approved by

DATE APRIL 23 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE APRIL 23 1972Rig No. 8 Page No. 5LOCATION CANDEL MOGIL OIL TROUVIS 1-11

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 5

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives				At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																							
VISCOSITY																							
GEL																							
No. 1		Pres- sure																					
Model		S.P.M.																					
No. 2		Pres- sure																					
Model		S.P.M.																					
No. 3		Pres- sure																					
Model		S.P.M.																					
No. 4		Pres- sure																					
Model		S.P.M.																					
No. 5		Pres- sure																					
Model		S.P.M.																					
No. 6		Pres- sure																					
Model		S.P.M.																					
No. 7		Pres- sure																					
Model		S.P.M.																					
No. 8		Pres- sure																					
Model		S.P.M.																					
No. 9		Pres- sure																					
Model		S.P.M.																					
No. 10		Pres- sure																					
Model		S.P.M.																					
No. 11		Pres- sure																					
Model		S.P.M.																					
No. 12		Pres- sure																					
Model		S.P.M.																					
No. 13		Pres- sure																					
Model		S.P.M.																					
No. 14		Pres- sure																					
Model		S.P.M.																					
No. 15		Pres- sure																					
Model		S.P.M.																					
No. 16		Pres- sure																					
Model		S.P.M.																					
No. 17		Pres- sure																					
Model		S.P.M.																					
No. 18		Pres- sure																					
Model		S.P.M.																					
No. 19		Pres- sure																					
Model		S.P.M.																					
No. 20		Pres- sure																					
Model		S.P.M.																					
No. 21		Pres- sure																					
Model		S.P.M.																					
No. 22		Pres- sure																					
Model		S.P.M.																					
No. 23		Pres- sure																					
Model		S.P.M.																					
No. 24		Pres- sure																					
Model		S.P.M.																					
No. 25		Pres- sure																					
Model		S.P.M.																					
No. 26		Pres- sure																					
Model		S.P.M.																					
No. 27		Pres- sure																					
Model		S.P.M.																					
No. 28		Pres- sure																					
Model		S.P.M.																					
No. 29		Pres- sure																					
Model		S.P.M.																					
No. 30		Pres- sure																					
Model		S.P.M.																					
No. 31		Pres- sure																					
Model		S.P.M.																					
No. 32		Pres- sure																					
Model		S.P.M.																					
No. 33		Pres- sure																					
Model		S.P.M.																					
No. 34		Pres- sure																					
Model		S.P.M.																					
No. 35		Pres- sure																					
Model		S.P.M.																					
No. 36		Pres- sure																					
Model		S.P.M.																					
No. 37		Pres- sure																					
Model		S.P.M.																					
No. 38		Pres- sure																					
Model		S.P.M.																					
No. 39		Pres- sure																					
Model		S.P.M.																					
No. 40		Pres- sure																					
Model		S.P.M.																					
No. 41		Pres- sure																					
Model		S.P.M.																					
No. 42		Pres- sure																					
Model		S.P.M.																					
No. 43		Pres- sure																					
Model		S.P.M.																					
No. 44		Pres- sure																					
Model		S.P.M.																					
No. 45		Pres- sure																					
Model		S.P.M.																					
No. 46		Pres- sure																					
Model		S.P.M.																					
No. 47		Pres- sure																					
Model		S.P.M.																					
No. 48		Pres- sure																					
Model		S.P.M.																					
No. 49		Pres- sure																					
Model		S.P.M.																					
No. 50		Pres- sure																					
Model		S.P.M.																					
No. 51		Pres- sure																					
Model		S.P.M.																					
No. 52		Pres- sure																					
Model		S.P.M.																					
No. 53		Pres- sure																					
Model		S.P.M.																					
No. 54		Pres- sure																					
Model		S.P.M.																					
No. 55		Pres- sure																					
Model		S.P.M.																					
No. 56		Pres- sure																					
Model		S.P.M.																					
No. 57		Pres- sure																					
Model		S.P.M.																					
No. 58		Pres- sure																					
Model		S.P.M.																					
No. 59		Pres- sure																					
Model		S.P.M.																					
No. 60		Pres- sure																					
Model		S.P.M.																					
No. 61		Pres- sure																					
Model		S.P.M.																					
No. 62		Pres- sure																					
Model		S.P.M.																					
No. 63		Pres- sure																					
Model		S.P.M.																					
No. 64																							

DATE APRIL 22 1972

Rig No. 8 Report No. 4

REMARKS	Time		
	Start	Stop	Interval
LAY 20" BUCKET DOWN +	12"		
PICK 24" BUCKET UP		12 ³⁰	$\frac{1}{2}$
REAM WITH 24" BUCKET	12 ³⁰	1 ³⁰	1
RIG SERVICE + CONNECTION	1 ³⁰	1 ⁴⁵	$\frac{1}{4}$
REAM WITH 24" BUCKET	1 ⁴⁵	8 ⁰⁰	6 $\frac{1}{4}$
			8
HELD 5 MIN SAFETY MEETING			
With Pipe	Without Pipe	Standby	
REAM WITH 24" BUCKET	8"	9 ¹⁵	$1\frac{1}{4}$
LAY DOWN SINGLE + 24"	9 ¹⁵		
BUCKET		9 ⁴⁵	$\frac{1}{2}$
PICK UP 20" LINER WELD	9 ⁴⁵		
ON STRAPS + RUN IN THE HOLE		10 ³⁰	$\frac{3}{4}$
CEMENT 20" LINER	10 ³⁰	12:00	$1\frac{1}{2}$
W.O.C + RIG UP TO DRILL	12:00	4:00	4
RAT HOLE. RIG TO CIRCULATE WATER			
PRIME MUD PUMP + FILL TANKS w/ WATER.			
RAN 89 FT OF 2.0 INCH CONDUCTOR P.H. WELDED +			
SEAMS WELDED @ JOINTS RAN 100 SACS OF FORD'S CEMENT			
FINISH CEMENT @ 12:00 P.M. IN APRIL 2, 1972			
With Pipe	Without Pipe	Standby	
60 FT OF 2.0" CONDUCTOR LEFT IN GROUND.			
W.O.C + DRILL RAT HOLE @ 12:00		8	
HELD 5 MIN SAFETY MEETING			
With Pipe	Without Pipe	Standby	

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller <u>C STAROBA</u>	<u>12</u>
Derrick <u>J. TOKAR</u>	<u>12</u>
Motor <u>G FLATO</u>	<u>12</u>
Floor <u>H MACKOW</u>	<u>12</u>
Floor <u>K. LEGUERRIER</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp. - <u>10</u>	
Weather Conditions <u>CLEAR</u>	
Road Conditions <u>FAIR</u>	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor <u>K. SOMMER</u>	<u>12</u>
<u>B. STACHNIK</u>	<u>12</u>
<u>B. SIMPSON</u>	<u>16</u>
<u>F. DENEVE</u>	
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller <u>I. PEDERSEN</u>	<u>12</u>
Derrick <u>S. CHABOT</u>	<u>12</u>
Motor <u>P. GAUMOND</u>	<u>12</u>
Floor <u>V. TOKAR</u>	<u>12</u>
Floor <u>G. KESLER</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp. <u>20+</u>	
Weather Conditions <u>CLEAR</u>	
Road Conditions <u>ROUGH</u>	

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____ Toolpusher _____
 B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____ Approved by _____

DATE APRIL 21 19 72

Rig No. 8 Page No. 3 LOCATION CANDEL MOBIL OIL TROQUIS 1-11

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 3

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands							
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.		Bbls.			
10		11		21																							
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.	
B																											
I																											
T																											
S																											

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	C. STAROE	12
Derrick	J. TOKAR	12
Motor	G. FLATO	12
Floor	H. MACKOW	12
Floor	K. LEGUERRIER	12
Accidents NIL		
Outside Temp. -5		
Weather Conditions Good		
Road Conditions FAIR		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller		
Derrick		
Motor		
Floor		
Floor	K. SOMMER	12
	B. SIMPSON	16
	F. DENEVE	12
	B. STACHNIK	12
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	L. PEDERSEN	12
Derrick	S. CHABOT	12
Motor	P. GAUMOND	12
Floor	V. TOKAR	12
Floor	G. KESLER	12
Accidents NIL		
Outside Temp. 20°		
Weather Conditions CLEAR		
Road Conditions FAIR		

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher _____

B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by _____

Toolpusher

Approved by _____

DATE April 20 1972

NABORS DRILLING LIMITED

WORK RECORD

DATE APRIL 20 1972Rig No. 8 Page No. 2 LOCATION CANDEL Marble Marshall 1-11

NOTE: Do Not Record Payroll Information Here

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					
M No. 2		Pres- sure																					
S Model		S.P.M.																					
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added							
WEIGHT																							
VISCOSITY																							
GEL																							
P No. 1		Pres- sure																					
U Model		S.P.M.																					

DATE APRIL 19 1972

NABORS DRILLING LIMITED

WORK RECORD

NOTE: Do Not Record Payroll Information Here

APR 24 1972

DATE APRIL 19 1972Rig No. 8 Page No. LOCATIONRig No. 8 Report No.

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
B																							
I																							
T																							
S																							
M																							
P																							
U																							
M																							
P																							
S																							
W.L.		F.C.		pH.		Solids		Cement															
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands			
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		COND.	
B																							
I																							
T																							
S																							
M																							
P																							
U																							
M																							
P																							
S																							
W.L.		F.C.		pH.		Solids		Cement															

REMARKS

Time

Start Stop Interval

RIGGING UP

With Pipe

Without Pipe

Standby

With Pipe

Without Pipe

Standby

RIGGING UP

With Pipe

Without Pipe

Standby

Tour — Midnight — 8 a.m.

Specify actual hours worked. Hrs.

Driller	C. STAROBA	14
Derrick	J. TOKAR	14
Motor	G. FLATO	14
Floor	J. COULSON	14
Floor	H. MACKOW	14

Accidents NILOutside Temp. 0Weather Conditions ColdRoad Conditions Good

Tour — 8 a.m. to 4 p.m.

Specify actual hours worked. Hrs.

Driller		
Derrick		
Motor		
Floor		
Floor	B. SIMPSON	12
Floor	E. DENELF	12

Accidents

Outside Temp.

Weather Conditions

Road Conditions

Tour — 4 p.m. to Midnight

Specify actual hours worked. Hrs.

Driller	L. PEDERSEN	14
Derrick	S. CHABOT	14
Motor	P. BAUMOND	14
Floor	K. LEQUERRIER	14
Floor	V. TOKAR	14

Accidents NIL

Outside Temp.

Weather Conditions

Road Conditions

Totco Ring on Bit No. D.P. Caliper Date Results From Pipe Rack

Total Contractor Time Hrs. Toolpusher

B.O.P. Test-Operated Time Results

Total Company Time Hrs. Approved by

Toolpusher

Approved by

DATE APRIL 18 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No.

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	C. STAROBA	14
Derrick	J. TOKAR	14
Motor	G. FLATO	14
Floor	J. COULSON	14
Floor	H. MACKOW	14

Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
B SIMPSON	12
F DENEUE	11

Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	L PEDERSEN	14
Derrick	S. CHABOT	14
Motor	P GAUMOND	14
Floor	K LEGUERRIER	14
Floor	V. TOKAR	14

Accidents	NIL
Outside Temp.	
Weather Conditions	
Road Conditions	

....From Pipe Rack

B.O.P. Test-Operated	Time	Results
----------------------	------	---------

.....Total Contractor Time Hrs. Toolpusher

...Total Company Time Hrs. Approved by

Toolpusher

Approved by _____

DATE APRIL 17 19 72

NABORS DRILLING LIMITED

WORK RECORD

NOTE: Do Not Record Payroll Information Here

APR 24 1972

DATE APRIL 17 19 72Rig No. 8 Page No. _____ LOCATION _____Rig No. 8 Report No. _____

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
No. 3		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.	
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives		At Surveys Degree		MOTOR HOURS		Oil Added					
WEIGHT																					
VISCOSITY																					
GEL																					
No. 1		Pres- sure																			
Model		S.P.M.																			
No. 2		Pres- sure																			
Model		S.P.M.																			
W.L.		F.C.		pH.		Solids		Cement													
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands	
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To					

DATE APRIL 16 1972

NABORS DRILLING LIMITED

WORK RECORD

NOTE: Do Not Record Payroll Information Here

APR 24 1972

DATE APRIL 16 1972Rig No. 8 Page No. 1 LOCATION _____Rig No. 8 Report No. 1

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		12 a.m.		2 a.m.		4 a.m.		6 a.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		8 a.m.		10 a.m.		12 p.m.		2 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											
S Model		S.P.M.																											
Liner Size																													
W.L.		F.C.		pH.		Solids		Cement																					
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands									
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gals.		Bbls.					
No.		Size		Type		Size Jets		Serial No.		Wt.		R.P.M.		From		To		Ftg.		Hrs.		Ft. Reamed		Hrs.		COND.			
MUD		4 p.m.		6 p.m.		8 p.m.		10 p.m.		Additives				At Surveys Degree				MOTOR HOURS		Oil Added									
WEIGHT																													
VISCOSITY																													
GEL																													
P No. 1		Pres- sure																											
U Model		S.P.M.																											
M Liner Size																													
P No. 2		Pres- sure																											

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher Toolpusher
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by Approved by

DATE APRIL 14 1972

NOTE: Do Not Record Payroll Information Here

Rig No. 8 Report No. 75

[illegible]

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller C. STAROBA	12
Derrick J. TOKAR	12
Motor G. FLATO	12
Floor J. COULSON	12
Floor H. MACKOW	12
Accidents NIL.	
Outside Temp. + 25°	
Weather Conditions SNOW	
Road Conditions SLIPPERY	

Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
B. SIMPSON	12
F. DENEVE	12
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	

Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller L. PEDERSEN	12
Derrick S. CHABOT	15
Motor F. GAUMOND	12
Floor K. LEGUERRIER	15
Floor V. TOKAR	12
Accidents NIL	
Outside Temp.	
Weather Conditions	
Road Conditions	

Totco Ring on Bit No. _____ D.P. Calipered Date _____ Results _____ From Pipe Rack _____ Total Contractor Time _____ Hrs. Toolpusher *John J. [Signature]* Toolpusher _____
B.O.P. Test-Operated _____ Time _____ Results _____ Total Company Time _____ Hrs. Approved by *[Signature]* Approved by _____

DATE APRIL 13 1972

APR 24 1957

Rig No. 8 Page No. 14 LOCATION MOBIL OIL BELT HILLS M⁶³

[illegible]

Tour — Midnight - 8 a.m.	
Specify actual hours worked.	Hrs.
Driller <u>C. STAROBA</u>	<u>12</u>
Derrick <u>J. TOKAR</u>	<u>12</u>
Motor <u>G. FLATO</u>	<u>12</u>
Floor <u>J. COULSON</u>	<u>12</u>
Floor <u>H. MACKOW</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp. <u>120</u>	
Weather Conditions <u>MILD</u>	
Road Conditions <u>FAIR</u>	
Tour — 8 a.m. to 4 p.m.	
Specify actual hours worked.	Hrs.
Driller	
Derrick	
Motor	
Floor	
Floor	
<u>B. SIMPSON</u>	<u>12</u>
<u>F. DENEVE</u>	<u>12</u>
Accidents	
Outside Temp.	
Weather Conditions	
Road Conditions	
Tour — 4 p.m. to Midnight	
Specify actual hours worked.	Hrs.
Driller <u>L. PEDERSEN</u>	<u>12</u>
Derrick <u>S. CHABOT</u>	<u>12</u>
Motor <u>P. GAUMOND</u>	<u>12</u>
Floor <u>K. LEGUERRIER</u>	<u>12</u>
Floor <u>V. TOKAR</u>	<u>12</u>
Accidents <u>NIL</u>	
Outside Temp.	
Weather Conditions	
Road Conditions	

Totco Ring on Bit No. D.P. Calipered Date Results From Pipe Rack Total Contractor Time Hrs. Toolpusher *[Signature]* Toolpusher
B.O.P. Test-Operated Time Results Total Company Time Hrs. Approved by *[Signature]* Approved by

DATE April 12 1972

NABORS DRILLING LIMITED

WORK RECORD

NOTE: Do Not Record Payroll Information Here

DATE April 12 1972Rig No. 8 Page No. 73LOCATION Mobil Oil 1163APR 17 1972
Rig No. 8 Report No. 73

From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		12 a.m.	2 a.m.	4 a.m.	6 a.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		8 a.m.	10 a.m.	12 p.m.	2 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs. on Bottom		Wt. Drill String (1000 lbs.)		DRILL COLLARS				FUEL		WATER		CRUDE		Stands																																
										No.		O.D.		I.D.		Wgt.		Gals.		Bbls.		Gal.																														
B	No.	Size	Type	Size	Jets	Serial No.	Wt.	R.P.M.	From	To	Ftg.	Hrs.	Ft. Reamed	Hrs.	COND.	D. Collars	Other Ft.	C.B. Ft.	Subs. Ft.	Ft. Down On Kelly	TOTAL	Next Slip																														
I																																																				
T																																																				
S																																																				
MUD		4 p.m.	6 p.m.	8 p.m.	10 p.m.	Additives				At Surveys Degree				MOTOR HOURS				Oil Added																																		
WEIGHT												1																																								
VISCOSITY												2																																								
GEL												3																																								
P	No. 1	Pres- sure											Light Plant				8																																			
U	Model	S.P.M.											BOILER HRS.																																							
M	No. 2	Pres- sure											Size				TRIPS				No. Lines				TON MILES				TOTAL MILES				Slip				Feet or				Cut				Feet Left on Spool				Next Slip			
P	Model	S.P.M.											Casing Record				Surface Prod.																																			
S	Liner Size																																																			
W.L.		F.C.		pH.		Solids		Cement																With Pipe		Without Pipe		Standby																								
From		Footage		To		Hrs																																														

DATE APRIL 11 1972

APR 17 1972

Rig No. 8 Report No. 72

[illegible]

Tour — Midnight - 8 a.m.		
	Specify actual hours worked.	Hrs.
Driller	C. STAROBA	12
Derrick	J. TOKAR	12
Motor	G. FLATO	12
Floor	J. COULSON	12
Floor	H. MACKOW	12
Accidents NIL		
Outside Temp. + 27°		
Weather Conditions MILD		
Road Conditions FAIR		
Tour — 8 a.m. to 4 p.m.		
	Specify actual hours worked.	Hrs.
Driller		
Derrick		
Motor		
Floor		
Floor		
	B. SIMPSON	12
Accidents		
Outside Temp.		
Weather Conditions		
Road Conditions		
Tour — 4 p.m. to Midnight		
	Specify actual hours worked.	Hrs.
Driller	N. CALLAGHAN	12
Derrick	K. COCHRANE	12
Motor	P. GAUMOND	12
Floor	K. LEGUERRIER	12
Floor	V. TOKAR	12
Accidents NIL		
Outside Temp. + 27°		
Weather Conditions MILD		
Road Conditions FAIR		

Totco Ring on Bit No.D.P. Calipered DateResultsFrom Pipe RackTotal Contractor Time Hrs. Toolpusher Toolpusher
 B.O.P. Test-OperatedTimeResultsTotal Company Time Hrs. Approved by Approved by

THIS IS A CONCISE REPORT OF THE
OPERATIONS CONDUCTED AT THE WELL

'CANDEL MOBIL ET AL IROQUOIS I-11'

Data in this report was compiled for
CanDel Oil Ltd. by T. A. D. Haddow, P. Geol.,
Geological Consultant at the well

July 28, 1972

A handwritten signature in cursive script, appearing to read 'K. E. Basaraba', written in dark ink.

K. E. Basaraba,
CANDEL OIL LTD.

WELL HISTORY REPORT
ON
CANDEL MOBIL et al IROQUOIS I-11

Unit I Section 11, Grid 67-50-129-30
Latitude $67^{\circ} 40' 40''$ Longitude $129^{\circ} 32' 05''$


NORTHWEST TERRITORIES, CANADA

FOR

CANDEL OIL LTD.

June, 1972

Submitted by:


T.A.D. Haddow, P.Geol.

INDEX

	<u>Page</u>
SECTION I - Summary of Well Data	1
SECTION II - Geological Summary	
Formation Tops	3
Sample Descriptions	4
SECTION III - Engineering Summary	
Drill Stem Test Reports	29
Casing Report	32
Bit Record	33
Daily Mud Report	34
Daily Progress Report with Deviation Surveys	35
Abandonment Plugs	38
Lost Circulation Zones	38
SECTION IV - Logs	39
SECTION V - Analysis	39

SECTION I - SUMMARY OF WELL DATA

Well Name and Number: CanDel Mobil et al Iroquois I-11

Permittee: Mobil Oil Canada Ltd. License No. 1432
 Sun Oil Company License No. 1941
 Inexco Oil Company License No. 1929
 North Canadian Oils Ltd. " No. 1973

Operator: CanDel Oil Ltd. License No. 1938
 28th Floor - Calgary Place One
 330-5th Avenue S.W.
 Calgary, Alberta

Location: Unit I, Section 11, Grid 67-50-129-30
 Latitude 67° 40' 40" Longitude 129° 32' 05"
 Unique Well Identifier: 3001116750129300
 Universal Well Location Reference: 67.67778°
 129.53472°

Permit No.: 4119

Contractor: Nabors Drilling Limited Rig #8 Emsco JA 500

Drilling Authority: 584 - Issued March 1, 1972

Classification: Wildcat

Elevations: Ground 400' K.B. 418'

Spudded: 2:30 a.m. - April 25, 1972

Completed Drilling: May 28, 1972

Total Depth: Driller 6961' Logger 6944'

Well Status: Dry & Abandoned

Rig Released: 12:00 - noon - June 2, 1972

Hole Sizes: Surface - 704' 12 1/4"
 704' - 6961' 8 3/4"

Summary of Well Data (Cont'd)

Conductor Pipe: Ran new 20" conductor pipe, landed at 78' K.B.
Cemented with 100 sacks Fondu cement.
Finished cementing at 12:00 p.m. April 22, 1972

Surface Casing: Ran 9 5/8" (724.91') Grade J-55, 36#, Rge. 3, ST & C, 8rd,
New Mannesmann Casing. Landed at 704' K.B.
Cemented with 350 sacks of Fondu Cement.
Displaced plug with water.
Plug down at 12:04 p.m. April 29, 1972

Representative for Operator: T.A.D. Haddow, P.Geol.

Representative for Contractor: H. Martinoff

SECTION II - GEOLOGICAL SUMMARYFORMATION TOPS

<u>Formation</u>	<u>Sample Depth</u>	<u>E-Log Depth</u>	K.B. 418' <u>E-Log Sub-sea Depth</u>
Devonian			
Hare Indian	30'	17'	+ 401'
Hume	125'	98'	+ 320'
Gossage (Bear Rock)	350'	347'	+ 71'
Sil - Ord Ronning	2120'	2106'	-1688'
Cambrian	5675'	5665'	-5247'
Salt	5850'	5842'	-5424'
Base Salt	6084'	6087'	-5669'
Proterozoic	6420'	6428'	-6010'
Total Depth	6961'	6944'	-6526'

Candel Mobil et al Iroquois I-11

Sample Descriptions

K.B. 418'

<u>Interval</u>	<u>Lithology</u>
Surface - 30'	<u>Glacial drift</u> - unconsolidated sand, granules, pebbles and cobbles <u>Hare Indian 30'</u> (E-Log 17')
30 - 40'	<u>Shale</u> - grey, fissile, micromicaceous, scattered black plant spores.
40 - 80'	<u>Shale</u> - medium grey, hard, fissile, micromicaceous, slightly bituminous in part, scattered, flecks of carbonaceous material (plant spores).
80 - 90'	<u>Shale</u> - dark grey to black, fissile, micromicaceous, bituminous, rare laminae of calcareous siltstone.
90 - 110'	<u>Shale</u> - as above, scattered plant remains and plant spores, trace of scattered pyrite.
110 - 120'	<u>Shale</u> - dark grey to black, brittle, micromicaceous, bituminous for the most part, scattered plant remains and spores, scattered fossils, calcareous in part - limy streaks. <u>Hume 125'</u> (E-Log 98')
120 - 130'	<u>Shale</u> - as above <u>Limestone</u> - grey - greenish to brownish in part, microcrystalline, very fine to fine crystalline in part, dense, silty, argillaceous, thin interbedded grey-calcareous shale, some dolomitic streaks - brownish grey, microcrystalline dense, abundant fossils - ostracods, brachiopods, bryozoa.
130 - 140'	<u>Shale</u> - medium grey, hard, micromicaceous, calcareous. <u>Limestone</u> - grey - greenish to brownish in part, microcrystalline to very fine crystalline, dense, bioclastic - micritic in part, fossiliferous, scattered fractures filled with coarse calcite crystals.
140 - 150'	<u>Limestone</u> - medium brownish to greenish grey, microcrystalline, some very fine to fine crystalline, bioclastic, peletoid in part, micritic in part, dense, argillaceous, some thin interbeds of grey calcareous shale, some cherty streaks, scattered fractures filled with crystalline calcite, fossiliferous, scattered pyrite.

- 150 - 160' Limestone - as above
Shale - medium grey, hard, micromicaceous, calcareous, pyritic in part.
- 160 - 170' Limestone - medium brownish to greenish grey, microcrystalline to very fine crystalline, bioclastic, dense, abundant fossils - brachiopods, ostracods, crinoids, some interbedded shale - medium grey, hard, micromicaceous, calcareous.
- 170 - 210' Limestone - medium brownish to greenish grey, microcrystalline to very fine crystalline, dense, argillaceous, fossiliferous.
Shale - medium grey, micromicaceous, calcareous.
- 210 - 220' Limestone - medium brownish to greenish grey, microcrystalline to very fine crystalline, bioclastic, micritic in part, dense, argillaceous, streaks, some interbedded grey calcareous shale, fossiliferous.
- 220 - 250' Limestone - medium brownish to greenish grey, microcrystalline to fine crystalline, bioclastic, micritic in part, dense, argillaceous, shaly, fossiliferous, scattered fractures filled with dog tooth spar.
- 250 - 270' Limestone - as above.
Shale - medium grey, fissile to blocky, micromicaceous, calcareous.
- 270 - 300' Limestone - greyish brown - some greenish to brownish grey, microcrystalline to fine crystalline, fragmental, micritic in part, dense, argillaceous, fossiliferous, some partings of dark grey calcareous shale and thin interbeds of medium grey calcareous shale, some scattered fractures filled with crystalline calcite.
- 300 - 350' Limestone - brownish grey, microcrystalline to very fine crystalline, micritic, dense, argillaceous, some partings of dark grey calcareous shale, some scattered pyrite, scattered fossils - brachiopods, crinoids, bryozoa.
- Gossage 350' (E-Log 347')
- 350 - 370' Limestone - light brownish grey, microcrystalline to fine crystalline, oolitic, dense, slightly argillaceous, some scattered fractures filled with crystalline calcite, rare scattered small vugs filled with crystalline calcite.
- 370 - 390' Limestone - as above and limestone - brownish to greenish grey, cryptocrystalline, micritic, dense, some scattered hairline fractures, some dolomitization along the fractures.
- 390 - 420' Limestone - brownish grey, microcrystalline, micritic, dense, argillaceous, some scattered ostracods, some scattered small patches and streaks of black carbonaceous material.
- 420 - 430' Limestone - medium dark brownish grey, cryptocrystalline to microcrystalline, micritic, dense, argillaceous, some partings of dark grey shale.

- 430 - 440' Limestone - greyish brown, microcrystalline to fine crystalline, fragmental - micritic in part, dense, argillaceous, scattered ostracods.
- 440 - 470' Limestone - light greyish brown, microcrystalline to fine crystalline - some bands of cryptocrystalline, fragmental, - organic in part, micritic in part, dense, argillaceous, some algal material, scattered ostracods, some partings of black bituminous shale.
- 470 - 480' Limestone - medium to dark greyish brown, microcrystalline to fine crystalline, micritic in part - fragmental, pelletoid and oolitic in part, dense, argillaceous, scattered stylolites some scattered partings of black bituminous shale, ostracods.
- 480 - 490' Limestone - light greyish brown, microcrystalline to fine crystalline, bioclastic, dense, fossiliferous - ostracods, brachiopods, rare corals.
- 490 - 510' Limestone - grey brown, cryptocrystalline to very fine crystalline, micritic, dense, scattered brachiopods, some scattered fine fractures filled with calcite.
- 510 - 520' Limestone - as above - some scattered hairline fractures, some streaks of shale - bluish grey, blocky, micromicaceous, bentonitic, scattered pyrite.
- 520 - 530' Limestone - light brownish grey, microcrystalline to fine crystalline, fragmental, dense, dolomitic, argillaceous, fossiliferous - brachiopods, ostracods.
- 530 - 540' Limestone - medium dark grey, microcrystalline to very fine crystalline, algal, dense, argillaceous, scattered ostracods, partings of black bituminous shale.
- 540 - 550' Limestone - light brownish grey, microcrystalline to fine crystalline, fragmental, dense, argillaceous, scattered ostracods, some scattered corals.
- 550 - 590' Limestone - brownish grey - some greenish streaks, cryptocrystalline to microcrystalline, micritic, dense, argillaceous.
- 590 - 600' Limestone - medium greyish brown, microcrystalline to fine crystalline, fragmental, dense, argillaceous, some partings of black bituminous shale. Trace of light greenish grey waxy shale, some scattered gastropods and brachiopods.
- 600 - 630' Limestone - as above - light to medium greyish brown, micritic in part.
- 630 - 640' Limestone - as above and limestone - brownish grey, cryptocrystalline, micritic, dense.

- 640 - 650' Limestone - greyish brown, cryptocrystalline to very fine crystalline, micritic, dense, argillaceous, scattered hairline and fine fractures - filled with calcite, a few scattered fossils.
- 650 - 680' Limestone - as above - few fragmental streaks - slightly dolomitic, a few streaks of dark grey shale and bluish grey bentonitic shale.
- 680 - 690' Limestone - as above - few fragmental streaks - dolomitic in part with dead oil stain.
- 690 - 700' Limestone - brownish grey, microcrystalline to very fine crystalline, fragmental - micritic in part, dense, argillaceous, some scattered ostracods.
- 700 - 720' Limestone - medium greyish brown - dark streaks, microcrystalline to very fine crystalline, fragmental in part, micritic in part, dense, argillaceous, partings of dark grey shale and thin interbeds of grey calcareous shale, scattered ostracods.
- 720 - 740' Limestone - brownish grey, microcrystalline to very fine crystalline, micritic, fragmental in part, dense, slightly argillaceous, some thin streaks of grey calcareous shale.
- 740 - 750' Limestone - as above and limestone - brownish grey, cryptocrystalline to microcrystalline, micritic, dense, argillaceous, some laminae of shale - bluish grey, blocky, finely disseminated pyrite.
- 750 - 770' Limestone - greyish brown, microcrystalline to very fine crystalline, fragmental in part, micritic in part, dense, argillaceous, few scattered fractures filled with crystalline calcite, some scattered ostracods.
- 770 - 790' Limestone - greyish brown, microcrystalline to very fine crystalline, fragmental, dense, argillaceous, some partings of black bituminous shale and bluish grey shale with finely disseminated pyrite.
- 790 - 800' Limestone - as above, partings of grey calcareous shale.
- 800 - 810' Limestone - greyish brown, cryptocrystalline to microcrystalline, micritic, argillaceous, calcite crystals infilling some fine scattered fractures and rare small vugs.
- 810 - 830' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic, dense, argillaceous, some interbedded grey calcareous shale, some scattered brachiopods.

- 830 - 840' Limestone - greyish brown, microcrystalline to fine crystalline, micritic, organic in part, fragmental in part, dense, argillaceous, pyritic in part, some thin interbedded grey calcareous shale and partings of bluish grey shale - fossiliferous - coral, algae, brachiopods, ostracods.
- 840 - 850' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic, algal in part, dense, argillaceous, some interbedded grey calcareous shale, pyritic in part, some scattered crinoids and brachiopods.
- 850 - 860' Shale - greenish grey, hard, micromicaceous, very calcareous, finely disseminated pyrite, some scattered limestone pellets.
Limestone - greyish brown, cryptocrystalline to microcrystalline, micritic, dense, argillaceous.
- 860 - 870' Limestone - greyish brown, very fine crystalline, micritic - fragmental in part, dense, argillaceous, some interbedded shale as above.
- 870 - 910' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic, dense, argillaceous (trace of stromatoporoids at 890').
- 910 - 920' Limestone - as above, some streaks of very light grey chalky limestone, some thin interbedded dolomite (5%) - greyish brown very fine crystalline, chalky in part, slight intercrystalline porosity - non effective, slightly calcitic.
- 920 - 940' Limestone - 75% and dolomite 25% as above.
- 940 - 950' Limestone - greyish brown, microcrystalline to very fine crystalline, micritic - fragmental in part, some cream chalky streaks, some interbedded dolomite with slight intercrystalline porosity - noneffective, some scattered coarse crystals of secondary dolomite.
- 950 - 960' Limestone - greyish brown microcrystalline to very fine crystalline with streaks of very light grey to cream - chalky, micritic; fragmental in part, some interbedded dolomite - greyish brown, very fine crystalline, earthy in part, slight intercrystalline porosity - noneffective.
- 960 - 980' Dolomite - greyish brown, very fine crystalline, slightly calcitic in part, slight intercrystalline porosity.
- 980 - 990' Limestone - cream to greyish brown, microcrystalline to very fine crystalline - chalky in part, micritic in part, fragmental in part, dense, slightly argillaceous in part, some streaks and thin interbedded dolomite as above - slight intercrystalline porosity - noneffective.

- 990 - 1010' Limestone - cream to greyish brown, microcrystalline to very fine crystalline - chalky in part, fragmental, tight, argillaceous streaks, slightly dolomitic - earthy in part.
- 1010 - 1030' Limestone - as above - micritic and fragmental.
- 1030 - 1050' Limestone - as above - micritic and fragmental, trace of milky chert.
- 1050 - 1060' Limestone - very light greyish brown - cream in part, microcrystalline, fragmental, micritic in part, some oolites, dense.
- 1060 - 1080' Limestone - very light to light greyish brown, microcrystalline to very fine crystalline - as above.
- 1080 - 1130' Limestone - very light greyish brown - cream in part, microcrystalline to very fine crystalline, fragmental and micritic, dense.
- 1130 - 1150' Limestone - light greyish brown, microcrystalline to very fine crystalline, fragmental and micritic, dolomitic streaks, tight.
- 1150 - 1160' Limestone - light greyish brown, microcrystalline to very fine crystalline, fragmental, micritic in part, dense.
Dolomite - greyish brown, very fine crystalline, slight intercrystalline porosity - noneffective.
- 1160 - 1170' Dolomite - greyish brown, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous.
- 1170 - 1180' Dolomite - as above.
Limestone - brownish grey, microcrystalline to very fine crystalline, fragmental, micritic in part, dense, argillaceous.
- 1180 - 1200' Limestone - greyish brown, microcrystalline to very fine crystalline, fragmental, micritic in part, pelletoidal in part, dolomitic streaks, tight, argillaceous.
- 1200 - 1230' Dolomite - greyish brown, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous, a few scattered fine fractures filled with calcite.
- 1230 - 1240' Dolomite - very light greyish brown - some darker streaks, microcrystalline to very fine crystalline, slight intercrystalline porosity, some argillaceous streaks, some streaks of limestone as above.
- 1240 - 1250' Dolomite - brown - greyish, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous, trace of quartz crystals.

- 1250 - 1260' Dolomite - greyish brown, microcrystalline to very fine crystalline, slight to poor intercrystalline, pinpoint and scattered small vuggy porosity, some scattered white coarse secondary dolomite crystals, argillaceous.
- 1260 - 1280' Dolomite - light greyish brown, microcrystalline to very fine crystalline, slight to poor intercrystalline, pinpoint and scattered small vuggy porosity, some scattered white coarse secondary dolomite crystals, slightly argillaceous in part.
- 1280 - 1360' Dolomite - greyish brown - some light streaks, microcrystalline to very fine crystalline, slight intercrystalline porosity, argillaceous.
- 1360 - 1380' Dolomite - very light greyish brown - some dark streaks - very fine to fine crystalline, slight to poor intercrystalline porosity.
- 1380 - 1400' Dolomite - greyish brown, microcrystalline to fine crystalline, slight intercrystalline porosity, argillaceous, some scattered fractures filled with crystalline calcite.
- 1400 - 1410' Dolomite - greyish brown to medium dark greyish brown, very fine to fine crystalline, slight intercrystalline porosity, argillaceous, some scattered partings of black bituminous shale, trace of quartz crystals.
- 1410 - 1420' Dolomite - greyish brown, very fine to fine crystalline, slight intercrystalline porosity, argillaceous, scattered fractures filled with crystalline calcite.
- 1420 - 1450' Dolomite - medium greyish brown, very fine to fine crystalline, slight to poor intercrystalline, pinpoint and small vuggy porosity, argillaceous, scattered fractures filled with crystalline calcite.
- 1450 - 1480' Dolomite - light greyish brown - some dark streaks, very fine to fine crystalline, poor intercrystalline & scattered small vuggy porosity, slightly argillaceous in part.
- 1480 - 1510' Dolomite - greyish brown, very fine to fine crystalline, slight to poor intercrystalline porosity, argillaceous.
- 1510 - 1540' Dolomite - light brownish grey - as above.
- 1540 - 1560' Dolomite - brownish grey - some dark streaks, very fine to fine crystalline, slight to poor intercrystalline porosity argillaceous.
- 1560 - 1580' Dolomite - as above, trace of quartz crystals, some calcite crystals (infilling fractures).
- 1580 - 1590' Dolomite - as above - marked increase in quartz crystals & calcite crystals.

- 1590 - 1600' Dolomite - brownish grey - some dark streaks, very fine to fine crystalline, slight to poor intercrystalline porosity, argillaceous.
- 1600 - 1610' Dolomite - light to medium dark greyish brown, microcrystalline to very fine crystalline, slight streaky intercrystalline porosity, streaky argillaceous content, few scattered quartz crystals.
- 1610 - 1620' Dolomite - light greyish brown, microcrystalline to very fine crystalline, streaky slight intercrystalline porosity, slightly argillaceous.
- 1620 - 1690' Dolomite - greyish brown, microcrystalline to very fine crystalline, streaky, slight intercrystalline porosity, argillaceous, few scattered quartz crystals, some scattered calcite crystals.
- 1690 - 1700' Dolomite - greyish brown - light streaks, microcrystalline to very fine crystalline, streaky slight intercrystalline porosity - noneffective, few quartz crystals and calcite crystals.
- 1700 - 1730' Dolomite - light greyish brown, microcrystalline to very fine crystalline, tight, silty, few quartz crystals and calcite crystals.
- 1730 - 1790' Dolomite - buff, some dark streaks in part, fine to medium crystalline, dense, silty, abundant, quartz crystals.
- 1790 - 1820' Dolomite - buff, microcrystalline to very fine crystalline, dense, silty (samples powdered - difficult to interpret).
- 1820 - 1910' Dolomite - medium grey, microcrystalline to very fine crystalline, dense, argillaceous, trace of quartz crystals, trace of greenish grey shale partings - silty.
- 1910 - 1940' Dolomite - light grey, microcrystalline, dense, silty.
- 1940 - 1960' Dolomite - light grey, microcrystalline to very fine crystalline, tight, silty - very fine, rare greenish grey shaly streaks.
- 1960 - 1990' Dolomite - grey, microcrystalline, tight, some argillaceous streaks, silty, some partings of dark grey shale.
- 1990 - 2010' Dolomite - brownish grey - some dark streaks, microcrystalline to very fine crystalline, dense, argillaceous, silty, rare partings of black bituminous shale, some scattered fractures filled with crystalline calcite.
- 2010 - 2020' Dolomite - dark brownish grey - some light streaks, microcrystalline, tight very argillaceous, silty, some partings of black bituminous shale.

- 2020 - 2030' Dolomite - grey, microcrystalline, tight, argillaceous, silty, some partings of greenish grey shale.
- 2030 - 2040' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline - some fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty, some partings of dark grey shale and black bituminous shale.
- 2040 - 2050' Dolomite - light grey - slightly greenish to brownish cast, microcrystalline to very fine crystalline, tight, silty.
- 2050 - 2070' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline, tight, very argillaceous, slightly silty, scattered fractures filled with crystalline calcite, partings of dark grey shale.
- 2070 - 2090' Dolomite - medium grey - slightly brownish, microcrystalline, dense, argillaceous, silty, scattered fractures with calcite.
- 2090 - 2100' Dolomite - brownish grey - some darker streaks, microcrystalline to fine crystalline, dense, argillaceous in part, silty, scattered fractures with calcite.
- 2100 - 2120' Dolomite - grey - slightly brownish - some light streaks, microcrystalline to very fine crystalline, dense, hard, argillaceous, silty, some scattered fractures filled with crystalline calcite.
- Ronning 2120' (E-Log 2106')
- 2120 - 2140' Dolomite - greyish brown - some light streaks, microcrystalline to fine crystalline - some light colored streaks are fine to medium crystalline, tight for the most part, some streaky slight intercrystalline porosity, argillaceous, silty, some streaks of greyish green shale, scattered fractures filled with crystalline calcite - trace of quartz crystals.
- 2140 - 2150' Dolomite - buff, microcrystalline to very fine crystalline slight intercrystalline porosity, silty, some streaks of greyish green shale, scattered fractures filled with calcite.
- 2150 - 2160' Dolomite - light greyish brown, microcrystalline to very fine crystalline, streaky, slight intercrystalline porosity, argillaceous, silty, trace of quartz crystals.
- 2160 - 2190' Dolomite - as above - some light colored streaks - very fine to fine crystalline, streaky intercrystalline porosity, scattered fractures filled with crystalline calcite.

- 2190 - 2220' Dolomite - very light buff, fine to medium crystalline, poor intercrystalline and vuggy porosity - abundant loose coarse dolomite rhombs - scattered quartz crystals, slightly silty and argillaceous.
- 2220 - 2230' Dolomite - greyish brown, fine to medium crystalline, slight to poor intercrystalline porosity, argillaceous, scattered quartz crystals.
- 2230 - 2240' Dolomite - light greyish brown - some dark streaks, fine to medium crystalline, poor intercrystalline and vuggy porosity - scattered dolomite rhombs, scattered quartz crystals, slightly argillaceous, silty.
- 2240 - 2250' Dolomite - very light buff - fine to medium crystalline, poor intercrystalline and vuggy porosity, scattered dolomite rhombs and quartz crystals.
- 2250 - 2280' Dolomite - very light greyish brown - fine to medium crystalline, poor intercrystalline & vuggy porosity, scattered dolomitic rhombs and quartz crystals, slightly silty, scattered fractures filled with crystalline calcite.
- 2280 - 2300' Dolomite - medium dark to dark greyish brown, very fine to medium crystalline, slight intercrystalline and vuggy porosity, scattered dolomite rhombs and quartz crystals, argillaceous and silty.
- 2300 - 2310' Dolomite - medium greyish brown, fine to medium crystalline - euhedral, slight scattered vuggy porosity, argillaceous, silty, scattered dolomite rhombs, trace of quartz crystals.
- 2310 - 2320' Dolomite - light to medium greyish brown - as above.
- 2320 - 2380' Dolomite - greyish brown, very fine to fine crystalline, streaky, slight intercrystalline porosity, argillaceous, silty, scattered quartz crystals.
- 2380 - 2390' Dolomite - very light buff, fine to medium crystalline, slight intercrystalline porosity, scattered vugs - some coarse dolomite rhombs.
- 2390 - 2410' Dolomite - very light buff to very light brown, very fine to medium crystalline - euhedral, slight vuggy porosity - scattered coarse dolomite rhombs, streaky slight intercrystalline porosity.
- 2410 - 2440' Dolomite - medium brownish grey - some light streaks, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty, scattered fractures filled with white coarse crystalline secondary dolomite. Some fractures filled with crystalline calcite.

- 2440 - 2460' Dolomite - medium to dark brownish grey, very fine to fine crystalline, dense, argillaceous, silty, some scattered loose dolomite rhombs (infilling fractures?)
- 2460 - 2480' Dolomite - brownish grey - some dark streaks, as above.
- 2480 - 2490' Dolomite - brownish grey, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty.
- 2490 - 2500' Dolomite - greyish brown, very fine to fine crystalline, dense, argillaceous, silty.
- 2500 - 2510' Dolomite - light greyish brown, very fine to fine crystalline, slight intercrystalline porosity, slightly argillaceous, silty, some secondary dolomite
- 2510 - 2540' Dolomite - greyish brown, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty.
- 2540 - 2580' Dolomite - light greyish brown - as above, slight intercrystalline and scattered vuggy porosity, argillaceous, silty, scattered white coarse crystals of dolomite (druses).
- 2580 - 2590' Dolomite - very light buff, very fine to medium crystalline, slight intercrystalline porosity, slightly silty.
- 2590 - 2610' Dolomite - greyish brown, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty.
- 2610 - 2620' Dolomite - greyish brown - some dark streaks, very fine crystalline, dense, argillaceous, silty.
- 2620 - 2700' Dolomite - greyish brown, very fine to fine crystalline, streaky slight intercrystalline and vuggy porosity - scattered dolomite rhombs, silty, slightly argillaceous, some scattered fractures filled with secondary dolomite.
- 2700 - 2720' Dolomite - greyish brown, microcrystalline to very fine crystalline - streaks of microsucrose with streaky slight intercrystalline porosity, argillaceous, silty.
- 2720 - 2740' Dolomite - brownish grey, microcrystalline to very fine crystalline, dense - some light buff microsucrosic streaks with slight intercrystalline porosity - noneffective, silty and sandy, abundant calcite crystals and some dolomite rhombs infilling fractures, trace of quartz crystals.
- 2740 - 2780' Dolomite - light buff - microsucrose and light greyish brown - microcrystalline to very fine crystalline; streaky slight intercrystalline porosity - noneffective, silty, argillaceous, some scattered calcite crystals, trace of quartz crystals and dolomite rhombs.

- 2780 - 2790' Dolomite - buff, microcrystalline to very fine crystalline, dense, silty.
- 2790 - 2800' Dolomite - light greyish brown, microcrystalline to very fine crystalline, tight, silty, some scattered inclusions of calcite crystals, rare quartz crystals.
- 2800 - 2850' Dolomite - greyish brown - light streaks, microcrystalline to fine crystalline, tight, silty, some scattered inclusions of calcite crystals.
- 2850 - 2880' Dolomite - brownish grey, microcrystalline to fine crystalline, dense for the most part - scattered blind vugs with coarse dolomite druses, silty, slightly argillaceous, some scattered fractures filled with secondary dolomite.
- 2880 - 2890' Dolomite - brownish grey, microcrystalline to fine crystalline, dense - scattered vugs partially to completely infilled with secondary dolomite, silty, argillaceous.
- 2890 - 2910' Dolomite - buff, microcrystalline to fine crystalline, slight intercrystalline porosity, rare drusy vugs, rare quartz crystals, some loose calcite and secondary dolomite crystals, argillaceous, silty (very fine).
- 2910 - 2920' Dolomite - greyish brown, microcrystalline to fine crystalline, dense, rare scattered vugs, argillaceous, silty, loose calcite crystals (fractures?).
- 2920 - 2940' Dolomite - as above slight scattered vuggy porosity - secondary dolomite druses.
- 2940 - 2950' Dolomite - as above, some light colored streaks and patches, slight vuggy porosity
- 2950 - 2970' Dolomite - greyish brown, microcrystalline to fine crystalline - sucrosic in part, streaky slight intercrystalline and scattered vuggy porosity, argillaceous, silty, scattered fractures filled with crystalline calcite, secondary dolomite druses.
- 2970 - 2990' Dolomite - as above, numerous fractures indicated by abundant loose white coarse calcite crystals, streaky slight intercrystalline and vuggy porosity, dolomite druses.
- 2990 - 3000' Dolomite - greyish brown, microcrystalline to fine crystalline, slight intercrystalline and vuggy porosity, coarse secondary dolomite rhombs partially to completely infilling scattered vugs, trace of quartz crystals, trace of milky chert, argillaceous, silty, some scattered fractures infilled with calcite.
- 3000 - 3010' Dolomite - light greyish brown, microcrystalline to fine crystalline, dense, some scattered fractures filled with calcite.
- 3010 - 3020' Dolomite - light buff, microcrystalline to fine crystalline, dense, silty, some scattered fractures filled with calcite.

- 3020 - 3050' Dolomite - light brownish and greenish grey, microcrystalline to fine crystalline, dense, fractures filled with calcite, a few vugs with druses of secondary dolomite, some finely disseminated pyrite.
- 3050 - 3060' Dolomite - very light greyish brown to buff, microcrystalline to fine & some medium crystalline, slight scattered vuggy porosity - druses of secondary dolomite, some fractures filled with calcite, trace of pyrobitumen.
- 3060 - 3100' Dolomite - light greyish brown, very fine to coarse crystalline, slight to poor intercrystalline and vuggy porosity, scattered slightly argillaceous streaks, some scattered pyrite.
- 3100 - 3120' Dolomite - very light to light grey - brownish in part, microcrystalline to medium crystalline, dense, a few fractures filled with calcite.
- 3120 - 3140' Dolomite - light greyish brown, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity, loose dolomite rhombs.
- 3140 - 3160' Dolomite - as above, very light buff in part, microcrystalline to coarse crystalline, a few streaks of medium dark brownish grey, very fine crystalline dolomite; a few slightly argillaceous streaks - some pyrite.
- 3160 - 3190' Dolomite - very light to light grey - brownish in part, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity, trace of green waxy shale, rare scattered glauconite.
- 3190 - 3210' Dolomite - very light grey, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity, milky & avery light bluish grey chert, trace of quartz crystals, some scattered pyrite.
- 3210 - 3230' Dolomite - very light to light brownish grey, microcrystalline to coarse crystalline, slight to poor intercrystalline and vuggy porosity, rare scattered glauconite, silty.
- 3230 - 3240' Dolomite - light grey, very fine to coarse crystalline, slight intercrystalline and small vuggy porosity - very good cavernous porosity (kelly dropped five feet) trace of glauconite.
- 3240 - 3250' Dolomite - light grey - brownish in part, very fine to coarse crystalline, slight to poor intercrystalline and vuggy porosity, scattered pyrite.
- 3250 - 3260' Dolomite - as above, some dark streaks of microcrystalline to very fine crystalline dolomite - silty and argillaceous, some quartz crystals.

- 3260 - 3280' Dolomite - light grey - brownish in part, very fine to coarse crystalline, slight intercrystalline and vuggy porosity, siliceous in part, very light grey chert, some quartz crystals, trace of bright green shale, scattered pyrite.
- 3280 - 3290' Dolomite - as above, abundant very light grey to milky chert, quartz crystals.
- 3290 - 3400' Dolomite - light greyish brown, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity - some cavernous porosity at 3380', light grey chert, siliceous in part, quartz crystals, some scattered pyrite.
- 3400 - 3410' Dolomite - as above (trip sample)
- 3410 - 3440' Dolomite - light greyish brown, very fine to coarse crystalline, scattered slight intercrystalline and vuggy porosity, cherty - light grey.
- 3440 - 3520' Dolomite - buff to light greyish brown, as above, a few quartz crystals, cherty.
- 3520 - 3560' Dolomite - buff, very fine crystalline to coarse crystalline, scattered slight intercrystalline and vuggy porosity, cherty.
- 3560 - 3570' Dolomite - as above and dolomite - medium to dark grey - slightly brownish, microcrystalline to very fine crystalline, dense, argillaceous, streaks of dark grey to black chert, some streaks of sandy dolomite - light grey, very fine crystalline, dense, very silty to sandy (very fine grained) - grading to a dolomitic sandstone, finely disseminated pyrite.
- 3570 - 3580' Dolomite - medium to dark grey with light grey silty to sandy streaks as above.
- 3580 - 3630' Dolomite - light buff to light greyish brown, very fine to medium crystalline, streaky, slight intercrystalline and vuggy porosity, silty, very light grey chert, some quartz crystals.
- 3630 - 3650' Dolomite - light buff, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, silty, some light grey chert, some quartz crystals.
- 3650 - 3670' Dolomite - light buff, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, silty.
- 3670 - 3690' Dolomite - as above, trace of light grey chert & quartz crystals.
- 3690 - 3700' Dolomite - as above, quartz crystals and very light grey chert - faint outline of oolites.
- 3700 - 3710' Dolomite - light buff to light greyish brown, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, quartz crystals, trace of very light grey chert.

- 3710 - 3750' Dolomite - very light buff, as above.
- 3750 - 3790' Dolomite - very light buff - brownish in part, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, quartz crystals.
- 3790 - 3800' Dolomite - very light buff, trace of reddish streaks, microcrystalline to medium crystalline, slight to poor intercrystalline porosity, silty, siliceous in part, very light grey to milky chert, quartz crystals.
- 3800 - 3820' Dolomite - very light grey and buff, very fine to medium crystalline, streaky slight intercrystalline porosity, silty, some quartz crystals, trace of very light grey chert.
- 3820 - 3850' Dolomite - very light buff - brownish in part, microcrystalline to coarse crystalline, streaky, slight intercrystalline and vuggy porosity, silty, siliceous in part, some very light grey chert & rare streaks of medium to dark grey chert, some quartz crystals.
- 3850 - 3860' Dolomite - very light grey - brownish in part, very fine to medium crystalline dense, some streaks - greyish brown - microcrystalline to very fine crystalline, argillaceous, silty, tight; trace of milky and medium to dark grey chert - banded in part.
- 3860 - 3880' Dolomite - as above, some very light grey chert, some quartz crystals.
- 3880 - 3890' Dolomite - very light grey - slightly brownish in part, microcrystalline to medium crystalline, dense, silty, siliceous in part, some chert - light to very light grey, quartz crystals.
- 3890 - 3920' Dolomite - very light grey - slightly brownish in part, microcrystalline to medium crystalline, dense, silty, very cherty - very light grey (faint outline of oolites) siliceous in part, quartz crystals, trace of gypsum crystals.
- 3920 - 3950' Dolomite - as above - chert becoming slightly darker in color.
- 3950 - 3970' Dolomite - light greyish brown, microcrystalline to medium crystalline, dense, silty, abundant very light grey to very light greyish brown oolitic chert, some loose calcite crystals.
- 3970 - 3990' Dolomite - very light greyish brown, microcrystalline to medium crystalline, dense, silty, very light grey chert, some quartz crystals.
- 3990 - 4020' Dolomite - very light buff, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, some light colored chert - oolitic in part, quartz crystals.

- 4020 - 4040' Dolomite - very light buff, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, some light colored chert, some quartz crystals.
- 4040 - 4090' Dolomite - very light buff, microcrystalline to medium crystalline, slight intercrystalline porosity - dense streaks, some very light grey chert, some quartz crystals.
- 4090 - 4120' Dolomite - very light buff to very light greyish brown, microcrystalline to medium crystalline, some medium greyish brownish streaks - microcrystalline to very fine crystalline, slightly argillaceous, silty; streaky - slight intercrystalline porosity, slightly cherty - oolitic in part, some quartz crystals.
- 4120 - 4180' Dolomite - very light to medium greyish brown, microcrystalline to fine crystalline, dense, silty, argillaceous streaks, some very light grey chert, some quartz crystals, some loose calcite crystals.
- 4180 - 4210' Dolomite - very light to medium greyish brown, microcrystalline to fine crystalline, dense, silty, argillaceous streaks, cherty - very light grey to dark grey, some loose calcite crystals, some quartz crystals.
- 4210 - 4230' Dolomite - as above - abundant quartz crystals, slight vuggy porosity.
- 4230 - 4280' Dolomite - very light to medium greyish brown, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, argillaceous streaks, quartz crystals, some cherty streaks - very light brownish grey to dark grey.
- 4280 - 4290' Dolomite - very light grey - slightly brownish - some dark streaks, microcrystalline to fine crystalline, dense, for the most part, some scattered small vugs, silty, quartz crystals.
- 4290 - 4300' Dolomite - brownish grey - light streaks, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, silty, argillaceous streaks, quartz crystals, some very light to dark grey chert.
- 4300 - 4370' Dolomite - grey - very light in part - slightly brownish, microcrystalline to fine crystalline, slight streaky intercrystalline porosity, silty, argillaceous in part, slightly cherty, few quartz crystals.
- 4370 - 4390' Dolomite - as above, few partings of dark grey shale.
- 4390 - 4430' Dolomite - very light buff, microcrystalline to medium crystalline, slight intercrystalline porosity, trace of scattered vugs, silty, pyritic in part, trace of light colored chert and quartz crystals.

- 4430 - 4490' Dolomite - very light to light grey, slightly brownish, some dark streaks, microcrystalline to coarse crystalline, streaky slight intercrystalline porosity, silty, slightly cherty, some scattered pyrite, some scattered partings of greyish green shale and dark grey shale - bituminous in part.
- 4490 - 4500' Dolomite - medium brownish grey - some light streaks microcrystalline to medium crystalline, tight, silty, argillaceous, rare light colored chert & quartz crystals, scattered pyrite.
- 4500 - 4510' Dolomite - very light grey - brownish - some dark streaks microcrystalline to medium crystalline, slight intercrystalline porosity, silty, argillaceous streaks, some quartz crystals, scattered pyrite, trace of shale partings.
- 4510 - 4540' Dolomite - very light greyish brown, very fine to coarse crystalline, streaky slight intercrystalline and vuggy porosity, slightly cherty - oolitic in part, some quartz crystals.
- 4540 - 4550' Dolomite - as above - some darker colored streaks.
- 4550 - 4570' Dolomite - greyish brown - microcrystalline to fine crystalline, tight, argillaceous, silty, some partings of dark grey shale, some scattered pyrite.
- 4570 - 4580' Dolomite - brownish grey, microcrystalline to fine crystalline, tight, silty.
- 4580 - 4650' Dolomite - greyish brown, microcrystalline to fine crystalline, tight, silty, argillaceous, some partings of dark grey and black bituminous shale.
- 4650 - 4670' Dolomite - light brownish grey, microcrystalline to fine crystalline, tight, silty, slightly argillaceous.
- 4670 - 4720' Dolomite - light to medium greyish brown, microcrystalline to fine crystalline, tight, silty, argillaceous, some scattered fractures filled with crystalline calcite, scattered shale partings.

- 4720 - 4740' Dolomite - very light grey to greyish brown - rare reddish streaks, microcrystalline to coarse crystalline, slight vuggy and intercrystalline porosity, silty, argillaceous streaks, some dark grey shale partings - some dark reddish coloration, trace of light grey chert and quartz crystals.
- 4740 - 4770' Dolomite - greyish brown, microcrystalline to fine crystalline, tight, silty, argillaceous, some partings of black bituminous shale and dark grey shale.
- 4770 - 4780' Dolomite - light to medium greyish brown - some streaks of very light grey, microcrystalline to fine crystalline, streaky - slight intercrystalline porosity, shale partings - dark grey - some rare purple streaks.
- 4780 - 4800' Dolomite - greyish brown, microcrystalline to fine crystalline tight, silty, argillaceous.
- 4800 - 4810 Dolomite - as above - some dolomite - very light grey to brownish grey, microcrystalline to coarse crystalline, slight intercrystalline and vuggy porosity - dense streaks, silty, argillaceous in part, rare quartz crystals.
- 4810 - 4830' Dolomite - very light grey, microcrystalline to very fine crystalline, streaky slight intercrystalline porosity silty (very fine).
- 4830 - 4840' Dolomite - very light to medium greyish brown, microcrystalline to medium crystalline, streaky slight intercrystalline porosity, silty, argillaceous in part.
- 4840 - 4850' Dolomite - very light grey - slightly brownish - some dark streaks, microcrystalline to medium crystalline, slight intercrystalline porosity, slightly argillaceous in part.
- 4850 - 4860' Dolomite - as above - increase in darker streaks, streaky, slight intercrystalline porosity, argillaceous in part.
- 4860 - 4880' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline, tight, argillaceous, silty, some partings of dark grey shale.
- 4880 - 4920' Dolomite - light to medium greyish brown, microcrystalline to medium crystalline, streaky - slight intercrystalline porosity, silty, argillaceous in part, partings of dark grey shale.
- 4920 - 4930' Dolomite - greyish brown - some dark streaks, microcrystalline to fine crystalline, tight, silty, argillaceous.
- 4930 - 4980' Dolomite - light to medium greyish brown, microcrystalline to medium crystalline, streaky - slight intercrystalline porosity, silty, argillaceous in part, scattered partings of dark grey shale.

- 4980 - 5010' Dolomite - as above, microcrystalline to fine crystalline.
- 5010 - 5030' Dolomite - very light buff, microcrystalline to fine crystalline, slight intercrystalline porosity, some scattered argillaceous streaks.
- 5030 - 5050' Dolomite - as above - some greyish brown streaks, a band of slightly greenish grey dolomite - microcrystalline to very fine crystalline, silty, dense.
- 5050 - 5060' Dolomite - very light grey - brownish in part to greyish brown, microcrystalline to fine crystalline, streaky slight intercrystalline porosity, some silty and argillaceous streaks.
- 5060 - 5070' Dolomite - as above - partings of black bituminous shale.
- 5070 - 5110' Dolomite - very light grey to greyish brown, microcrystalline to fine crystalline, trace of slight intercrystalline porosity, silty and argillaceous streaks, trace of dark grey chert at 5090'
- 5110 - 5140' Dolomite - very light grey - brownish in part to light greyish brown, microcrystalline to very fine and some fine crystalline, tight, trace of very light grey to light brown chert at the top.
- 5140 - 5150' Dolomite - light to medium grey - some dark streaks - brownish in part, microcrystalline to fine crystalline, tight, silty and argillaceous, trace of very thin streaks of very light grey chert.
- 5150 - 5180' Dolomite - very light brownish grey to greyish brown, microcrystalline to very fine crystalline, tight, silty.
- 5180 - 5220' Dolomite - very light grey - slightly brownish in part, microcrystalline to very fine crystalline, dense, silty.
- 5220 - 5230' Dolomite - as above - greyish brown in part, some partings of dark grey shale.
- 5230 - 5240' Dolomite - greyish brown - very light in part - dark in part, microcrystalline to very fine crystalline, tight, silty, slightly argillaceous in part.
- 5240 - 5280' Dolomite - greyish brown, microcrystalline to fine crystalline, trace of slight intercrystalline porosity, silty, argillaceous.
- 5280 - 5300' Dolomite - very light buff - some greyish brown, microcrystalline to fine crystalline, trace of slight intercrystalline porosity, silty, some partings of black bituminous shale.
- 5300 - 5310' Dolomite - very light grey to greyish brown, microcrystalline to very fine crystalline, tight, silty, argillaceous streaks.

- 5310 - 5340' Dolomite - very light grey, very fine crystalline, slight intercrystalline porosity, silty.
- 5340 - 5350' Dolomite - medium to dark brownish grey, microcrystalline to very fine crystalline, tight, argillaceous, silty.
- 5350 - 5370' Dolomite - as above - some light brownish grey.
- 5370 - 5450' Dolomite - very light to medium grey - brownish in part, microcrystalline to very fine crystalline, dense, silty, some partings of black bituminous shale and dark grey shale.
- 5450 - 5480' Dolomite - light grey - grey, microcrystalline, dense, silty, some partings of greenish grey and black bituminous shale.
- 5480 - 5500' Dolomite - as above, some rare faint reddish streaks.
- 5500 - 5520' Dolomite - light to dark grey, brownish, microcrystalline to very fine crystalline, dense, silty, argillaceous streaks, scattered shale partings, trace of quartz crystals.
- 5520 - 5580' Dolomite - light to dark grey, microcrystalline to very fine crystalline, dense, few scattered blind vugs, banded in part, silty, argillaceous in part, trace of inclusions of gypsum, some partings of black bituminous shale.
- 5580 - 5590' Dolomite - medium to dark grey, microcrystalline to very fine crystalline, dense, silty, argillaceous, some thin interbeds of dark grey and greenish grey shale - hard, brittle, dolomitic.
- 5590 - 5620' Dolomite - light to medium grey - brownish in part, microcrystalline to very fine and some fine crystalline, dense, argillaceous, silty, some scattered pyrite, interbedded greenish grey dolomitic shale, trace of gypsum crystals.
- 5620 - 5630' Dolomite - as above, streaks of very light grey dolomite - microcrystalline to very fine crystalline - chalky in part.
- 5630 - 5640' Dolomite - light to medium greyish brown - rare reddish streaks, microcrystalline to very fine crystalline, dense, silty, argillaceous, some thin interbeds of greenish grey dolomitic shale.
- 5640 - 5650' Dolomite - as above; dolomite - light grey - reddish streaks, dense, argillaceous, trace of floating quartz grains.
Shale - greenish grey and maroon.
- 5650 - 5660' Dolomite - light brownish grey, microcrystalline, dense.
- 5660 - 5670' Dolomite - brownish grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, thin interbedded greenish grey shale.

Cambrian 5675' (E-Log 5665')

- 5670 - 5710' Dolomite - reddish and greenish grey, microcrystalline to very fine crystalline, dense, very silty, argillaceous
Shale - maroon and greyish green, hard, blocky, micromicaceous.
- 5710 - 5730' Dolomite - pink to red, and greenish grey, microcrystalline to very fine crystalline - chalky in part, silty, argillaceous a trace of anhydrite.
Shale - maroon and greyish green, blocky, micromicaceous.
- 5730 - 5740' Shale - maroon, fissile to blocky, micromicaceous, some streaks of dolomite.
- 5740 - 5760' Shale - maroon & greyish green, fissile to blocky, micromicaceous.
Dolomite - very light grey - pink & brownish in part tight, microcrystalline to very fine crystalline, silty, some sandy streaks, trace of quartzite.
- 5760 - 5780' Dolomite - grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, some sandy streaks.
Shale - maroon and green, micromicaceous.
- 5780 - 5800' Shale - greenish grey - some maroon streaks, fissile to blocky, micromicaceous, some streaks of dolomite.
- 5800 - 5820' Shale - as above
Dolomite - grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, trace of quartz crystals, trace of gypsum.
- 5820 - 5850' Dolomite - as above.
Shale - greenish grey & maroon, fissile to blocky, micromicaceous.

Salt 5850' (E-Log 5842')

- 5850 - 5890' Salt - with shaly streaks, thin interbeds and streaks of dolomite, some slightly brownish grey anhydrite (salt not recovered in samples)
- 5890 - 5910' Samples Missing - no recovery.
- 5910 - 5920' Dolomite - grey, microcrystalline to very fine crystalline, dense, pelletoid in part, silty, some streaks of maroon and greyish green shale.
Salt - (no recovery in samples)
- 5920 - 6080' Salt - (no recovery - except 6080' sample) thin interbeds and streaks of dolomite, shale laminae, minor anhydrite and gypsum.

Base of Salt 6084' (E-Log 6087')

- 6080 - 6090' Salt - (no recovery)
Dolomite - grey, microcrystalline, dense, earthy in part, silty some scattered salt casts.

- 6090 - 6100' Dolomite - grey - slightly brownish, microcrystalline - earthy for the most part, tight, argillaceous, silty, some scattered salt casts.
- 6100 - 6110' Shale - greyish green - fine white specks, fissile to blocky, micromicaceous, slightly dolomitic, some fine veins of gypsum.
- 6110 - 6120' Shale - medium grey - trace of white specks, brittle, micromicaceous, slightly dolomitic, some streaks of dolomite - light grey, microcrystalline to very fine crystalline, tight.
- 6120 - 6150' Shale - medium grey - some greyish green and reddish streaks, brittle, micromicaceous, slightly dolomitic, some streaks of dolomite - grey to brownish grey and pink to reddish grey, microcrystalline to very fine crystalline, tight - silty and sandy streaks.
- 6150 - 6170' Shale - with interbedded dolomite as above - ochre cast in part.
- 6170 - 6190' Shale - greenish and brownish grey, brittle, micromicaceous, some interbedded dolomite - light grey to greenish and reddish grey, very fine to fine crystalline, dense, silty and sandy streaks, trace of floating quartz grains.
- 6190 - 6210' Dolomite - medium to dark grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, shale streaks, very cherty - milky and brownish grey - oolitic in part, trace of quartzite, trace of gypsum crystals.
- 6210 - 6220' Dolomite - brownish grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, some shale streaks, some inclusions of anhydrite and gypsum (also infilling fine fractures).
- 6220 - 6270' Dolomite - medium grey, microcrystalline to fine crystalline, dense, very argillaceous, silty, shale streaks, pyritic in part, scattered blebs of anhydrite, few gypsum crystals, trace of salt casts.
- 6270 - 6280' Dolomite - as above
Shale - medium grey and greenish grey, fissile to blocky, micromicaceous, slightly dolomitic.
- 6280 - 6320' Dolomite - medium grey, microcrystalline to very fine and some fine crystalline, dense, very argillaceous, very shaly, silty, few scattered blebs of anhydrite, trace of gypsum.
- 6320 - 6330' Dolomite - as above - some lighter brownish streaks.
- 6330 - 6380' Dolomite - medium to dark grey, microcrystalline, dense, very argillaceous and silty, shaly streaks, scattered blebs of anhydrite, trace of salt casts.
- 6380 - 6390' Dolomite - medium grey - slight greenish cast, microcrystalline to very fine crystalline, dense, very argillaceous

- 6380 - 6390'
(cont'd) and silty, shaly, some anhydrite and gypsum.
- 6390 - 6410' Dolomite - grey, microcrystalline to very fine crystalline, dense, argillaceous, silty, shale streaks, scattered glauconite, pyritic in part, scattered blebs and thin interbeds of anhydrite.
- 6410 - 6420' Dolomite - medium to dark brownish grey, very fine to fine crystalline, streaky slight intercrystalline porosity, argillaceous, silty, shale streaks, glauconite & pyrite.
Proterozoic 6420' (E-Log 6428')
- 6420 - 6440' Dolomite - very light grey - brownish - greenish - pinkish in part, microcrystalline to very fine crystalline - chalky in part, streaky slight intercrystalline porosity, some scattered quartz crystals, pyritic in part, glauconitic in part, some blebs and thin streaks of anhydrite, sandy streaks, thin cherty streaks, trace of oolitic texture, some streaks of maroon and green shale.
- 6440 - 6450' Dolomite - as above; dolomite - light greyish brown, microcrystalline to very fine crystalline, dense.
- 6450 - 6470' Dolomite - very light grey to light greyish brown - some reddish streaks and patches, microcrystalline to fine crystalline, streaky, slight intercrystalline porosity, trace of oolitic texture, scattered inclusions of gypsum crystals, scattered pyrite.
- 6470 - 6490' Dolomite - as above; dolomite - medium dark brownish grey, microcrystalline to fine crystalline, dense, argillaceous, streaks of greenish grey shale, silty, sandy streaks, glauconitic, inclusions of gypsum.
- 6490 - 6520' Dolomite - greyish brown some scattered red spots and patches, microcrystalline to very fine crystalline, dense, slightly pyritic in part, some inclusions of gypsum & dolomite rhombs, some blebs of anhydrite, silty and sandy, trace of chert.
- 6520 - 6530' Dolomite - as above - increase of red patches & streaks.
- 6530 - 6590' Dolomite - greyish brown with red streaks and patches, as above.
- 6590 - 6620' Dolomite - light to medium greyish brown, a few reddish streaks microcrystalline to very fine crystalline, dense, silty, slightly cherty, some dolomite rhombs, siliceous streaks, trace of salt casts, trace of quartz crystals.
- 6620 - 6640' Dolomite - greyish brown - pink to reddish patches - some dark streaks, microcrystalline to very fine crystalline, dense, silty, trace of quartz crystals, some dolomitic rhombs lining and infilling scattered vugs, streaks of greenish grey and some maroon shale, trace of light grey anhydrite, trace of oolitic texture.

- 6640 - 6650' Dolomite - as above - fewer reddish patches.
- 6650 - 6670' Dolomite - light brownish grey to greyish brown - some reddish patches, microcrystalline to fine crystalline, dense, slightly silty, cherty - smoky to light greyish brown, some streaks of medium brownish grey dolomite with granules of glauconite. Some dolomite rhombs, some scattered pellets of medium brownish grey dolomite.
- 6670 - 6710' Dolomite - light brownish grey to greyish brown - some pink and red streaks, microcrystalline to fine crystalline, dense, slightly silty, trace of quartz crystals, some dolomite rhombs, trace of light brownish grey anhydrite, some interbedded greyish green shale, some partings of black bituminous shale.
- 6710 - 6730' Dolomite - very light grey to greyish brown - pink and red streaks and patches, microcrystalline to fine crystalline, dense, few scattered vugs partially to completely infilled with secondary dolomite, some shale streaks, trace of salt casts.
- 6730 - 6740' Dolomite - very light grey to light and dark greyish brown, some pink and red streaks, microcrystalline to fine crystalline, dense, scattered blind vugs partially to completely infilled with secondary dolomite, silty, argillaceous streaks & shale streaks, trace of anhydrite, trace of salt casts, trace of green siltstone.
- 6740 - 6840' Dolomite - very light to medium greyish brown - pink to red streaks and patches, microcrystalline to very fine crystalline, dense, silty, some secondary dolomite infilling vugs, trace of anhydrite, trace of quartz crystals, slightly cherty - greyish brown, some streaks of greyish green shale & dull grey soft shale, some thin streaks of greyish brown anhydrite, trace of salt casts, brecciated in part (along edge of infilled fractures), trace of gypsum, trace of faint pellets.
- 6840 - 6860' Dolomite - as above - trace of green siltstone, slight increase in salt casts.
- 6860 - 6870' Dolomite - very light to medium greyish brown - pink to red streaks and patches - some dark greyish brown - argillaceous streaks, microcrystalline to fine crystalline, dense, silty, secondary dolomite, streaks of anhydrite and gypsum, trace of quartz crystals.
- 6870 - 6890' Dolomite - very light buff - brown, pink and red in part, microcrystalline to fine crystalline, dense, slightly silty, secondary dolomite infilling vugs, streaks of anhydrite and gypsum, streaks of dull grey, soft shale, scattered salt casts.

- 6890 - 6910' Dolomite - light to medium greyish brown - pink to red streaks and patches - as above.
- 6910 - 6920' Dolomite - as above - granular in part with streaky slight intercrystalline porosity.
- 6920 - 6950' Dolomite - dense, as above.
- 6950 - 6960' Dolomite - very light to medium greyish brown - some dark streaks pink to red streaks and patches, microcrystalline to fine crystalline, dense, trace of oolites, some argillaceous streaks, white medium crystalline secondary dolomite rhombs infilling vugs, abundant shaly streaks - dull grey to medium dark grey and some greyish green, some salt casts, trace of anhydrite & gypsum, some scattered fractures infilled with dolomite.

F.T.D. -- 6961'

- 29

Engineer.....T.A.D. Haddow.....

- 30

Engineer.....T.A.D. Haddow.....

— 3

Engineer.....T.A.D. Haddow

CASING REPORT

- 3

Well CanDel Mobil et al Iroquois I-11 Date April 29, 1972

Type of Casing String: (surface) (intermediate) (production) (liner) (other)

Drilling Contractor Nabors Rig #8

PIPE DATA

Make of Casing Mannesmann

Type: (seamless) (welded) Size

No. of Joints

Weight 36#Grade J-55Range 3

Threads

ST & C

Couplings: (short) (long) Minimum I.D.

9-5/8"

Maximum O.D.

Casing Shoe: make type depth ft.

Cementing Collar: make type depth ft.

Centralizers: No. Make and Type

Depths

Scratchers: No. Make and Type

Depths

Welding: (electric) (acetylene) No. of Collars?

Casing Shoe?

Total amount casing run	<u>724.91</u>	ft.	Kelly Bushing elevation	<u>418</u>	ft.
Amount pipe above K.B.	<u>20.91</u>	ft.	K.B. to Rotary Table		ft.
Depth Casing Shoe landed	<u>704</u>	ft.	R.T. to Derrick Floor		ft.
Top of casing below K.B.		ft.	D.F. to Ground Level		ft.
Amount of casing in hole		ft.	Ground Level elevation	<u>400</u>	ft.
Length of Landing Joint		ft.	G.L. to (casing bowl) to (casing collar)		ft.
Length of Cut off Joint		ft.	Csg. Bowl Flange Elev.		ft.
Length of Shoe Joint overall		ft.	K.B. to top of casing		ft.

CEMENTING DATA

Time Hole Open Before Casing Started in Hole		hrs.
Casing Started in Hole	M.	Casing in M. (elapsed) hrs.
Circulating: Started	M.	Finished M. (elapsed) hrs.
Mixing Cement: Started	M.	Finished M. (elapsed) min.
Displacing: Started	M.	Plug Down <u>12:04</u> p.m. (elapsed) min.

Maximum Displacement Pressure psi. Final Pressure psi.

Plug Displaced to ft. Displacement Fluid: (mud) (water) (other)

Method of Displacement with water

Method of Cementing

Amount Cement Used 350 Sacks. Average Cement Slurry Weight lbs./gal.

Kind of Cement: (Canadian) (American) (bulk) (sack): Weight per sack lbs.

Estimated Amount Cement Returns 16 bbls. sacks. Time Cement to Set hrs.

Was Pipe Worked During Circulating? Cementing? How Long

Additives to Cement

Cementing Company B-J Service Operator Mel Moscrip

Casing Landed in hrs. Well Head Make

Remarks See summary of Well Data for information on conductor pipe.

Signed

BIT RECORD

Well: CanDel Mobil et al Iroquois I-11-67-50-129-30

Date Spudded: 2:30 a.m. April 25, 1972

Date Finished Drilling:

May 28, 1972

Bit No.	Size	Make & Type	Serial	Depth In	Depth Out	Footage	Hours	Condition
1A	8-3/4	HW OSC 3J	23593	60	127	67	7½	3-2-1
2A	8-3/4	Smith DT2	37621	127	424	307	16¼	5-2-1
3A	8-3/4	HW ODV	14702	424	750	326	25½	3-6-1
4A RR	8-3/4	Smith DT2	37621	750	819	69	5¼	
5A	12¼	Reamer	845-P	78	704	626	20½	4-8-1
6	8-3/4	HW ODV	16694	819	1010	191	10	6-5-1
7	8-3/4	HW X55R	38833	1010	2141	1131	50 3/4	8-7-1
8	8-3/4	HW RRG2BX	WF216	2141	2261	120	10	6-5-1
9 RR	8-3/4	HW RRG2BX	WF216	2261	2671	410	32½	2-3-1
10	8-3/4	HW RRG2BX	ZL998	2671	3403	732	50 3/4	7-6-1
11	8-3/4	HW RRG2BX	WF001	3403	3815	412	24 3/4	4-4-1
12	8-3/4	HW RGIX	NB121	3815	4445	630	36½	4-8-1
13	8-3/4	HW RRGIX	RT487	4445	4946	501	36½	6-8-1
14	8-3/4	HW J-88	HH341	4946	5484	538	44	6-4-1
15	8-3/4	HW RRG1	DP954	5484	5628	144	26½	6-8-1
16	8-3/4	HW X55R	37892	5628	6119	491	45	6-8-1
17	8-3/4	HW X55R	38291	6119	6285	166	26	6-8-1
18	8-3/4	HW WD7	40025	6285	6350	65	13	6-5-1
19	8-3/4	HW X55R	31208	6350	6500	150	28½	6-8-1
20	8-3/4	HW X55R	38288	6500	6923	181	22	7-8-1
21	8-3/4	HW WD7	38284	6923	6961	38	4 3/4	2-2-1

DAILY MUD RECORD

- 34

Date 1972	Depth Feet	Weight	Viscosity	Water Loss	Filter Cake	Ph.	Remarks and Additives				
		# / Gal.	Seconds	15 min. C.C.	32nds		Bapi Gel	Lost Spill	Circulation Material	Caustic Salt	Remarks & Misc
April 25	120	8.4	52				7000#				Spud at 2:30 a.m.
26	391		67				500#				
27	662		53				1000#				
28	819										Reaming surface hole
29	819										Running Csg.
30	819										W.O.C.
May 1	819										W.O.C.
2	1010	8.4	27				24#				
3	1356	8.4	28				20#				
4	1930	8.4	28				20#				
5	2222	8.4	28								
6	2373	8.4	28				8#				
7	2630	8.4	28				12#				
8	2872	8.4	28				16#				
9	3205	8.4	28				16#				
10	3403	8.4	28				20#	Fibre Seal 6 Sx.			Partial lost circulation at 3403'
11	3763	8.4	28				8#				
12	4090	8.4	28				12#				
13	4420	8.4	28					Sawdust 15 Sx.			Losing fluid to formation.
14	4686	8.4	28				4#	Sawdust 30 Sx.			
15	4946	8.4	28					(Sawdust 12 Sx (Fibre Seal 8 Sx (Quick Seal 6 Sx			
16	5214	8.4	28				4000#	(Fibre Seal 15 Sx (Quick Seal 11 Sx (Sawdust 14 Sx	300		
17	5468	8.5	32			10.5	3900#	(Sawdust 50 Sx (Cotton (Hulls 75 Sx (Quick Seal 25 Sx (Cell-O-Seal 25 Sx	100	8000	Fluid loss 10 - 12 bbls. per hour.
18	5571	9.6	31			10.5		(Cotton (Hulls 6Sx (Fibre Seal 2 Sx (Cell-O-Seal 12 Sx	100	4000	Inhibitor 10 gal. DeFoamer 7 gal.
19	5668	9.7	31			10.5		Cell-O-Seal 2 Sx	300	3600	Inhibitor 5 gal DeFoamer 2 gal.
20	5882	9.7	30		2			Cell-O-Seal 10 Sx Fibre Seal 6 Sx	250	19,000	Losing 8 bbls per hour.
21	6128	10.4	30							43,000	Inhibitor 4 gal.
22	6280	10.4	30			10.5			150	18,000	DeFoamer 2 gal.
23	6350	10.3	30							10,000	
24	6429	10.3	30						200	12,000	Inhibitor 7 gal.
25	6570	10.3	31							10,000	
26	6740	10.3	30			10.5				20,000	
27	6886	9.3	30			11.5			150		Inhibitor 5 gal.
28	6961	10.3	30			10.5					Running Logs
29	6961	10.3	30			10.5				12,000	Losing 5 bbls/h
30	6961	10.3	30			10.5		Fibre Seal 5 Sx		28,000	W.O.C.
31	6961										Running Plugs - no more additives.

DAILY PROGRESS REPORT

DATE	DEPTH		Logging	Hours on Bottom	BIT NOS.	DEVIATION SURVEY		REMARKS
	From	To				Depth	R.D.G.	
April 25	60'	120'	60'	4 3/4	1			Drilling. Started conductor hole at 6:00 p.m. April 20, 1972 drill 20" hole with bucket - ream to 24" Ran 89' of 20" conductor pipe, landed at 78' K.B. Cemented with 100 sacks Fondu cement- Finished Cementing 12:00 p.m. April 22. Drill rat hole - gravel falling in - complete rat hole and cementing around same at 12:00 midnight April 24. Spud with 8 3/4" bit at 2:30 a.m. April 25, 1972.
April 26	120'	391'	271'	17 1/4	1 & 2	120 150 240 300 350 440 530	3/4 1/2 1/2 1/2 1/4 1/2 1/8	Drilling - Trip to remove bucket tooth from bit. Trip Bit #1 - Jets plugged. Run Bit #2 - trip out - iron from bucket wedged in cones - run #2 back in
April 27	391'	662'	271'	19 3/4	2 & 3	620 650 710	3/4 3/4 1/4	Drilling
April 28	662'	819'	(D)157' (R)207'	18	4&Reamer	800	1/2	Reaming - Drill 8 3/4" pilot hole to 819' - commence reaming 8 3/4" hole to 12 1/4"
April 29		819'	(R)419'	15 1/4	Reamer			Running Casing - Reamed to 12 1/4" to depth of 704'. Start running Csg.
April 30		819'						W.O.C. Ran 9 5/8" Casing (724.91") Mannesman Grade J-55, 36#, Rge. 3 ST C, 8 rd. Landed at 704' K.B. Cemented with 350 sacks of Fondu cement. Displaced plug w/water. 16 bbls/cement returns Plug down at 12:04 p.m. April 29, 1972
May 1		819'						W.O.C. - Nipple up - drill mouse hole - gravel falling in. Pressure test blind rams, Hydril & 3 1/2" pipe rams to 1400# for 15 mins. - o.k. Drill Out - plug @ 659'. Clean to 819' K.B. Trip out for stabilizers.
May 2	819'	1010'	191'	10	4	990	1/8	Running DST #1. Drill to 1010' - testing porosity in Bear Rock
May 3	1010'	1356'	346'	16 1/4	5			Drilling. Completed DST #1 - good test.
May 4	1356'	1930'	574'	22 3/4	5	1385 1800	1 1 3/4	Drilling

DAILY PROGRESS REPORT

DATE 1972	DEPTH		Logging Depth	Hours on Bottom	BIT NOS.	DEVIATION SURVEY		REMARKS
	From	To				Depth	R.D.G.	
May 5	1930'	2222'	292'	19 1/2	5&6	2130	2 3/4	Drilling. Tripped for new bit at 2141'
May 6	2222'	2373'	151'	9 3/4	6	2300	2	Drilling. Drilled to 2261' and ran DST #2 in Running porosity Good test - drilled ahead with Bit #7
May 7	2373'	2630'	257'	22 3/4	7	2450	2	Drilling
May 8	2630'	2872'	242'	19 1/2	7 & 8	2650	1 3/4	Drilling. Tripped for new bit at 2671'
May 9	2872'	3205'	333'	19	8	2920	1 1/2	Drilling
May 10	3205'	3403'	198'	11 3/4	8	3100	1 1/2	Rig Repairs. Tripped for new bit at 3403' - slip line, repair brakes
May 11	3403'	3763'	360'	21	9	3400	1	Drilling. Partially lost circulation at 3403' - drilled 10' and regained circulation.
May 12	3763'	4090'	327'	17 3/4	9 & 10	3815	1 1/4	Drilling. Tripped for new bit at 3815'
May 13	4090'	4420'	330'	22 3/4	10	4330	1 3/4	Drilling
May 14	4420'	4686'	266'	18 3/4	10&11			Drilling - Tripped for new bit at 4445' - Losing from 10 - 20 barrels of drilling fluid to the formation.
May 15	4686'	4946'	260'	19 1/2	11 & 12	4820	1 1/2	Rig Repairs. Tripped for new bit at 4946'
May 16	4946'	5214'	268'	20 3/4	12			Drilling
May 17	5214'	5468'	254'	22 3/4	12	5360	1/4	Drilling - Fluid loss 10 - 12 bbls/hr.
May 18	5468'	5571'	103'	16 3/4	12 & 13			Drilling - Trip for new bit at 5484'
May 19	5571'	5668'	97'	18 1/2	13 & 14	5628	10	Drilling. Tripped for new bit at 5628'
May 20	5668'	5882'	214'	23 1/4	14			Drilling
May 21	5882'	6128'	246'	17	14 & 15			Drilling - Tripped for new bit at 6119'
May 22	6128'	6280'	152'	23 1/4	15			Drilling
May 23	6280'	6350'	70'	14 1/4	15 & 16	6285	2	Tripping for new bit. Tripped for new bit at 6285' and 6350'
May 24	6350'	6429'	79'	20 1/4	17			Drilling
May 25	6429'	6570'	141'	17 3/4	17 & 18			Drilling - Tripped for new bit at 6500'
May 26	6570'	6740'	170'	23 1/4	18	6500	2	Drilling
May 27	6740'	6886'	146'	17 3/4	18 & 19	6742	2 1/8	Drilling - Tripped for new bit at 6742'
May 28	6886'	6961'	75'	10	19 & 20			Running Logs. Tripped for new bit at 6923' drilled to Final Total Depth at 6961' - started logging with Dresser Atlas.
May 29		6961'	0	0				Running Logs

DAILY PROGRESS REPORT

DATE 1972	DEPTH		Footage	Hours on Bottom	BIT NOS.	DEVIATION SURVEY		REMARKS
	From	To				Depth	R.D.G.	
May 30		6961'	0	0				Waiting on Orders. Finished running logs. Losing mud at 5 bbls/hr W.O.C. Run Plug #1 6961' - 6861' & Plug #2 3600 - 3450' Running DST #3. Waited 8 hrs. on Plug #2. Felt at 3614' Polished off top. Commence DST #3 3200 - 3614' Pismantle B.O.P.'s Complete DST #3 - good test. Ran Plug #3 2150 - 2000'. Felt Plug #3 at 2010' after 8 hours. Ran Plug #4 630 - 780' Felt top of Plug #4 at 623' after 8 hours. Clean up location. Weld plate on casing. Rig Released at 12:00 noon - June 2, 1972
May 31		6961'	0	0				
June 1		6961'	0	0				
June 2		6961'	0	0				
June 3		6961'	0	0				

ABANDONMENT PLUGS

- #1 - 6961 - 6861' - 55 sacks cement, plug down at 3:00 a.m. May 31, 1972 - no feel
- #2 - 3600 - 3450' - 100 sacks cement + 3% CaCl_2 , plug down at 5:00 a.m. May 31, 1972
Felt plug at 3614' after 10 hours
- #3 - 2150 - 2000' - 100 sacks cement + 3% CaCl_2 , plug down at 11:30 a.m. June 1, 1972
Felt plug at 2010' after 8 hours
- #4 - 780 - 630' - 100 sacks + 3% CaCl_2 , plug down at 9:00 p.m., June 1, 1972
Felt plug at 623' after 8 hours
Five sacks of cement put in top of surface casing - plate welded on with name tag.

LOST CIRCULATION ZONES

Intercrystalline, vuggy and some cavernous porosity is present in the Ronning formation. Below 3400 feet the drilling fluid was being lost to the formation at the rate of approximately 10 barrels per hour. Lost circulation material was added daily to the system to hold this loss to a minimum. On two occasions circulation was lost following a trip for a new bit, this occurred at 3403 feet and 4445 feet. In both instances, circulation was regained after drilling a few feet.

SECTION IV - LOGS

Electrical Logs: by Dresser Atlas

Induction Electrolog	Run 1	May 27, 1972	704 - 6940'
Sidewall Neutron Gamma Ray	Run 1	May 28, 1972	704 - 6932'
Compensated Densilog	Run 1	May 28, 1972	704 - 6932'
BHC Acoustilog	Run 1	May 29, 1972	704 - 6924'

SECTION V - ANALYSIS

<u>Lab No.</u>	<u>Sample</u>	<u>From</u>	<u>To</u>	<u>Source</u>	<u>Remarks</u>
933-2670	Water	3200	3614	DST #3 Ronning	Water Analysis
933-2581	Water	900	1010	DST #1 Bear Rock	Water Analysis
933-2581	Water	2121	2261	DST #2 Ronning	Water Analysis

WELL HISTORY LOG

of

CANDEL MOBIL et al IROQUOIS I-11

located at

UNIT 1, SECTION 11, GRID 67-50-129-30

Latitude 67° 40' 40" Longitude 129° 32' 05"

NORTHWEST TERRITORIES, CANADA

Well Status: Dry & Abandoned

Date Spudded: April 25, 1972

Date Completed Drilling: May 28, 1972

Operator: CanDel Oil Ltd.

Geology By: T.A.D. Haddow

Elevation: Gr 400'

K.B. 418'

Total Depth: Driller 6961' Logger 6944'

Drilling Contractor: Nabor Drilling Limited

Rig No. 8

LEGEND

	SIDERITE, bedded		GYPSUM		ANHYDRITE, secondary		GRANITE WASH
	SANDSTONE		MARLSTONE, limy-dolomitic		SHALE		IGNEOUS, basic
	SILTSTONE		LIMESTONE		CLAYSTONE		IGNEOUS, acidic
	BENTONITE		DOLOMITE, primary		GLACIAL TILL		VOLCANIC
	COAL		DOLOMITE, secondary		CONGLOMERATE, i.e. 40% chert, 40% ls., etc.		METAMORPHIC
	SALT		ANHYDRITE, primary		BRECCIA		
	ARKOSIC		FLOATING SAND GRAIN		CHERT, sandy & oolitic		SIDERITE PELLETS
	ARGILLACEOUS, disseminated		SILTY		NODULES, Fe-st		GLAUCONITIC
	DOLOMITIC		SANDY		NODULES, limy		SALT CAST or INFILL
	CALCAREOUS		ARGILLITE GRAIN		NODULES, dolomitic		
	ANHYDRITIC		CHERT, light & dark		NODULES, phosphatic		
	GYPSIFEROUS		CHERT, tripolitic		NODULES, siderite		
	LITHOGRAPHIC		CRYPTOCRYSTALLINE		EARTHY		CHALKY
	KARST TOPOGRAPHY		VERY POOR SAMPLES, questionable		CAVINGS, cannot interpret		NO SAMPLES
	ALGAL, nondescript		BIOCLASTIC or FRAGMENTAL		BRYOZOA		MOLLUSKS
	ALGAL, encrusting		PSEUDO OOLITES or PELLETS		FORAMINIFERA		OSTRACODS
	ALGAL, ooloid		CORAL		CRINOID		
	ALGAL, coralline		STROMATOPOROID		OOLITES		
	MARL, limy		PYRITE		SIDERITE CEMENT		PLANT REMAINS
	MARL, dolomitic		BENTONITIC		PLANT SPORES		FISH REMAINS
	LIMESTONE STREAKS		SILICEOUS		MINERAL CRYSTALS		FOSSILS
	DOLOMITE STREAKS		SHALE, laminae		CALCITE or secondary DOLOMITE crystals		CARBONACEOUS

OIL STAIN OR RECOVERY

GAS SHOW OR RECOVERY

FLOURESCENCE

BITUMIN

FORMATION WATER RECOVERY - exponent shows ppm Cl.


FORMATION TESTS

A. BOTTOM HOLE

B. DUAL PACKERS

C. PACKER SET IN CASING

D. F.T.T. SCHLUMBERGER



WATER ANALYSES

FOR

CANDEL OIL LTD.

CANDEL MOBIL ET AL IROQUOIS F-11
IROQUOIS RIVER AREA
NORTHWEST TERRITORIES

CORE LABORATORIES - CANADA LTD.

Petroleum Reservoir Engineering

CALGARY - EDMONTON - REGINA



CORE LABORATORIES - CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS



File 933-2670 Page 2 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois I-11 K.B. Grd.
67° 40' 40.00 N.L.

Location 129° 32' 05.00 W.L. Field Iroquois River Area Province N. W. T.

Formation Ronning Interval 3200 - 3614

Sampled from DST #3 (Bottomhole Sampler) by

Date sampled May 31/72 Date analysed June 6/72 Analyst ML

Recovery 2820' liquid.

Mud type Water cushion

Total Solids:

Resistivity 0.059 Ohm-meters @ 69 °F Calculated 181,808 mg/liter

Specific gravity 1.1226 @ 60°F By evaporation @ 110°C - mg/liter

pH 11.1 H₂S Absent By evaporation @ 180°C - mg/liter

Refractive Index 1.3617 At ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
70162	1063	25	Trace	Abs.	-	-	108193	0	2167	82	116


PER CENT CALCULATED SOLIDS

38.6	.6	.0	Trace	Abs.	-	-	59.5	.0	1.2	.0	.1
------	----	----	-------	------	---	---	------	----	-----	----	----

MEQ PER LITER

3050.5	53.0	2.1	Trace	Abs.	-	-	3051.0	.0	45.1	2.7	6.8
--------	------	-----	-------	------	---	---	--------	----	------	-----	-----

LOGARITHMIC PATTERN MEQ PER LITER



181182. 70162.0



CORE LABORATORIES - CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS



File 933-2670 Page 1 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois I-11 K.B. 418 Grd. 400'
67° 40' 40.00 N.L.

Location 129° 32' 05.00 W.L. Field Iroquois River Area Province N. W. T.

Formation Ronning Interval 3450' - 3614'

Sampled from (Top #1) 0.57 #3 by _____

Date sampled May 31/72 Date analysed June 6/72 Analyst ML

Recovery 2820' liquid.

_____ Mud type _____ Water cushion _____

Total Solids:

Resistivity 0.048 Ohm-meters @ 69 °FCalculated 287,757 mg/literSpecific gravity 1.1886 @ 60°FBy evaporation @ 110°C - mg/literpH 11.4 H₂S AbsentBy evaporation @ 180°C - mg/literRefractive Index 1.3772 @ 74°FAt ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
111819	1104	25	Trace	-	-	-	171489	0	2915	58	347


PER CENT CALCULATED SOLIDS

38.9	.4	.0	Trace	-	-	-	59.6	.0	1.0	.0	.1
------	----	----	-------	---	---	---	------	----	-----	----	----

MEQ PER LITER

4861.7	55.1	2.1	Trace	-	-	-	4836.0	.0	60.6	1.9	20.4
--------	------	-----	-------	---	---	---	--------	----	------	-----	------

LOGARITHMIC PATTERN MEQ PER LITER



287673.111819.0

CORE LABORATORIES – CANADA LTD.

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSIS



File 933-2581 Page 1 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois I-11 K.B. _____ Grd. 400'
67° 40' 20.00 N.L.

Location 129° 32'05.00 W.L. Field Iroquois River Area Province N.W.T.

Formation _____ Interval 900' - 1010'

Sampled from DST #1 (BJ Tool #RS28) by BJ Testers

Date sampled _____ Date analysed May 17/72 Analyst LK

Recovery Tool Recovery: 3000 cc's Water.

Mud type _____ Water cushion _____

Total Solids:

Resistivity 3.09 Ohm-meters @ 74 °F Calculated 1,858 mg/liter

Specific gravity 1.0027 @ 60°F By evaporation @ 110°C - mg/liter

pH 9.3 H₂S Present By evaporation @ 180°C - mg/liter

Refractive Index 1.3326 @ 73°F At ignition - mg/liter

MILLIGRAMS PER LITER

Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
695	3	1	Trace	-	-	-	832	210	31	86	Nil


PER CENT CALCULATED SOLIDS

37.4	.2	.1	Trace	-	-	-	44.8	11.3	1.7	4.6	.0
------	----	----	-------	---	---	---	------	------	-----	-----	----

MEQ PER LITER

30.2	.1	.1	Trace	-	-	-	23.5	3.4	.6	2.9	.0
------	----	----	-------	---	---	---	------	-----	----	-----	----

LOGARITHMIC PATTERN MEQ PER LITER



**CORE LABORATORIES — CANADA LTD.**

PETROLEUM RESERVOIR ENGINEERING

WATER ANALYSISFile 933-2581 Page 2 of 2

Company CanDel Oil Ltd.

Well CanDel Mobil et al Iroquois I-11 K.B. Grd. 400'
67° 40'20.00 N.L.

Location 129° 32'05.00 W.L. Field Iroquois River Area Province N.W.T.

Formation Interval 2121' - 2261'

Sampled from DST #2 (JB Tool #124) by

Date sampled Date analysed May 17/72 Analyst LK

Recovery Tool Recovery: 3000 cc's Water.

 Mud type Water cushion

Total Solids:

Resistivity 1.21 Ohm-meters @ 75 °F Calculated 4,969 mg/liter

Specific gravity 1.0046 @ 60°F By evaporation @ 110°C - mg/liter

pH 7.9 H₂S Present By evaporation @ 180°C - mg/liter

Refractive Index 1.3334 @ 73°F At ignition - mg/liter

MILLIGRAMS PER LITER


Na + K	Ca	Mg	Fe	Ba	Br	I	Cl	HCO ₃	SO ₄	CO ₃	OH
1442	209	112	Trace	Abs.	-	-	2399	488	319	Nil	Nil

PER CENT CALCULATED SOLIDS

29.0	4.2	2.3	Trace	Abs.	-	-	48.3	9.8	6.4	.0	.0
------	-----	-----	-------	------	---	---	------	-----	-----	----	----

MEQ PER LITER

62.7	10.4	9.2	Trace	Abs.	-	-	67.7	8.0	6.6	.0	.0
------	------	-----	-------	------	---	---	------	-----	-----	----	----

LOGARITHMIC PATTERN MEQ PER LITER

4556. 1442.0