

**MGM et al Windy Island J-39**  
"As Built" Abandonment

UWI 300J396500125300  
WID 2072

Well Sign

6mm welded steel plates  
178mm casing sealed  
244mm annulus sealed  
10 m cement plug  
on rag plug@ 40KB

Top of casing -1m GL  
29m air space in 178mm & 9m in 178/244mm annulus  
Top of cement 30mKB (25mGL)

406mm Conductor  
-13m GL

Cemented full length  
244mm shoe  
407mKB

178mm 38.7 & 47.6 kg/m L-80 casing  
Filled with inhibited water  
0.6% Baker CRW 132

Cemented full length

1281m PBD (approx)  
1292m 178mm casing shoe  
1300m TD

